#### ECOLOGICAL STUDY

## MERRIMACK RIVER ESTUARY - MASSACHUSETTS

Presented to the

U. S. ARMY, CORPS OF ENGINEERS

1971

In compliance with

CONTRACT NO.: DACW33-71-C-0077

PROJECT NO.: NEDSD-P-6

Prepared by:

Bruce Miller
Donald A. Normandeau
Glenn Piehler
Pamela Hall
Arthur Mathieson
Richard Fralick
Donna Turgeon
Philip Mahoney

NORMANDEAU ASSOCIATES, INC. Manchester, New Hampshire

and

Wadsworth Owen

VAST, Inc. Hartford, Connecticut

## ECOLOGICAL STUDY

# MERRIMACK RIVER ESTUARY - MASSACHUSETTS

## TABLE OF CONTENTS

# Section I. GENERAL INTRODUCTION TO THE STUDY

I-2.

A. THE PROBLEM

в.	SCOPE OF THE PROJECT	I-4.
	Section II. DESCRIPTION OF THE STUDY AREA	
	Section III. SALINITY STUDY, MERRIMACK RIVER ESTUARY	
	MATHEMATICAL MODEL	
Α.	INTRODUCTION AND OBJECTIVES	III-2.
В.	APPROACH	III-3.
	<ol> <li>Problem Statement</li> <li>Review of Applicable Models</li> <li>Model Selection</li> </ol>	III-4. III-4. III-6.
c.	DESCRIPTION OF THE MODEL AND THE METHOD OF SOLUTION	III <b>-</b> 7.
	<ol> <li>Derivation</li> <li>Finite Difference Form</li> <li>Diffusion Coefficients</li> <li>Solution</li> <li>Testing and Evaluation</li> <li>Principal Limitations</li> </ol>	III-8. III-12. III-14. III-21. III-22. III-26.
D.	RESULTS	III-27 <b>.</b>
	3 A	III-27. III-29. III-32.

## Section IV. POTENTIAL EFFECTS OF DIVERSION ON THE

## PHYSICAL CHARACTERISTICS OF THE ESTUARY

2. Net Inflow of Bottom Sediments Resulting from Changes in Current Flow  IV-29.  E. UPPER ESTUARINE TEMPERATURE CHANGES  F. CHANGES IN THE EFFECT OF POLLUTION LOAD  IV-33.  Section V. POTENIAL BIOLOGICAL CHANGES RESULTING  FROM DIVERSION  A. INTRODUCTION  B. INTERTIDAL BENTHIC ORGANISMS  V-5.  1. Rationale and Objectives 2. Description of Stations 3. Intertidal Algae and Vascular Plants 4. Intertidal Invertebrates  V-37.  C. SUBTIDAL BENTHIC INVERTEBRATES  V-50.  1. Methods 2. General Results 3. Analyses According to Sampling Station V-59.  D. PLANKTON  V-62.  1. Methods 2. Results 3. Existing Composition and Distribution of Plankton V-73.	Α.	INTRODUCTION	IV-2.			
D. PHYSICAL CHANGES RESULTING FROM ALTERATIONS OR CIRCULATION IV-28.  1. Alterations in Suspended Sediment Distribution 2. Net Inflow of Bottom Sediments Resulting from Changes in Current Flow IV-29.  E. UPPER ESTUARINE TEMPERATURE CHANGES IV-32.  F. CHANGES IN THE EFFECT OF POLLUTION LOAD IV-33.  Section V. POTENIAL BIOLOGICAL CHANGES RESULTING  FROM DIVERSION  A. INTRODUCTION V-2.  B. INTERTIDAL BENTHIC ORGANISMS V-5.  1. Rationale and Objectives V-5. 2. Description of Stations V-6. 3. Intertidal Algae and Vascular Plants V-13. 4. Intertidal Invertebrates V-37.  C. SUBTIDAL BENTHIC INVERTEBRATES V-50.  1. Methods V-52. 2. General Results V-52. 3. Analyses According to Sampling Station V-55. 4. Discussion V-62.  D. PLANKTON V-62.  1. Methods V-62. 2. Results V-63. 3. Existing Composition and Distribution of Plankton V-73.	в.	LONGITUDINAL CHANGES IN SALINITY DISTRIBUTION	IV-3.			
IV-28.  1. Alterations in Suspended Sediment Distribution 2. Net Inflow of Bottom Sediments Resulting from Changes in Current Flow  IV-29.  E. UPPER ESTUARINE TEMPERATURE CHANGES  F. CHANGES IN THE EFFECT OF POLLUTION LOAD  Section V. POTENIAL BIOLOGICAL CHANGES RESULTING  FROM DIVERSION  A. INTRODUCTION  V-2.  B. INTERTIDAL BENTHIC ORGANISMS  1. Rationale and Objectives 2. Description of Stations 3. Intertidal Algae and Vascular Plants 4. Intertidal Invertebrates  V-50.  C. SUBTIDAL BENTHIC INVERTEBRATES  1. Methods 2. General Results 3. Analyses According to Sampling Station 4. Discussion  V-62.  P. PLANKTON  V-62.  1. Methods 2. Results 3. Existing Composition and Distribution of Plankton  V-73.	c.	ALTERATIONS OF ESTUARINE CIRCULATION				
2. Net Inflow of Bottom Sediments Resulting from Changes in Current Flow IV-29.  E. UPPER ESTUARINE TEMPERATURE CHANGES IV-32.  F. CHANGES IN THE EFFECT OF POLLUTION LOAD IV-33.  Section V. POTENIAL BIOLOGICAL CHANGES RESULTING  FROM DIVERSION  A. INTRODUCTION V-2.  B. INTERTIDAL BENTHIC ORGANISMS V-5.  1. Rationale and Objectives V-5. 2. Description of Stations V-6. 3. Intertidal Algae and Vascular Plants V-13. 4. Intertidal Invertebrates V-37.  C. SUBTIDAL BENTHIC INVERTEBRATES V-50.  1. Methods V-52. 3. Analyses According to Sampling Station V-55. 4. Discussion V-59.  D. PLANKTON V-62.  1. Methods V-62. 2. Results V-63. 3. Existing Composition and Distribution of Plankton V-73.	D.					
E. UPPER ESTUARINE TEMPERATURE CHANGES  F. CHANGES IN THE EFFECT OF POLLUTION LOAD  Section V. POTENIAL BIOLOGICAL CHANGES RESULTING  FROM DIVERSION  A. INTRODUCTION  B. INTERTIDAL BENTHIC ORGANISMS  V-5.  1. Rationale and Objectives 2. Description of Stations 3. Intertidal Algae and Vascular Plants 4. Intertidal Invertebrates  V-50.  C. SUBTIDAL BENTHIC INVERTEBRATES  V-50.  1. Methods 2. General Results 3. Analyses According to Sampling Station V-59.  D. PLANKTON  V-62.  Results V-63. 3. Existing Composition and Distribution of Plankton V-73.		2. Net Inflow of Bottom Sediments Resulting from	IV-28.			
Section V. POTENIAL BIOLOGICAL CHANGES RESULTING  FROM DIVERSION  A. INTRODUCTION V-2.  B. INTERTIDAL BENTHIC ORGANISMS V-5.  1. Rationale and Objectives V-5.  2. Description of Stations V-6.  3. Intertidal Algae and Vascular Plants V-13.  4. Intertidal Invertebrates V-37.  C. SUBTIDAL BENTHIC INVERTEBRATES V-50.  1. Methods V-52. 2. General Results V-52. 3. Analyses According to Sampling Station V-55. 4. Discussion V-59.  D. PLANKTON V-62.  1. Methods V-62. 2. Results V-63. 3. Existing Composition and Distribution of Plankton V-73.	Ε.		IV-32.			
A. INTRODUCTION V-2.  B. INTERTIDAL BENTHIC ORGANISMS V-5.  1. Rationale and Objectives V-5. 2. Description of Stations V-6. 3. Intertidal Algae and Vascular Plants V-13. 4. Intertidal Invertebrates V-37.  C. SUBTIDAL BENTHIC INVERTEBRATES V-50.  1. Methods V-52. 2. General Results V-52. 3. Analyses According to Sampling Station V-55. 4. Discussion V-59.  D. PLANKTON V-62.  1. Methods V-62. 2. Results V-63. 3. Existing Composition and Distribution of Plankton V-73.	F.	CHANGES IN THE EFFECT OF POLLUTION LOAD	IV-33.			
A. INTRODUCTION V-2.  B. INTERTIDAL BENTHIC ORGANISMS V-5.  1. Rationale and Objectives V-5. 2. Description of Stations V-6. 3. Intertidal Algae and Vascular Plants V-13. 4. Intertidal Invertebrates V-37.  C. SUBTIDAL BENTHIC INVERTEBRATES V-50.  1. Methods V-52. 2. General Results V-52. 3. Analyses According to Sampling Station V-55. 4. Discussion V-59.  D. PLANKTON V-62.  1. Methods V-62. 2. Results V-63. 3. Existing Composition and Distribution of Plankton V-73.		Section V. POTENIAL BIOLOGICAL CHANGES RESULTING				
B. INTERTIDAL BENTHIC ORGANISMS  1. Rationale and Objectives 2. Description of Stations 3. Intertidal Algae and Vascular Plants 4. Intertidal Invertebrates  V-37.  C. SUBTIDAL BENTHIC INVERTEBRATES  1. Methods 2. General Results 3. Analyses According to Sampling Station 4. Discussion  V-62.  PLANKTON  V-62.  1. Methods 2. Results 3. Existing Composition and Distribution of Plankton V-73.		FROM DIVERSION				
1. Rationale and Objectives V-5. 2. Description of Stations V-6. 3. Intertidal Algae and Vascular Plants V-13. 4. Intertidal Invertebrates V-37.  C. SUBTIDAL BENTHIC INVERTEBRATES V-50.  1. Methods V-52. 2. General Results V-52. 3. Analyses According to Sampling Station V-55. 4. Discussion V-59.  D. PLANKTON V-62.  1. Methods V-62. 2. Results V-63. 3. Existing Composition and Distribution of Plankton V-73.	Α.	INTRODUCTION	V-2.			
2. Description of Stations 3. Intertidal Algae and Vascular Plants 4. Intertidal Invertebrates  V-37.  C. SUBTIDAL BENTHIC INVERTEBRATES  V-50.  1. Methods 2. General Results 3. Analyses According to Sampling Station V-55. 4. Discussion  V-62.  PLANKTON  V-62.  1. Methods 2. Results 3. Existing Composition and Distribution of Plankton V-73.	в.	INTERTIDAL BENTHIC ORGANISMS	V-5.			
1. Methods V-52. 2. General Results V-52. 3. Analyses According to Sampling Station V-55. 4. Discussion V-59.  D. PLANKTON V-62.  1. Methods V-62. 2. Results V-63. 3. Existing Composition and Distribution of Plankton V-73.		<ol> <li>Description of Stations</li> <li>Intertidal Algae and Vascular Plants</li> </ol>				
2. General Results 3. Analyses According to Sampling Station 4. Discussion  V-59.  D. PLANKTON  V-62.  1. Methods 2. Results 3. Existing Composition and Distribution of Plankton  V-73.	c.	SUBTIDAL BENTHIC INVERTEBRATES	V-50.			
<ol> <li>Methods</li> <li>Results</li> <li>Existing Composition and Distribution of Plankton V-73.</li> </ol>		<ol> <li>General Results</li> <li>Analyses According to Sampling Station</li> </ol>	V-52. V-52. V-55. V-59.			
<ol> <li>Results V-63.</li> <li>Existing Composition and Distribution of Plankton V-73.</li> </ol>	D.	PLANKTON	V-62.			
za riviecteu changes as a resuit di Diversion (27):		2. Results	V-62. V-63. V-73.			

Ε.	COMMERC	IALLY IMPORTANT INVERTEBRATES	v-78.
	1. 2.	The Soft-Shell Clam, Mya arenaria The American Lobster, Homarus americanus	v-78. v-89.
	3.	Crabs	V-89.
	٥.	CI abs	v-09.
F.	FINFISH		V-90.
	1.	Present Distribution and Relative Abundance of Finfish in the Merrimack River Estuary	v-90.
	2.	Potential Effects of Salinity Change on the Abundant Finfish Species, and on Species of Sport and Commercial Importance	V-93.
		a. The Sand Lance, Ammodytes americanus	V-94.
		b. The Striped bass, Roccus saxatilis	V-97.
		c. The Atlantic Salmon, Salmo salar	v-101.
		d. The Shad, Alosa sapidissima	V-107.
		e. The Alewife, Alosa pseudoharengus	V-110.
		f. The Blueback Herring, Pomobolus aestivalis	V-113.
		g. The Atlantic Mackerel, <u>Scomber scombrus</u> h. The Winter Flounder, <u>Pseudopleuronectes</u>	V-113.
		americanus	V-115.
		i. The American Eel, Anguilla rostrata	V-115.
PAR		tion VI. POTENTIAL EFFECTS OF DIVERSION ON THE	REFUGE
	<u> </u>	Section VII. CONCLUSIONS AND RECOMMENDATIONS	
Α.	SUMMARY	OF MAJOR ELEMENTS STUDIED	VII-2.
	1.	Salinity Study - Mathematical Model	VII-2.
	2.	Potential Effects of Diversion on the Physical	A T T - Z .
		Characteristics of the Estuary	VII-3.
	3.	Potential Biological Changes Resulting From	*** **
		Diversion	VII-7.
	4.	Potential Effects of Diversion on the Parker	*** / *
		River Estuary and the Parker River National	
		Wildlife Refuge	VTT-18

C.	RECOMMENDATIONS	
	Section VIII. LITERATURE CITED	
	APPENDICES	
A. B.	HIGH TIDE SALINITY DISTRIBUTIONS LOW TIDE SALINITY DISTRIBUTIONS	3. 28.
C.	AVERAGE WEEKLY FLOW RATES 1927-1967	54.

VII-18.

B. CONCLUSIONS

## LIST OF FIGURES

FIGURE NO.		SECTION/PAGE
1.	THE MERRIMACK RIVER ESTUARY	II-3.
2.	MERRIMACK RIVER - AVERAGE WEEKLY FLOW RATE (ft <sup>3</sup> /sec.)	III-15.
3.	MERRIMACK RIVER CROSS-SECTIONS (ft <sup>2</sup> )	III-17.
4.	SALINITY OF MOUTH OF MERRIMACK RIVER FOR VARIOUS FLOW RATES	III-20.
5a-c	COMPARISON OF OBSERVED AND CALCULATED SALINITY DISTRIBUTIONS IN THE MERRIMACK RIVER	/ III-23.
6.	SALINITY STATION KEY	III-31.
7a.	COMPARATIVE EFFECTS OF SEVERAL DIVERSION RATES ON THE SEASONAL FLOW PATTERN IN THE MERRIMACK RIVER	IV-5.
7b-m	EFFECTS OF VARIOUS DIVERSIONS ON THE HYDROGRAF FOR AVERAGE, HIGH, AND DRY YEARS (1943, 1951, and 1965)	PHS
8.	AVERAGE LONGITUDINAL INTRUSION OF WATERS OF 5 $^{\rm O}/_{\rm OO}$ AT DIFFERENT RATES OF DIVERSION DURING HIGH TIDE	IV-21.
9.	AVERAGE LONGITUDINAL INTRUSION OF WATERS OF 5 O/OO AT DIFFERENT RATES OF DIVERSION DURING HIGH TIDE	IV-22.
10.	AVERAGE LONGITUDINAL INTRUSION OF WATERS OF 5 O/OO AT DIFFERENT RATES OF DIVERSION DURING HIGH TIDE	IV-23.
11.	LOCATION OF INTERTIDAL SAMPLING STATIONS - MERRIMACK RIVER ESTUARY	V-14.
12.	THE DISTRIBUTION OF SELECTED INTERTIDAL VASCULAR PLANTS OCCURRING ALONG THE MERRIMACK RIVER ESTUARY, MASSACHUSETTS, 1971.	
13.	LOCATION OF SUBTIDAL BENTHIC SAMPLING STATIONS MERRIMACK RIVER ESTUARY	v-51.

FIGURE NO. SECTION/PAGE

LOCATION OF PLANKTON SAMPLING STATIONS - MERRIMACK RIVER ESTUARY	V-64.
SOFT-SHELL CLAM FLATS OF THE MERRIMACK RIVER ESTUARY -	V-80.
LOCATION OF SEINING STATIONS (Adapted from Jerome, et al, 1965) MERRIMACK RIVER ESTUARY	V-91.

## LIST OF TABLES

I.	COEFFICIENTS FOR K - MERRIMACK RIVER	III-19.
II.	DIVERSION INDEX	III-28.
III.	SALINITY STATION AND HALF-KILOMETER GRID POINT KEY	III-30.
IV.	FLOWS IN CFS WHICH WERE EXCEEDED IN A GIVEN PERCENT OF TIME DURING THE PERIOD OF RECORD (1927-1968)	IV-19.
٧.	NUMBER OF TIMES RIVER DISCHARGE WAS AT OR NEAR DESTRATIFICATION LEVELS (1923-1968)	IV-27.
VI.	A DESCRIPTION OF THE INTERTIDAL COLLECTING STATIONS STUDIED IN THE MERRIMACK RIVER ESTUARY	v- 7.
vII.	VASCULAR PLANTS OF THE MERRIMACK RIVER ESTUARY AND THEIR ESTUARINE DISTRIBUTION	V-15.
VIII.	SPECIES COMPOSITION AND DISTRIBUTION OF CONSPICUOUS VASCULAR PLANTS OCCURING IN THE TIDAL REACHES OF THE MERRIMACK RIVER ESTUARY.	V-19.
IX.	LIST OF THE ALGAL SPECIES OF THE MERRIMACK RIVER ESTUARY, THEIR LONGEVITY AND DISTRIBUTION	V-23.
Х.	SPECIES COMPOSITION AND DISTRIBUTION OF CONSPICU- OUS INTERTIDAL ALGAE IN THE MERRIMACK RIVER ESTUARY	V-26.
XI.	SPECIES COMPOSITION AND DISTRIBUTION OF CONSPICU- OUS INTERTIDAL INVERTEBRATES IN THE MERRIMACK RIVER ESTUARY - 1971.	V-38.
XII.	BENTHIC STATION DESCRIPTIONS	V-53.
XIII.	PREDOMINANT BOTTOM SEDIMENT CHARACTERISTICS AT BENTHIC STATIONS	V-54.
XIV.	DISTRIBUTION AND ABUNDANCE OF SUBTIDAL BENTHIC ANIMALS	V-56.

1W•	SEASONAL DISTRIBUTION OF PLANKTON IN THE MERRIMACK RIVER ESTUARY, 1971	V-65.
XVI.	DOMINANT PLANKTON AT EACH SAMPLING STATION DURING SPRING	V-71.
XVII.	DOMINANT PLANKTON AT EACH SAMPLING STATION DURING FALL.	V-72.
XVIII.	SURVEY OF 1964 MERRIMACK RIVER ESTUARY FISH SURVEY (Condensed from Jerome, et al, 1965) - TOTAL NUMBER OF SPECIMENS CAPTURED PER THREE MONTHS, RANKED BY ABUNDANCE AT EACH STATION.	V-92

## ECOLOGICAL STUDY

MERRIMACK RIVER ESTUARY - MASSACHUSETTS

I. GENERAL INTRODUCTION TO THE STUDY

#### ECOLOGICAL STUDY

## MERRIMACK RIVER ESTUARY - MASSACHUSETTS

#### I. GENERAL INTRODUCTION TO THE STUDY

#### A. THE PROBLEM:

population is growing at a steady rate throughout the already crowded northeast, and with this increase comes the critical problem of how to best plan for and provide the basic services needed to improve or at least sustain the present standard of living. Of all the crises facing the region, water shortage may be one of the more critical, for water resources now existent in the vicinity of eastern Massachusetts will not be sufficient to meet the needs of the population projected for the next twenty years. This problem can be solved by reducing the overall demand for water by limiting the population to the natural carrying capacity of the watershed area, by reduction of per capita consumption, or by diverting water from adjacent watersheds to augment the existing supply. In the immediate absence of an acceptable method of population limitation or per capita consumption reduction, water may have to be diverted to meet the projected demand.

The North Atlantic Division of the Army Corps of Engineers has the responsibility of alleviating water needs in this region, and to fulfill this responsibility the Corps has considered three plans to augment the existing water supply. One plan, initiating a diversion

of water from the Connecticut River into Quabbin Reservoir in Massachusetts, has already been accepted by the Commonwealth of Massachusetts. The second, the Tully diversion, is in the initial planning stage, and a third plan, still in the formative stage, involves a diversion of water from the Merrimack River. The Merrimack River Estuary Ecological Study has been designed to determine the potential environmental effects of diversion of water from the river in the vicinity of Lowell, Massachusetts, and to give a qualitative evaluation of the significance of these effects to the ecology of the estuary and associated wetlands.

Relatively little work has previously been done on the ecology of the estuary, and the present study, of less than nine months duration, has only covered limited aspects of the estuarine environment. Implicit in a study of this scope and duration is the understanding that quantitative data are not available, and definitive answers cannot be presented at its conclusion. However, the study will serve to clarify many aspects of the existing ecology of the estuary, and will point out the potential areas of change that a diversion may impose upon the estuarine environment. If the diversion appears to be feasible, the questions of critical concern will necessarily have to be studied in further detail before the plan can be implemented.

#### B. SCOPE OF THE PROJECT

The Merrimack River Estuary Ecological Study has been designed to determine whether diversion of Merrimack River water from the vicinity of Lowell, Massachusetts, to the Eastern Massachusetts region for water supply purposes would significantly alter the ecological, biological, and physical characteristics of the Merrimack River Estuary. This determination has been made on the basis of field investigations, existing literature, and other available information, and has been supported by an analysis of the effects of simulated flow diversions upon the historic period of record.

The diversions are being considered from two viewpoints. First, a direct diversion of flow from the river utilizing "natural" flows. The wide range of diversion rates that has been selected is intended to gather the widest information band possible with respect to potential diversions. None of the flow rates have been selected nor is it anticipated that higher rates would, in fact, be adopted.

The following diversion rates (100, 300, 500, 800, 1,100, 1,500, and 2,000 cfs) were evaluated for their possible effects on the estuary, when the average daily flows, as measured at the U. S. Geological Survey gauging station at Lowell on the Merrimack River, exceed the following control flows:\*

October-May	800	cfs
June	1,000	cfs
July	1,500	cfs
August	1,500	cfs
September	1,000	cfs

<sup>\*</sup>Diversions will not cause river flows to be less than the control flows.

Secondly, diversions were evaluated with a provision for upstream storage and flow augmentation release during low flow periods. The effect of this storage is reflected in the analysis primarily during the spring and summer periods. During the spring period only (March, April, and May) the diversion rates given in the preceding section are increased as follows:

105	1	100)	0 050	,	
192	(vs.	100)	2,850	(vs.	1,100)
610	(vs.	300)	5,170	(vs.	1,500)
1,070	(vs.	500)	8,050	(vs.	2,000)
1,860	(vs.	800)			

During low flow periods this storage would be released to "make up" the difference between desired withdrawals, control flow, and natural flows conditions. Thus, no effect would be recorded on salinity beyond the spring period.

The study was composed of two major parts. The first pertains to possible physical changes in the estuary, primarily salinity, brought about by diversion. The second relates to the biotic communities, permanent and temporary, occurring in the estuary, and the potential effects the diversion might have upon them.

A mathematical model to graphically represent the longitudinal salinity distributions predicted for each incremental change in freshwater flow of the Merrimack River throughout the year was generated by Vast, Inc. of Hartford, Connecticut. Data used in the preparation of this model consisted of existing data on salinity and river flow,

augmented with data collected from April through September, 1971 by Normandeau Associates at the Merrimack River stations established by Jerome, et al (1965), and three additional stations located upriver. This description includes an analysis of the present and projected salinities at the eight sampling stations. In addition to the salinity data collected for inclusion into the mathematical model, additional salinity readings have been collected by Normandeau Associates throughout the sampling period.

Potential effects of physico-chemical changes other than salinity have also been considered, including changes in the pattern of sedimentation, alterations of current flow, reduction in temperature extremes, changes in transparency, pollution load, and BOD.

The evaluation of physico-chemical changes related to diversion, along with the results of a series of biological samplings taken throughout the study period, have been used to explore the potential effects of freshwater diversion on the biology and ecology of the estuary. Throughout the project period, studies have been conducted at 39 sampling stations to determine the existing distribution and relative abundance of six major groups of organisms along the length of the tidal estuary (i.e., intertidal benthos, subtidal benthos, plankton, finfish, intertidal algae, and intertidal vascular plants). The results of these studies have been utilized in an attempt to answer

## the following questions:

- 1. What is the existing distribution of species? Are these species marine, estuarine or freshwater?
- What are the dominant species in the biological association at each station?
- 3. What part of the life cycle of each species will be most affected by the potential physico-chemical changes? At what time of the year is this situation most critical?
- 4. How will the biological association change with potential physico-chemical changes?
- 5. Will the change in the biological association at each station lead to other biological or physical changes?
- 6. Will new species be introduced at some stations with changes in physico-chemical factors? Will some species be eliminated?
- 7. What will be the net effect of potential physico-chemical changes on the ecology of the Merrimack River Estuary?

In conclusion, an attempt has been made to determine the effects that are potentially of greatest significance to the overall stability of the estuarine environment, and approaches are suggested to study these effects in greater detail if the diversion plan is to be pursued further.

## ECOLOGICAL STUDY

MERRIMACK RIVER ESTUARY - MASSACHUSETTS

II. DESCRIPTION OF THE STUDY AREA


#### II. DESCRIPTION OF THE STUDY AREA

The Merrimack River is one of the five largest in New England, draining an area of approximately 12,970 Km<sup>2</sup>. The river has its source in the New Hampshire White Mountains, and flows in a generally southerly direction to the sea in northeastern Massachusetts. A considerable portion of the river is subject to tidal action, and measureable salt intrusion periodically occurs more than ten miles from the sea. For the purpose of the present report, the estuarine study area includes those portions of the tidal river presently or potentially exposed to measureable salt intrusion (Figure 1).

The channel of the estuary is continually scoured by tidal currents and the sediment is coarse, whereas shallow intertidal areas are covered by fine mud, silt, and sludge from domestic and industrial pollution and natural siltation. Some rock outcroppings are present along the length of the estuary, but for the most part the region is characterized by extensive salt marshland nearest to the ocean, and low deciduous and pine forest further upriver.

A complete description of the hydrography of the Merrimack River Estuary, along with a list of references pertinent to the area, was pub- $\frac{1}{1}$  Km = 0.621 mile

II-2.



## II-4.

lished by Hartwell (1970), and a detailed analysis of the marine resources of the region was written by Jerome, et al (1965).

#### ECOLOGICAL STUDY

MERRIMACK RIVER ESTUARY - MASSACHUSETTS

III. SALINITY STUDY, MERRIMACK RIVER ESTUARY

MATHEMATICAL MODEL

# III. SALINITY STUDY, MERRIMACK RIVER ESTUARY MATHEMATICAL MODEL

#### A. INTRODUCTION AND OBJECTIVES

The objective of the Ecological Study of the Merrimack River Estuary is to determine if diversion of river water before it enters the estuarine section of the river basin would significantly change the physical or ecological character of the estuary.

Normandeau Associates, Inc., an ecological consulting firm, was given the overall responsibility for the performance of the ecological survey. VAST, Incorporated, under subcontract to Normandeau Associates, was given the task of developing a one-dimensional mathematical model of the Merrimack Estuary to determine the effects of various amounts of diversion on the salinity characteristics of the estuary.

An estuary may be defined as a semi-enclosed coastal body of water in which sea water is diluted by freshwater runoff from the land (Pritchard, 1959). Estuaries are usually subject to tidal action which is often the most readily apparent water motion. More subtle in nature and yet in many ways more important is the net non-tidal circulation brought about by pressure forces set up by the variations in density due to dilution of sea water by the less dense freshwater runoff from the land. This

circulation governs and establishes the flushing characteristics of the estuary and together with other factors the limit of saltwater intrusion in the estuary. The saltwater intrusion limits are of major importance to the ecology of the Merrimack and give rise to the need for the mathematical model.

The mathematical model used in this study is based on the salt balance equation of Pritchard (1959) in which the seaward salt advection is balanced by turbulent diffusion toward the head of the river. Data from actual measurements made by previous researchers on the river and also by Normandeau Associates have been used to determine the diffusion coefficients and boundary conditions for the partial differential equation used in the model. Once these coefficients and boundary conditions are determined the equation can be used to predict the effects of future diversions on the salinity and on the limit of salt intrusion which is important to the ecology of the Merrimack River. Thus the results of the VAST mathematical model study will provide information necessary for the ecologists to assess the ecological impact of diversion on the Merrimack River Estuary.

#### B. APPROACH

The approach used in this study of the salinity of the Merrimack River Estuary has been to clearly state the problem, evaluate the possible methods of solution of the stated problem, select the method most

consistent with the available data to solve the problem, and to devise an efficient method, in terms of user time, of presenting the solution.

#### 1. Problem Statement

The problem to be solved is: Generate a mathematical model to describe the effects of proposed diversion of freshwater from the Merrimack River Basin on the limit of saltwater intrusion and on the salinity of fixed stations in the Merrimack.

#### 2. Review of Applicable Models

The most elementary model of an estuary is an embayment in which complete, instantaneous mixing is assumed for each tidal cycle. This model may have some elementary application for bar-built estuaries, however, its greatest value is in its conceptual use in the development of more realistic models such as the segmented model. The next step in increasing complexity and realism is the segmented model in which each segment is completely mixed, conservation equations are used and exchange factors are developed for each segment. In this type of model Ketchum (1950) has taken the extent of the tidal excursion for the length of the segments.

Dorrestein (1960) developed a model for the Ems estuary in which he considered the exchange coefficients to be functions only of the position within the estuary, and apparently obtained good agreement

between predicted and observed values of tracer concentration for a given river flow. Another example of a segmented model is Thomann's which Hetling (1968) applied to the Potomac Estuary. Using observed boundary conditions and diffusion coefficients determined empirically, partly from observed salinity distributions and partly from dye studies, Hetling used the model to study the effect of increased diversion of freshwater to supply the Washington, D. C. metropolitan region.

An approach that presents an attractive alternative to the segmented box model involves the direct use of a one-dimensional form of the salt balance equation. Pritchard (1959) numerically integrated a time-dependent, one-dimensional salt balance equation in application to the Delaware Estuary. The diffusion coefficients were determined from measurements made on the Delaware hydraulic model at Vicksburg, Mississippi, and boundary conditions were fixed at both ends of the estuary. Boicourt (1969) added a time varying boundary condition to Pritchard's model and applied it to the Upper Chesapeake Bay. Boicourt was able to predict the salinity distribution in the Upper Chesapeake Bay for a given freshwater inflow from the Susquehanna River. Boicourt used one year's salinity data to determine the functional dependence of the coefficient on the freshwater inflow. The boundary value at the head of the estuary was held fixed, while the seaward boundary value was allowed to vary with time. A separate predictor model related this value to the flow of the Susquehanna.

## 3. Model Selection

After a detailed review of the available models, a model based on the salt balance equation of Pritchard (1959) was selected for the Merrimack River Study. A time varying boundary conditions was added to the model following the method of Boicourt (1969). This model is the most realistic (and complex) that is compatible with the available data. A more complex model would require much more detailed measurement in time and in space. In our opinion, the additional cost in both time and money to obtain the additional data and to implement a more complex model would not be justified for the present purpose. ticular model had also been used to test the effects of diversion of water from the Susquehanna Basin through the Delaware Canal with measurable success, providing further confidence for this approach. Further, it appeared that the frontal salinity distribution in the Upper Chesapeake Bay is similar in many respects to the frontal salinity distribution in the Merrimack Estuary. Thus, it appeared that the longitudinal advection and the turbulent diffusion terms on which the salt balance equation is based would have a similar importance in the Merrimack, as in the Upper Chesapeake Bay. In the Upper Chesapeake Bay the variation of cross-section area with the tide is not great and the assumption is made that the cross-section area does not change as a function of the tide. However, it is not possible to make this assumption in the

Merrimack where the range of the tides measurably affects the crosssection area. To solve this problem the model of the Merrimack is actually two models, one for high tide and one for low tide. In summary,
the salt balance equation of Pritchard in modified form as discussed
above was selected for the Merrimack River Study because it appears
to be the most realistic model compatible with the available input data.

## C. DESCRIPTION OF THE MODEL AND THE METHOD OF SOLUTION

In modeling geophysical phenomena, one is usually faced with two practical restrictions on the detail and the complexity of the describing equations. The first requirement is that the model be mathematically tractable. The second is that the equations use and predict information that relates to available observational data.

A common method for simplifying the equations used in describing an estuary is to integrate in the direction of least variation in tracer property or in the direction in which the variation is of least interest.

The direction of most importance in the Merrimack is the longitudinal direction since this is the direction of the salt intrusion.

Therefore, the longitudinal axis was selected for this one dimensional model based on the salt continuity equation in which the seaward salt advection is balanced by turbulent diffusion toward the head of the estuary. Since the interest is in the effects of net non-tidal circulation, the

governing equation has been averaged over the tidal cycle. In final form, it is a linear, parabolic partial differential equation with variable coefficients.

#### Derivation

The basic three-dimensional salt balance equation states that the local (Eulerian) time rate of change of salinity is a result of advective transport and diffusion processes:

$$\frac{\partial \dot{s}}{\partial t} = \frac{\partial (\dot{u}\dot{s})}{\partial x} - \frac{\partial (\dot{v}\dot{s})}{\partial y} - \frac{\partial (\dot{w}\dot{s})}{\partial z} + D\Delta^2 \dot{s}$$
 [1]

where  $\dot{s}$  = salinity at (x, y, z, t),

 $\overset{\star}{\text{u}}, \overset{\star}{\text{v}}, \overset{\star}{\text{w}}$   $\Xi$  cartesian components of velocity, and

D = molecular diffusion coefficient for salt.

In dealing with an estuary, one can seldom obtain instantaneous measurement of the variables in equation [1]. Existing measurement schemes usually force the use of some averaged form, in which the molecular diffusion terms are negligible in comparison to eddy diffusion terms that appear as a result of the averaging. Pritchard (1968) has shown that averaging equation [1] over a time scale  $\Delta t$  which is long compared to the characteristic time of molecular motion but small in comparison to the characteristic time of large advective processes such as the tidal

period, produces a relation that is more amenable to existing measurement and analytic techniques. If the instantaneous variables are expressed as the sum of a mean value and a deviation term,

and

where as for any variable f

$$f = \langle f \rangle = \frac{1}{\Delta t} \int_{\Delta t}^{*} f dt' \text{ and } \langle f' \rangle = 0,$$

the substituting into equation [1] and using Reynolds' rules for averages, results in

$$\frac{\partial \mathbf{s}}{\partial t} = -\frac{\partial (\mathbf{u}\mathbf{s})}{\partial \mathbf{x}} - \frac{\partial (\mathbf{v}\mathbf{s})}{\partial \mathbf{y}} - \frac{\partial (\mathbf{w}\mathbf{s})}{\partial \mathbf{z}}$$

$$-\frac{\partial \langle \mathbf{u}'\mathbf{s}' \rangle_{\Delta t}}{\partial \mathbf{x}} - \frac{\partial \langle \mathbf{v}'\mathbf{s}' \rangle_{\Delta t}}{\partial \mathbf{y}} - \frac{\partial \langle \mathbf{w}'\mathbf{s}' \rangle_{\Delta t}}{\partial \mathbf{z}}$$
[2]

the turbulent fluxes in [2] have conventionally been represented as a product of a diffusivity and a gradient of the mean salinity:

$$K_{\mathbf{x}} \frac{\partial \mathbf{s}}{\partial \mathbf{x}} \equiv -\langle \mathbf{u's'} \rangle_{\Delta t},$$

$$K_{\mathbf{y}} \frac{\partial \mathbf{s}}{\partial \mathbf{y}} \equiv -\langle \mathbf{v's'} \rangle_{\Delta t},$$
and
$$K_{\mathbf{z}} \frac{\partial \mathbf{s}}{\partial \mathbf{z}} \equiv -\langle \mathbf{w's'} \rangle_{\Delta t}.$$

Based on an analogy to the molecular diffusion case, these coefficients are the nonadvective salt fluxes due to that part of the motion which takes place at time scales smaller than  $\Delta t$ . The three-dimensional salt balance equation now becomes

$$\frac{\partial s}{\partial t} = -\frac{\partial (us)}{\partial x} - \frac{\partial (vs)}{\partial y} - \frac{\partial (ws)}{\partial z} + \frac{\partial}{\partial z} \left( K_{x} \frac{\partial s}{\partial z} \right) + \frac{\partial}{\partial z} \left( K_{z} \frac{\partial s}{\partial z} \right).$$
[3]

To reduce [3] to a one-dimensional form, a spatial average must be taken over the cross-sectional area of the estuary,  $\sigma$ . The procedure used is similar to that employed in obtaining the time-averaged equations; that is, each of the variables is separated into a spatial average term and a deviation term:

$$s \equiv s_{\sigma} + s_{\sigma}'$$
,

$$u \equiv u_{\sigma} + u_{\sigma}'$$
,

$$v \equiv v_{\sigma} + v_{\sigma}'$$
,

and

$$w = w_{\sigma} + w_{\sigma}'$$

where

$$f_{\sigma} \equiv \langle f \rangle_{\sigma} = \frac{1}{\sigma} \iint_{\sigma} f d\sigma'$$

and 
$$\langle f_{\sigma}' \rangle_{\sigma} = 0$$
.

When these substitutions are introduced into [3] and the equation inte-

grated over the cross section  $\sigma$ , the result is

$$\frac{\partial (\sigma s_{\sigma})}{\partial t} = -\frac{\partial (\sigma u_{\sigma} s_{\sigma})}{\partial x} - \frac{\partial}{\partial x} (\sigma << u's'>_{\Delta t} + u_{\sigma}'s_{\sigma}'>_{\sigma}) . [4]$$

A coefficient K can be formally defined in a similar manner  $\mathbf{x}_{,\sigma}$  to the turbulent diffusion coefficients in [3]:

$$K_{\mathbf{x}}$$
,  $\frac{\partial s}{\partial \mathbf{x}} \equiv - \langle \langle \mathbf{u}' \mathbf{s}' \rangle_{\Delta t} + \mathbf{u}_{\sigma}' \mathbf{s}_{\sigma}' \rangle_{\sigma}$ .

The one-dimensional equation then becomes

$$\frac{\partial (\sigma s)}{\partial t} = -\frac{\partial (\sigma u s)}{\partial x} + \frac{\partial}{\partial x} (\sigma K_{x,\sigma} \frac{\partial s}{\partial x}) . \qquad [5]$$

The coefficients in the three-dimensional equation can be spoken of as representing nonadvective fluxes over the averaging period which are due to deviation terms that relate to the turbulent flow. Equation [5] balances the mean longitudinal advection with an effective one-dimensional diffusion. The reason for the introduction of  $K_{\mathbf{x},\sigma}$  is that it allows one to relate the effective diffusion term to external parameters of the estuary more readily than do the averaged cross-products of the deviation terms. With averaging, continuity considerations allow the replacement of the quantity  $\sigma u_{\sigma}$  in the advective term by R, the net freshwater inflow to the estuary above section  $\sigma$ . Equation [5] then becomes

$$\frac{\partial (\sigma s)}{\partial t} = -\frac{\partial (Rs)}{\partial x} + \frac{\partial}{\partial x} (\sigma K_{X,\sigma} \frac{\partial s}{\partial x})$$
where  $R = R(x,t)$  and  $s = s_{\sigma}$ .

For practical application of [6] to the estuary, the salinity s has been interpreted as the value of position x at a specified phase of the tide such as slack water before flood, rather than as a true average over the tidal cycle. Under the assumption that the tide simply advects a fixed salinity pattern, these two values should be equivalent.

#### 2. Finite Difference Form

Equation [6] has been used as a model to relate the observed longitudinal distribution to the freshwater inflow. The one-dimensional salt balance equation is linear, second-order, and parabolic, with variable coefficients which are functions of both space and time. In its solution, the property of linearity makes it amenable to numerical finite difference techniques.

The partial differential equation [6] may be converted to a finite difference equation by expanding the derivatives into differences.

The time derivative is replaced by a forward difference:

$$\frac{\partial s}{\partial t} \sim \frac{s(t+\Delta t) - s(t)}{\Delta t}$$
.

The advective term, involving two variables R and s, is replaced by a central difference:

$$\frac{\partial (Rs)}{\partial x} \sim \frac{R(x+\Delta x) s(x+\Delta x) - R(x-\Delta x) s(x-\Delta x)}{2\Delta x}.$$

The diffusion term can be expressed as

$$\frac{\partial}{\partial \mathbf{x}} \left( \sigma \mathbf{K} \frac{\partial \mathbf{s}}{\partial \mathbf{x}} \right) = \sigma \mathbf{K} \frac{\partial^2 \mathbf{s}}{\partial \mathbf{x}^2} + \frac{\partial \sigma \mathbf{K}}{\partial \mathbf{x}} \frac{\partial \mathbf{s}}{\partial \mathbf{x}} . \tag{7}$$

In finite difference form, the first term on the right side of [7] is replaced by a second difference form:

$$\sigma K = \frac{\partial^2 s}{\partial x^2} \sim \frac{\sigma K(x)}{2\Delta x^2} \quad [s(x+\Delta x) - 2s(x) + s(x-\Delta x)] \quad .$$

The second term is represented as follows:

$$\frac{\partial (\sigma \mathbf{k})}{\partial \mathbf{x}} \frac{\partial \mathbf{s}}{\partial \mathbf{x}} \sim \frac{1}{2\Delta \mathbf{x}^2} \left\{ \sigma \mathbf{K} (\mathbf{x} + \Delta \mathbf{x}) \left[ \mathbf{s} (\mathbf{x} + \Delta \mathbf{x}) - \mathbf{s} (\mathbf{x}) \right] - \sigma \mathbf{K} (\mathbf{x} - \Delta \mathbf{x}) \right\}$$

$$\left[ \mathbf{s} (\mathbf{x}) - \mathbf{s} (\mathbf{x} - \Delta \mathbf{x}) \right] \right\}$$

When these differences are combined in the salt balance equation there is a choice of whether to take the spatial derivatives at time t or at time t +  $\Delta t$ . The choice of taking the derivatives at t would be attractive because, once s(t) is known, s(t +  $\Delta t$ ) can be solved for explicitly, without having to invert a matrix of simultaneous equations. Unfortunately, for the  $\Delta t$ (6.048 x 10<sup>5</sup>s) and  $\Delta x$ (500 m) which were used in the analysis, this differencing scheme would violate the stability requirement for the convergence of the solution. By using an implicit scheme, taking the spatial directives at t +  $\Delta t$ , one has to solve a system of simultaneous equations, but the solution is unconditionally stable. This differencing scheme converts the partial differential equation to a set of difference equations:

III-14.

$$P_{L}(\mathbf{x})s'(\mathbf{x}-\Delta\mathbf{x}) + s'(\mathbf{x}) + P_{R}(\mathbf{x})s'(\mathbf{x}+\Delta\mathbf{x}) = \frac{s(\mathbf{x})}{P_{L}(\mathbf{x})}$$
 [8]

where

$$P_{C}(\mathbf{x}) = 1 + D(\mathbf{x}) \left[ \sigma K(\mathbf{x} - \Delta \mathbf{x}) + 2\sigma K(\mathbf{x}) + k (\mathbf{x} + \Delta \mathbf{x}) \right]$$

$$P_{L}(\mathbf{x}) = \frac{-B(\mathbf{x})R(\mathbf{x}-\Delta\mathbf{x}) - D(\mathbf{x})[\sigma K(\mathbf{x}-\Delta\mathbf{x}) + \sigma K(\mathbf{x})]}{P_{C}(\mathbf{x})}$$

$$P_{R}(x) = \frac{B(x)R(x+\Delta x) - D(x)[\sigma K(x) + \sigma K(x+\Delta x)]}{P_{C}(x)}$$

and


$$B(x) = \frac{\Delta t}{2\sigma(x)\Delta x}$$
,  $D(x) = \frac{B(x)}{\Delta x}$ 

and s' = salinity at time  $t + \Delta t$ .

Given an initial salinity distribution in an estuary of length  $N\Delta x$ , the set of equations [8] can be used in conjunction with the two boundary conditions S'(0) and S'(N) to describe the salinity distribution for a time  $\Delta t$  later.

#### 3. <u>Diffusion Coefficients</u>

The diffusion coefficients, K, are functions of both position in the estuary and flow of the Merrimack River. The average weekly flow rate of the Merrimack is given in Figure 2. If sufficient data were available, EQ. [6] could be integrated over x and solved for ok. There were not sufficient observations for the Merrimack River to perform this integration. Since Boicourt's model for the Upper Chesapeake



Bay was used as the basis for the model for the Merrimack River it was decided to see if K values could be transferred. The cross-sectional areas,  $\sigma$ , were known for both estuaries, hence, K values could be recovered from the Cheskapeake  $\sigma K$  values (Figure 3).

Boicourt (1969) used the form

$$\sigma K = \exp \left[C_0 + C_1 x\right].$$
 [9]

The coefficients  $C_0$  and  $C_1$  were determined by a least-squares fit to 1966-67 data. Two functions were developed to relate the coefficients to river flow:

$$C_{o} = A_{o} (log R)^{O}$$
 [10]

where  $A_0 = 7.724$   $B_0 = .3580$ ,

and 
$$C_1 = A_1 (\log R)^{B_1}$$
 [11]

where  $A_1 = .6138 \text{ and } B_1 = 1.498$ 

and R is the average weekly river flow  $(m^3/\text{second})$ .


EQ. [9] may be rewritten

$$\ln \sigma K = C_0 + C_1 \times [9a]$$

and given  $\sigma$  as function of  $\mathbf{x}$ , a new equation for K can be determined,

$$\ln K = H_0 + H_1 x$$
 [12]

Figure 3. Merrimack River Cross-sections (ft<sup>2</sup>).



$$H = \exp [0.460 + 0.1955 \ln R]$$
 [13]

$$H_1 = \exp [-3.17 - .00287 R]$$
 [14]

These values provide a good average salinity over both estuaries but for salinity at high or low tide the coefficients must be modified. Using the limited data available for the Merrimack River, the coefficients in Table I were determined to provide an acceptable fit to observations.

The upstream boundary value was set to 0 while the boundary value at the mouth of the river was found to be a function of river flow and tide stage. The boundary values used in the mathematical model are shown in Figure 4.

In summary, the major assumptions made in this development include the following:

- Salinity values used in the model are averages over the cross-section of the estuary and that variables are related only to time and position along the longitudinal axis of the estuary.
  - 2) Molecular diffusion is negligible.
- 3. That eddy diffusion can be treated in a manner analogous to molecular diffusion that is as a product of a diffusivity and a

# SALINITY STUDY, MERRIMACK RIVER ESTUARY MATHEMATICAL STUDY

#### TABLE L

#### COEFFICIENTS FOR K - MERRIMACK RIVER

# High Tide


$$H = \exp [0.23 + 0.10 \ln R]$$

$$H_1 = \exp [-1.6 - .015 R]$$

# Low Tide

$$H_O = \exp [0.46 + 0.19 \ln R]$$

$$H = \exp [-3.0 - .003 R]$$



gradient. (Note that in this study diffusivity is taken as a function of space and time.)

- 4) The tidal currents are assumed to advect a fixed salinity pattern periodically up and down the estuary. (This assumption allows measurements made and one phase of the tide to be treated as averages over the tidal cycle.)
- 5) That the Merrimack River's salinity distribution has little time history effect.
- 6) That the Merrimack River can be treated as nearly sectionally homogeneous.
- 7) Effects of the earth's rotation are assumed to be negligible.

#### 4. Solution

The finite difference equation [8] with the addition of the two boundary conditions, forms a set of N simultaneous linear equations in N unknowns, where  $N\Delta x$  is the length of the estuary. Given an initial salinity distribution S(x), the salinity at a time  $\Delta t$  later can be determined by inverting the matrix of the S'(x) coefficients. A convenient method for this inversion is to triangularize and then solve for the S'(x) via back substitution (Gauss elimination; see Hildebrand,

1968). The tridiagonal nature of the matrix fortuitously reduces the triangularization procedure to a recursive sweep over x space. This sweep consists of computing the space functions Q(x) and P(x) (Pritchard, 1969):

$$Q(x) = \frac{-P_R(x)}{1 + P_L(x)Q(x-1)}$$

$$P(x) = \frac{\frac{S(x)}{P_{C}(x)} - P_{L}(x)P(x+\Delta x)}{1 + P_{L}(x)Q(x-\Delta x)}$$

where  $\mathbf{P}_{L}$  ,  $\mathbf{P}_{R}$  , and  $\mathbf{P}_{C}$  are coefficients in equation [8].

Back substitution, which produces the S'(x) values, consists of a recursive sweep in the opposite direction:


$$S'(x) = P(x) + Q(x)S'(x+\Delta x)$$


The resulting S'(x) became the S(x) for the next time step, where a new set of difference equations are formed from the new coefficients computed from the new value of the river flow.

### 5. Testing and Evaluation

The predicting functions for the coefficients and boundary values were tested against salinity data obtained during the years 1967 to 1971. The model is supposed to predict weekly average salinity values. Some of the observed data represent only two days. The plotted results are shown in Figure 5. The results appear to be quite

Figure 5a. Comparison of Observed and Calculated Salinity Distributions in the Merrimack River.










Figure 5b. Comparison of Observed and Calculated Salinity Distributions in the Merrimack River.









Figure 5c. Comparison of Observed and Calculated Salinity Distribution in the Merrimack River.



Downstream

Grid Point Locations

reasonable. There is a tendency for the model to overpredict in the two kilometers immediately upstream of the mouth of the river at high flow rates, (i.e., greater than 5,000 cfs, for low tide).

More verification is needed at flow rates less than 5,000 cfs. There was only one observation at 2,000 cfs and the model appeared to overpredict slightly for high tide. Since the coefficients determining the diffusion rates are based on the observed data, the use of the model outside the range of validation should be done with caution.

#### 6. Principal Limitations

The principal limitation of the mathematical model of the Merrimack River Estuary is that the vertical and horizontal gradients are not considered. Since there is not sufficient seasonal and spatial data to justify a more elaborate model, a one-dimensional model in space has been used. Of principal importance to the ecological study is the limit of salt intrusion and the average salinity at the various stations. The verification studies reported in the paragraph above indicate that these methods have been justified with respect to the vertically averaged salinity values and the limit of salt intrusion in the estuary. Thus a one-dimensional model can satisfactorily represent the average distribution of salinity in the Merrimack River, but it is inadequate for those who require information on the vertical distribution. However, in the region of the salt front where the

horizontal salinity gradients are the greatest and the vertical salinity gradients the weakest, the model can be used directly as a first approximation to the salinity structure. For more vertically stratified conditions such as those which occur in the lower reaches of the estuary during moderately low flows at high tide it is possible to refer to other information such as a "typical" salinity-depth curve to obtain an indication of the possible salinity values in the upper and lower layers.

#### D. RESULTS

The results of the mathematical model are presented as a series of computer printouts in graphic form. The method of indexing the graphic charts has been arranged for the greatest possible user convenience consistent with the detail of the information required. Sensitivity studies were made to determine the effect of small changes in runoff on the salinity distribution. These studies indicated that incremental changes of less than 100 cfs at the low ranges and 2,000 cfs at the high ranges have little effect on the model and further that the recent time history of flow also has very little effect on the model. Hence, it has been possible to devise a diversion index, Table II., which summarizes and keys them to the graphic charts.

#### 1. The Diversion Index

Natural flows are tabulated in the left hand "flow" column of

# SALINITY STUDY, MERRIMACK RIVER ESTUARY MATHEMATICAL STUDY

TABLE II.

### DIVERSION INDEX

7	(Cubic Feet per Second) 1 100 200 300 500 600 800 1000 1100 1500 1900 2000 2800 5200 8000													
DIVERSION	100	200	300	500	600	800	1000	1100	1500	1900	2000	2800	5200	8000
FLOW														
							<del></del>							
800														
850														
900														
950	2													
1000	3							1*	•					
1100	5	3												
1200	6	5.	. 3											
1300	7	6	5											
1400	8	7	6	3										
1500	9	8	7	5	3									
1600	10	9	8	6	5									
1700	11	10	9	7	6	3								
1800	12	11	10	8	7	5								
1900	13	12	11	9	8	6	3							
2000	14	13	12	10	9	7	5	3						
3000	16	16	16	15	15	15	15	15	10	5	5			
4000	17	17	17	17	16	16	<b>1</b> 6	16	15	15	15	7		
5000	18	18	18	17	17	17	17	17	17	16	16	15		
6000	19	19	19	19	18	18	18	18		17	17	16		
7000	20	20	20	19	19	19	19	19	19	18	18	17	13	
8000	21	21	21	21	20	20	20	20	19	19	19	18	16	
10000	22	22	22	22	22	22	21	21	21	21	21	20	18	15
12000	23	23	23	23	23	23	22	22	22	22	22	22	20	17
14000	24	24	24	24	24	24	24	23	23	23	23	23	21	19
16000	25	25	25	25	25	25	25	24	24	24	24	24	22	21
cfs														

<sup>\*</sup>All blank table entries refer to Figure 1 of Appendices A and B for high and low tides, respectively. Figures 1 (A & B) represent the minimum control flow established by the Corps of Engineers.

Although natural flows in river frequently occur below 800 cfs, salinity profile plots were not carried out below 800 cfs because this represents the minimum flow beyond which diversions are not contemplated.

the diversion index. The various diversion rates are listed across the top of the table. The index numbers represent the appropriate figure of Appendix "A" for the high tide case and also the appropriate figure of Appendix "B" for the low tide case. For example, when the river flow is 1,800 cfs, the diversion index number is 10. Thus, the appropriate figure in the salinity atlas is A-10 for the high tide case and B-10 for the low tide case. Appendix "C" is a listing of the weekly average flow rates from 1927 to 1967. Weekly flow rates instead of monthly flow rates have been used since the estuary responds to different flow rates quickly enough to warrant additional detail. To use the index, select the flow and diversion to be investigated; at the intersection of the columns (diversions) and horizontal lines (flows) will be found the index number. The index number references the applicable figure number of the graphical computer printouts of longitudinal salinity for the Merrimack River Estuary.

### 2. Graphic Computer Printout

The graphic computer printout is a plot of the computed vertical average of salinity at high tide (low tide) weighted by the width of the estuary. The units of the horizontal coordinate are one-half kilometer intervals. Table III keys the Normandeau Associates station numbers to the graphic printout one-half kilometer intervals. The vertical coordinate represents the vertical weighted average salinity in the range of 0 to 35 parts per thousand (S<sup>O</sup>/oo). Figure 6 is the salinity station and half-kilometer grid point key.

# III-30.


# SALINITY STUDY, MERRIMACK RIVER ESTUARY

### MATHEMATICAL STUDY

# TABLE III SALINITY STATION AND HALF-KILOMETER GRID POINT

# KEY

NORMANDEAU ASSOCIATES, INC. STATION NUMBER	ONE-HALF KILOMETER INTERVAL SHOWN OF GRAPHIC PRINTOUTS
s 1	40 (mouth of estuary)
S 2	39
S 3	37
S 3A	31
S 4	29
S 5	24
S 6	11
s 7	- 3 (head of estuary)



Approximate Scale: 1:93,600

#### 3. Summary

The salinity distribution in the Merrimack River Estuary has been modeled using a model based on the one-dimensional salt balance equation of Pritchard. The results of the computations have been presented in graphical form, keyed to the runoff values and proposed diversions by an index.

The results of the computations indicate a seaward progression of the salt from grid point 5 at 800 cfs to grid point 26 at 16,000 cfs for the high tide case. For the low tide case the corresponding progression is from grid point 18 at 800 cfs to grid point 35 at 16,000 cfs. For higher flows the salt front is essentially removed from the estuary and detailed computations are not necessary. These results are in agreement with physical reality in the important characteristics and trends. Thus, it is concluded the model is a useful one which could be utilized for other purposes in future planning for the Merrimack Basin.

The one-dimensional model used in this study is of value for two reasons: 1) it furnishes the desired predicting ability and it also provides a base from which more elaborate models can be developed; 2) of immediate practical interest would be the addition of the ability to model BOD loading using this model as a basis. The regional planning regarding the effects of sewer or other outfalls could be implemented using this model as a basis.

# ECOLOGICAL STUDY

MERRIMACK RIVER ESTUARY - MASSACHUSETTS

IV. POTENTIAL EFFECTS OF DIVERSION ON THE

PHYSICAL CHARACTERISTICS OF THE ESTUARY

v-0J.

A. MUBULUB

#### ECOLOGICAL STUDY

MERRIMACK RIVER ESTUARY - MASSACHUSETTS

IV. POTENTIAL EFFECTS OF DIVERSION ON THE

PHYSICAL CHARACTERISTICS OF THE ESTUARY

#### A. INTRODUCTION

A rapidly expanding body of knowledge on the effects of river diversions on the physical characteristics of rivers and estuaries is becoming available. Much of this information was covered in general terms at the New England Conference on River Diversions, held at the New England Center for Continuing Education, Durham, New Hampshire, in May 1971 (Forste, R. H., Editor, 1971). As was pointed out at that time, even though many of the consequences associated with particular river diversions are unique to those rivers, other effects are comparable to those encountered in all potential diversion cases.

These effects fall into two categories. With any diversion, certain substances are removed directly from the system, including freshwater, dissolved and particulate organic material, freshwater plankton, trace elements, and sediments. The removal of these substances may lead to direct physical changes in the system, including some or all of the following:

- 1. Salinity increase.
- Changes in sedimentation.
- 3. Alteration of current flow.
- 4. Reduction of temperature extremes.
- 5. Changes in the effect of pollution load.
- 6. Difference in dissolved  $0_2$ .
- 7. Changes in transparency.

Some of these changes have potentially serious effects on the ecology of the estuary, while others appear to be of minimal importance. In some instances further study must be done before definite conclusions can be drawn. Those physical changes that appear to be of potential ecological significance to the estuary will be discussed in the following pages.

# B. LONGITUDINAL CHANGES IN SALINITY DISTRIBUTION

Results of VAST's mathematical model, as well as other salinity measurements made during 1971 and earlier findings reported by Hartwell (1970), indicate that under high discharge the Merrimack River Estuary is essentially fresh throughout most of the tidal cycle. Saline water progresses further upstream as discharge drops. Based on this information and a knowledge of suggested diversion rates and minimum flows below which diversions will not be made, it is possible to evaluate the consequences of potential changes in longitudinal salinity patterns resulting from diversion.

Natural flows in the Merrimack River rarely drop below 800 cfs on an average weekly basis (Appendix C). This occurred only twice in a 40 year period and, in fact, average flows were below 1,000 cfs during less than 1% of the 2,080 weeks studied. The latter flows were experienced during 18 weeks distributed over four of the 40 years involved, namely 1957, 1964, 1965, and 1966. Average flows less than 1,500 cfs occurred during 24 of the 40 years, the total number of weeks involved being 138, or 7% of the 2,080 week period.

The daily operational pattern of the several dams along the Merrimack River is such that river flows fluctuate markedly within a week. While the number of high flow days is greater than the number of low flow days, hence the two to three thousand cfs rate shown during summer months (Figure 7a), flow rates well below 800 cfs do occur periodically. This is reflected in monthly averages of the daily minima which occurred from 1924 to 1969 during July, August, and September, which are 1,026, 772, and 778 cfs, respectively. These naturally occurring average minima are below the control levels established for the river for the July-September period (Section I).

We conclude from these facts that upriver areas presently affected by salt water intrusion only periodically, such as between miles 5 to 10, may be subjected to more frequent saline influence due to diversion. This should not represent an entirely new experience however. The effects of diverting water at several different rates







Figure 7a. COMPARATIVE EFFECTS OF SEVERAL DIVERSION RATES ON THE SEASONAL FLOW PATTERN IN THE MERRIMACK RIVER.








**.** 





-- --- --- onore i ishenes























as suggested by the Corps of Engineers are shown in Figure 7a, which is based on average weekly flows in the Merrimack River over the period of record. Figures 7b through 7m are included in order that the reader may gain an appreciation of the wide range of flow conditions which occur from year to year, and how diversions may affect the hydrograph in each of the cases presented. Table IV illustrates the distribution of flow rates in the Merrimack River over the period of record.

Referring now to 7a, on the average, water flow exceeds the control value for each month by an amount which is equal to the differential between the control zone (shaded) and curve "A". If we then impose some suggested diversion rates on curve "A", we can study the overall relationships between absolute and relative flow patterns over the course of the year, and gain some knowledge as to the average amount of time certain parts of the river would be exposed to measureable salinities. For example, the increased amounts of time during which flow rates would be 5,000 cfs or less are:

- 0.5 weeks at diversion rate "B";
- 1.5 weeks at diversion rate "C";
- 12.0 weeks at diversion rate "D"; and
- 19.0 weeks at diversion rate "E".

Putting this in terms of salinity exposure, using high tide (Figure A-18 of Appendix A), Station S-5 (Km 12 of VAST) would experience salinities at least as high as 19.5 % oo, 3 percent, 8 percent, 62 percent, and 100 percent more of the time than at present. At the mouth of the river (Figure 3), high tide salinities would approach 29.5 % oo for equally

# ECOLOGICAL STUDY MERRIMACK RIVER ESTUARY - MASSACHUSETTS

TABLE IV.


FLOWS IN CFS WHICH WERE EXCEED IN A GIVEN PERCENT OF TIME DURING THE PERIOD OF RECORD (1927 - 1968)

	MAXIMUM	PERCENT							
MONTH	FLOW	02%	05%	10%	20%	50%	80%	FLOW	
1	39800.	20200.	14900.	11900.	8600.	5410.	3330.	585.	
2	27200.	16600.	14300.	11600.	8840.	5600.	3600.	630.	
3	161000.	41800.	29400.	21600.	15600.	9540.	<b>5</b> 930.	1410.	
4	77200.	45200.	<b>3</b> 6900.	31200.	25900.	16900.	10700.	2490.	
5	48600.	29900.	23600.	19900.	16300.	9660.	6060.	666.	
6	47800.	19600.	14500.	11900.	8960.	4680.	2780.	403.	
7	27900.	9420.	7260.	5520.	4260.	2660.	1600.	249.	
8	20600.	8000.	6020.	4580.	3280.	2100.	1310.	233.	
9	118000.	15600.	7930.	5120.	37 <b>3</b> 0.	2040.	1280.	219.	
10	34900.	13000.	8510.	6660.	4810.	2550.	1430.	214.	
11	66200.	22800.	15900.	12100.	8180.	4350.	2460.	319.	
12	39800.	24600.	17400.	13500.	9150.	5140.	3050.	378.	

lengthened periods of time, and low tide salinities of 22.5 °/oo would also occur more often. Intuitively, this sort of pattern would be expected to hold true for any station, but would be proportionately different depending upon flow.

seasonal changes in longitudinal salinity distribution beyond mile 5 of the estuary are schematically illustrated in Figure 8 through 10. Detectable salinities of 5 % of were used in these figures, and upstream intrusions are based on average monthly flow rates from 1927-1967. It should be noted that in Figure 10 (September) intrusions occurring at diversion rates "D" and "E" (-1,100 cfs and -2,000 cfs, respectively) are hypothetical cases since no diversions will be made to cause flows to be reduced below control levels.

The figures provide an indication of how far upriver a salinity gradient of 5 °/00 will move each season, given that flow conditions approximate the 40 year mean used in our calculations. The difference in salinity encroachment between average natural weekly flows and the highest diversion rate considered (E) varied from 0.47 miles (0.76 Km) in March and May, when flows are high, to 1.71 miles (2.75 Km) in September and October. However, salinity intrusion characterizing monthly averages of daily flow minima for each month are generally of the same magnitude as the maximum diversion rate. Therefore, organisms at most locations would simply be subject to more frequent increases in salinity. Salinity encroachment at control levels is considerably








Figure 8. Average longitudinal intrusion of waters of 5  $^{\rm O}/{\rm oo}$  at different rates of diversion during high tide.





Figure 9. Average longitudinal intrusion of waters of 5  $^{\rm O}/{\rm oo}$  at different rates of diversion during high tide.


- A. Avg. Natural Flow 1927-1967 D. -1100 cfs
- B. -100 cfs


E. -2000 cfs

C. -500 cfs

- F. Monthly avg. of daily minima 1926-1969
- G. Control levels










Figure 10. Average longitudinal intrusion of waters of 5 0/00 at different rates of diversion during high tide.

higher, in proportionate sense, than the 2,000 cfs diversion rate (excepting the summer and fall months). This amounts to from 2 (3.22 Km) to > 5 miles further upriver than that which occurs under average condtions, depending upon season. Diversions representing smaller proportions of the natural flows, for example, 1,100 cfs from 16,000 cfs, move the point of minimum measureable salinity lesser distances upstream, in this instance three tenths of a mile (one-half kilometer).

Beyond these seasonal patterns, tidal oscillations produce interesting results also. A six hour tidal cycle moves the salinity concentration pattern approximately 7 to 8 Km (4.34 to 4.96 miles) up or downstream. Depending on the grid point this movement causes varying degrees of six hour salinity fluctuations. For instance, at grid point 9, under an 800 cfs condition, salinity varies from 0 to 6 °/oo. At point 35, with 16,000 cfs, salinity varies from 0 to 11.5 °/oo.

### C. ALTERATIONS OF ESTUARINE CIRCULATION

The Merrimack River Estuary usually exhibits the characteristics of the moderately stratified estuary (type B) in the estuarine sequence as defined by Pritchard (1959, 1968). Salinity distribution in the Merrimack River varies as a function of river flow and phase of the tide. As in most moderately stratified estuaries, the effects of the earth's rotation are discernable. The tidal flat region bordering the southern bank of the Merrimack River Estuary near its mouth is

characterized by water of lower salinity than the water of the main channel. As has been described in pages III-17 through III-18, and summarized on pages III-18 and III-21, the model treats the average salinity along the main channel of the estuary where the longitudinal salinity gradients are most important and the effect of the earth's rotation has therefore been neglected.

Vertical stratification in the Merrimack Estuary varies with river flow. Hartwell (1970) has shown that stratification occurs in the estuary when river flows are in the range of 1,900 to 6,300 cfs, but it is generally observed that the estuary exhibits well developed stratification at river flows above 3,000 cfs. As flows drop below this value the estuary becomes progressively less stratified and increasingly well-mixed.

Complete records on Merrimack River daily flows have been taken at the Lowell Gauging Station from 1923 to the present. A study of the data from 1923 to 1968 (Table V) indicates that monthly river flows in July, August, September, and October have been below 6,000 cfs at least 85% of the years on record, and dropped below 3,000 cfs in at least 50% of the years. In addition, monthly flows in November, December, January, and June are below 6,000 cfs in more than 50% of the years. Because alterations in estuarine circulation patterns occurring in this range of flows may affect other physical parameters discussed later, and because such flows are frequently approached in

the Merrimack River, diversions which would increase these periods of time substantially may have important ecological implications.

## ECOLOGICAL STUDY MERRIMACK RIVER ESTUARY - MASSACHUSETTS

NUMBER OF TIMES RIVER DISCHARGE WAS AT OR NEAR

DESTRATIFICATION LEVELS (1923-1968)

DISCHARGE						3-1968 ONTHS	3)					
(cfs)	Jan	Feb	Mar	Apr	May	June	July	Aug	Sept	Oct	Nov	Dec
Under												
3,000 cfs	7	3	0	0	0	7	28	<b>37</b> <sup>-</sup>	34	24	9	7
3,000 cfs to												
6,000 cfs	14	23	4	0	3	20	14	6	10	15	19	18

## D. PHYSICAL CHANGES RESULTING FROM ALTERATIONS OF CIRCULATION

## 1. Alterations in Suspended Sediment Distribution:

Ocean water entering the estuary carries a relatively small suspended sediment load, while the river, even under periods of low discharge, carries a much higher load. Because of this difference in sediment content of the two masses of water, changes in the freshwater/saltwater stratification of the estuary could lead to alterations in the pattern of sedimentation.

When the river is at high discharge, much of the sediment load is flushed out of the estuary over the salt wedge, and little sedimentation occurs (Goldsmith, 1971, pers. comm.). Under periods of normal river flow, but when stratification is still well-developed, large amounts of sediment are deposited over shallow areas on the south side of the estuary. This heavy sedimentation is particularly apparent on Joppa Flats, where accumulation of sediments and pollutant materials contributed to the recent shoaling of the channel south of Woodbridge Island, and also the rapid accretion of Spartina alterniflora marsh (Hartwell, 1970).

The pattern of sedimentation becomes quite different however under low flow periods when the estuary is unstratified. At these times sediments do not settle selectively over Joppa Flats, but are more or less evenly deposited throughout the estuary.

Diversion of freshwater from the vicinity of Lowell, Massachusetts may affect the present patterns of sedimentation in two ways. The removal of freshwater would reduce the amount of sediment carried by the river, which will in turn lower the total load brought into the estuary. However, with decreased discharge less of this river water will be flushed out, possibly resulting in a net increase in the amount of fine sediment deposited within the estuary (Goldsmith, 1971, pers. comm.). Since diversion of freshwater will increase the number of days on which flows are low, this should lead to reduced deposition over the Joppa Flats area but somewhat increased sedimentation in other parts of the estuary. The extent of these changes and their significance cannot be determined without further study.

## 2. Net Inflow of Bottom Sediments Resulting From Changes in Current Flow:

Hartwell (1970) and Hayes, et al (1970) have done a considerable amount of research on hydrography and sedimentation in the Merrimack River Estuary and other estuaries. This research has shown that velocities of currents entering an estuary on the flood tide tend to be considerably stronger than those of currents leaving on the ebb, and these currents are active in the formation of flood tidal deltas due to a net influx of sediments into the estuary.

Aerial photographs of the Merrimack River Estuary taken in July 1971 reveal sand movements along the bottom and into the estuary at its narrow entrance. This transport has resulted in the production of a large bedform with steep slip-faces located on the inshore side. In spite of this observed influx of sand, the flood tidal delta at present is relatively small in comparison to the total size of the estuary, and with respect to flood tidal deltas in other estuaries. In addition, indications are that the Merrimack River flood delta has been relatively stable, with only minor changes compared to other estuaries.

How might this situation change as a result of diversion?

Hayes, et al (1970) have shown that the velocity, time during which flood tidal currents dominate, and distance of penetration of the salt wedge are all directly related. Their studies have also shown that decreased river discharge results in an increased penetration of the salt wedge. Therefore, since the amount of sand transported into the estuary is related to the amount of penetration of the salt wedge (Hartwell, 1970), it follows that an increase in the amount of flood oriented sand waves will occur with decreased discharge.

Goldsmith (1971, pers. comm.) suggested that the following sequence may be theoretically possible with decreased river discharge:

- a) An increased rate of sediment movement, as bedforms, into the estuary through the flood tidal channel resulting in a larger flood tidal delta;
- b) Increased sand deposition which would require increased effort of the existing maintenance dredging program; and
- c) Decreased circulation in the Merrimack River Estuary resulting in increased deposition of fine sediments (and associated pollutants) in the estuary.

Even a small increase in rate of sediment influx into the Merrimack River could result in rearrangement of ebb and flood tidal channels, rearrangement of circulation patterns within the estuary, and altered patterns of erosion and deposition within the estuary. Hartwell (1970), found very strong sediment patterns within the estuary, and these could conceivably be changed, thus affecting the distribution of infauna such as clams. Increased sand deposition at the river entrance (Point "b" above) is thought not to be a major issue since the Army Corps of Engineers periodically dredges this area. Over the past ten years the Corps has removed a total of 700,000 cubic yards of sediment from the mouth of the Merrimack River. This was accomplished in five dredges, at approximately two year intervals, and an average removal of 140,000 cubic yards per dredging effort. It is expected that this activity will continue at essentially the same rates as in the past.

It is reasonable to assume that much of the sand transported into the estuary with greater salt-wedge penetration will come from the beaches adjacent to the inlet. A model of tidal circulation at inlets based upon studies of 15 New England (including the Merrimack) and numerous Alaskan coastal inlets showed that flood tidal currents tend to approach from the sides of an inlet and along the beaches (Hayes, et al, 1970). Based on these findings, increased transport into the estuary could result in possible beach erosion adjacent to the jetties.

#### E. UPPER ESTUARINE TEMPERATURE CHANGES

Daily and seasonal temperature variability is generally more pronounced in river than in ocean waters, with summer temperatures generally warmer, and winter temperatures colder, than the ocean. This implies that temperature variability in an estuary is directly affected by the amount of freshwater entering that estuary.

A reduction in freshwater from any proposed upriver diversion could result in two noticeable changes in the temperature characteristics of an estuarine system. If significant quantities of water are withdrawn during the summer when flows are normally low, stagnant pools of water could form. These would be subject to excessive heating, and could affect the ecology of certain portions of the estuary. Since no temperature studies have been done on this region, the extent of

thermal increase cannot presently be determined.

A lesser, but still noticeable effect may be observed in the lower estuary where reduced freshwater inflow could reduce daily and seasonal temperature fluctuation in the mixed estuarine waters, making them conform more closely with ocean temperature variabilities.

#### F. CHANGES IN THE EFFECT OF POLLUTION LOAD

The Merrimack River is grossly polluted along most of its length by industrial and domestic effluents. Numerous studies have been done to determine the nature and extent of this pollution, including work done by Oldaker (1966) and Daly, et al (1969). Data from these reports indicate that many parts of the freshwater river become anaerobic, especially in late summer and early fall when flows drop and temperatures rise. The situation is not nearly as serious in the Merrimack River Estuary, for the pollution load soon becomes well-mixed with relatively unpolluted ocean water. Even so, Jerome, et al (1965) found late summer dissolved oxygen readings as low as 5.0 ppm at the upper stations in 1964, and indicated that readings as low as 1.0 ppm have been observed at these stations during other years. They conclude that dissolved oxygen readings lower than 5.0 ppm will have adverse effects on finfish and some invertebrates, especially during the warmer summer months.

Since DO readings presently drop to critical levels under low flow/high temperature conditions in late summer and early fall, it

is probable that unless pollution is abated, extensive diversion during this time period may further aggravate the situation. However, since the control flows specified for these months would not permit diversion when the flows are below 1,000 cfs for June and September, and 1,500 cfs for July and August, no serious problems are anticipated.

## ECOLOGICAL STUDY

MERRIMACK RIVER ESTUARY - MASSACHUSETTS

V. POTENTIAL BIOLOGICAL CHANGES RESULTING FROM DIVERSION

#### ECOLOGICAL STUDY

#### MERRIMACK RIVER ESTUARY - MASSACHUSETTS

#### V. POTENTIAL BIOLOGICAL CHANGES RESULTING FROM DIVERSION

## A. INTRODUCTION

Every physical change brought about in an ecological system will result in corresponding changes in the biology of that system.

These changes will be manifested by alterations in aspects of life history of individual organisms, which in turn may affect the distribution and abundance of entire populations. Many of these biological changes may be imperceptible, and will fall well within the naturally occurring limits of variability experienced by a species. However, others may place sufficient stress upon a species so that survival rates could decrease, resulting in a gradual elimination of this species from a formerly suitable habitat. The interrelationships of the several populations occurring in an ecosystem are both complex, and for some, critical. Loss of an important population could result in a significant change in the makeup of the biotic community.

It must be understood that the limited data available do not permit any definite conclusions to be drawn relative to the biological effects of diversion on the intricate ecological balance of the estuary. However, from past experience, the reaction of specific organisms

to physical changes can be predicted, and the extent of possible changes can be discussed. For the present limited study, the following approaches to the problem have been used. Field sampling was carried out for five biological components of the estuarine system (intertidal benthos, intertidal algae, intertidal vascular plants, subtidal benthos, and plankton). Using the results of field sampling and available literature, an attempt has been made to cover, whenever possible, the following format for each biological component:

- 1) General introduction to the study, including purpose;
- 2) Methods utilized in collection of samples and analysis of data:
- 3) What is the existing distribution of the species and are these species marine, estuarine, cosmopolitan, or freshwater?;
- 4) What are the dominant species in the biological association at each station?;
- 5) What part of the life cycle of dominant species will be most affected by a salinity increase or by the potential changes in other physical parameters mentioned above? At what time of year is this situation most critical?
- 6) How might the biological association change if the salinity is increased, or if any of the other projected physical changes occur?;
- 7) Will this change in the association lead to other biological or physical changes?

8) Will new species be introduced into the area if salinity is increased, or if other physical changes occur, will any species be eliminated?

Species of commercial, recreational, or aesthetic importance to the Merrimack River Estuary have been discussed individually, and based on field sampling and available literature, an attempt has been made to evaluate the economic importance of the species to the area, the pertient aspects of life history, present distribution of the species in the Merrimack River Estuary, and potential effects of diversion on the ecology of the species.

#### B. INTERTIDAL BENTHIC ORGANISMS

#### 1. Rationale and Objectives:

If we are to make sound predictions concerning the biological effects of flow diversion on the ecology of the Merrimack River Estuary, it is essential to have a detailed picture of the animals and plants presently inhabiting the intertidal zone. This is particularly important because many of these organisms are extremely sensitive to changes in physico-chemical factors that occur in this environment, such as exposure to wave action, fluctuating salinity and temperature, and desiccation. Therefore, these organisms can tell us more about the existing physical conditions in the estuary and any changes that may occur following diversion than we could learn through our efforts due to the lack of sensitivity of sampling instrumentation. In addition, the wide variety of substrata in the intertidal, including mud, sand, marsh, and rocks, provides an assortment of micro-habitats, and thus potentially allows colonization by a series of introduced species should the physico-chemical changes resulting from diversion provide optimal conditions. Because an introduction of species could lead to interspecific competition, it is important to attempt to predict those species that may be introduced, those that could be eliminated as a result of competition or physiological stress, and how these floral and faunal changes may affect the overall composition of the intertidal community.

The objectives of the studies were threefold: 1) to collect and identify the intertidal algae, vascular plants, and invertebrates present at selected sites throughout the estuary; 2) to provide a qualitative description of the intertidal biota from the open ocean to the upriver limits of salt water intrusion; and 3) to evaluate the potential effects of freshwater diversion on this biota.

#### 2. Description of Stations:

A complete description of all intertidal stations sampled is presented in Table VI. The breakwater at Stations 1 and 3 provided the maximum amount of stable substrata for epibenthic organisms. intertidal areas at the remaining stations were primarily composed of scattered rock outcrops, boulders, pebbles and junk, interspersed The largest amount of solid rock was usually eviwith sand or mud. dent in the upper intertidal and the substrata tended to grade into sand-mud in the lower shore. From the mouth of the river to Station 29 there was a reduction in the amount of rocks (particularly large outcrops) and a progressive increase in the deposition of mud on the shore. A buildup of extensive peat-like material was evident in the upper intertidal zone at many stations throughout the estuary, where the roots of Spartina spp. stabilize muddy surfaces and allow colonization by seaweeds, vascular plants and invertebrates.

## TABLE VI

# A DESCRIPTION OF THE INTERTIDAL COLLECTING STATIONS STUDIED IN THE MERRIMACK RIVER ESTUARY

STATION	LOCATION AND DESCRIPTION
1	Open ocean side of the breakwater at Salisbury Beach:
	At this location large granite boulders extend from a sloping sand beach out into the clear, cold waters of the Atlantic. The rocks are exposed to open ocean surf, and those immediately adjacent to the beach are scoured clean by constant abrasion. A lush covering of marine algae and extensive sets of blue mussels and barnacles cover the intertidal and subtidal zones.
2	Estuarine side of the breakwater at Plum Island Point:
	This area consists of an extensive sand and gravel beach studded with large granite boulders. Currents are extremely strong, waves hit the area constantly, and the rocks are fairly well scoured. Marine organisms are only found in cracks in the rocks were they are protected from abrasion.
3	Estuarine side of the breakwater at Salisbury Beach:
	At this station large granite blocks are surrounded by the sands of Salisbury Beach. The rocks are exposed to very strong tidal currents and choppy waves. The overall appearance of the area is considerably sparser than Station 1, but mats of green algae cover the inter- tidal, and fairly large beds of blue mussels are found at low water.
4	Breakwater near Badgers Rocks:
	A breakwater of large granite rocks extend from the intertidal area out into deeper subtidal waters at this location. Coarse sand and gravel surround the rocks, which are covered by barnacles above mean water, and large

STATION	LOCATION AND DESCRIPTION
4 (con't)	sets of blue mussel and mats of filamentous green algae at low water.
5	Western bank of Plum Island River underneath the bridge connecting Plum Island to Newburyport:
	This habitat, a combination of mud banks and out-croppings of small granite rocks, is located on the Plum Island River, a tidal channel connecting the Parker River - Plum Island Sound Estuary with the Merrimack River Estuary. Beds of Spartina spp. predominate on the flats, and the rocks, all of which are coated with green filamentous algae, hold small colonies of barnacles and blue mussels.
6	Black Rock Point:
	This habitat consists of a large outcropping of rocks located throughout the intertidal and subtidal zones, surrounded by tidal creeks, mud flats, and beds of <u>Spartina</u> spp. The rocks throughout the intertidal are covered with thick mats of <u>Ascophyllum</u> and <u>Fucus</u> , and the flats, while high in H <sub>2</sub> S, support a dense population of the soft-shell clam, <u>Mya arenaria</u> .
7	Lunt Rock:
	Lunt Rock is a large granite boulder lying in the shallow subtidal flats. The top of the rock is exposed at low tide, and is covered by an extensive set of barnacles and blue mussels.
8	Morrill Creek:
	This habitat consists of a series of large granite rocks surrounded by an extensive soft-shell clam flat. The rocks are coated with silt and mud, and support few intertidal organisms.

TABLE VI (continued)

STATION	LOCATION AND DESCRIPTION
9	Joppa Flat:
	Joppa Flat is an extensive shallow mud flat located on the Newburyport side of the Merrimack River Estuary No rocks are exposed in this area, and the shallow sludge covered bottom supports large beds of blue mussels and clams.
10	Rocks just upriver from Coffin Point:
	This area is characterized by salt marsh inter- spersed with granite outcroppings. Wave action and cur- rents are minor, water looks and smells polluted, and few organisms are visible on the sludge-covered rocks.
11	Waterfront at Newburyport just west of the power generating station:
	This habitat consists of slime covered wooden pilings. No living macroinvertebrates are apparent, but the sight and smell of pollution is impressive.
12	Salisbury shoreline just upriver of the Rt. 1A Bridge:
	This area is predominantly a large <u>Spartina</u> spp. covered mud flat. The mud is soft and high in H <sub>2</sub> S, and the whole area emits a strong rotten smell. Clusters of slime-covered rocks jut out at points throughout the intertidal.
13	Shoreline across the river from Station 12:
	This habitat is a sloping gravel beach cluttered with rocks and junk. Several relatively clear freshwater springs percolate out of the sand and enter the river. With the exception of a coating of blue-green algae, the habitat is bare of intertidal organisms.
14	Twin Rocks station, on the Salisbury side of the river:
	This habitat is composed of a mixture of rock out- croppings and mud, interspersed with small patches of

## TABLE VI (continued)

STATION	LOCATION AND DESCRIPTION
14 (con't)	Spartina spp. H <sub>2</sub> S is just beneath the surface of the mud, water is brown and putrid, and little life other than blue-green algal scum is visible on the rocks.
15	North End Boat Club:
	A sloping shore composed of rocks, pebbles, and patches of <u>Spartina</u> spp. predominate in this area. All rocks are coated with blue-green algal scum, and little life is visible.
16	Station in the secondary tidal channel across from Ram Island, near Town Creek:
	This habitat consists of <u>Spartina</u> spp. flats at the upper intertidal, blue-green algal covered rocks in the intertidal, and mud at and below LW. H <sub>2</sub> S is near the surface of the mud throughout the area, and wave and current action are minimal.
17	Rocky shore across from Ram and Carr Islands:
	This habitat is primarily a large pile of rocks extending out into a fairly rapid channel. The rocks are barren except for a coating of blue-green algae.
18	Station on the rocky promontory of Ram Island:
	This station consists of blue-green algal covered rocks outcropping from Spartina spp. beds near HW and mud flats at and below LW.
19	Station in the main channel on a rocky promintory of Carr Island:
	As with the previous station, the habitat is a combination of rock outcroppings surrounded by mud flats and upper intertidal Spartina spp. beds. All rocks are covered by a thick scum of blue-green algae.

STATION	LOCATION AND DESCRIPTION
20	Station on the north side of the river across from Eagle Island:
	This habitat is composed of a series of rocky out-croppings throughout the intertidal, interspersed with anoxic mud flats and <u>Spartina</u> spp. beds. The <u>Spartina</u> spp. appeared rather unhealthy, and only a light coating of algae covered the rocks.
21	Rocky shore on the Newburyport side of Deer Island:
	This station, located at the base of the bridge, is composed of rocks in the intertidal, with patches of <a href="Spartina">Spartina</a> spp. near high tide mark. The rocks are lightly coated with blue-green algae, and H <sub>2</sub> S is close to the surface in the mud.
22	On the south shore just upriver of the Rt. 1-95 Bridge:
	This habitat is mostly sloping rocky substratum interspersed with some mud and gravel. Patches of <u>Spartina</u> spp. cover the upper-intertidal, and a light coating of blue-green algae covers some rocks.
23	Rocky promontory at Salisbury Point:
	This habitat, located in a cove at the bend of the river, is composed of rock outcroppings and scattered broken rocks throughout the intertidal, with gravel and some Spartina spp. in mud near high tide.
24	Shoreline in Amesbury between Stations 23 and the Allen B. Marina:
	This area is characterized by very anoxic and putrified mud, interspersed with junk. H <sub>2</sub> S predominates and the few rocks present are coated with muck and mud.
25	Allen B. Marina:
	A mixture of scattered rocks, sand and mud characterize this area. ${\rm H_2S}$ is just below the surface in mud, all

TABLE VI (continued)

STATION	LOCATION AND DESCRIPTION
25 (con't)	rocks are coated with scum, and raw sewage often covers the banks. Some Spartina spp. is present in the intertidal, interspersed with freshwater reeds.
26	On the north shore just upriver of the factories:
	This habitat is a rocky conglomerate shore, gently sloping into muddy water. A mixture of <u>Spartina</u> spp. and reeds is scattered on the beach.
27	On the north shore just upriver of the Seahorse Marina:
	A mixture of conglomerate and mud similar to Station 26 is found at this location.
28	On the south shore just downriver of the Artichoke River:
	A very gently sloping mud habitat, covered by a thick mat of freshwater reeds, is found at this location.
29	On the south shore between the Artichoke and Indian Rivers:
	This habitat is an all mud flat covered by a dense thicket of freshwater reeds and grasses.
<b>3</b> 0	North shore one-half mile upriver of Locust Street:
	This habitat is characterized by a mixture of scattered rocks gently sloping to the water, interspersed with gravel, sand, and mud. Freshwater plants predominate in the muddy areas.
31	South shore just upriver of the Groveland Bridge:
	This station is a typical freshwater habitat composed of scattered rocks and mud, and covered with a wide variety of freshwater plants.


## 3. Intertidal Algae and Vascular Plants:

Methods:

Collections and observations of intertidal algal and vascular plants were made throughout the Merrimack River Estuary during the summer and fall of 1971. Vascular plants were studied at 14 stations and algae was studied at 13 locations (Figure 11). Representative specimens of algae from each site were collected, processed as herbarium voucher specimens and deposited in the Herbarium of the University of New Hampshire (NHA). A deliberate attempt was made to summarize a broad "baseline" of information on species composition, distribution, and abundance of plants at each station. In addition, type and quantity of substratum available for benthic plants were noted. The nomenclature of the Second Revised British Checklist (Parke and Dixon, 1968) was applied for most taxa of seaweeds, while the Eighth Edition of Gray's Manual (Fernald, 1950) was employed for the identification and nomenclature of vascular plants.

Species Composition of Intertidal Vascular Plants at Representative Habitats Along the Length of the Merrimack River Estuary:

Thirty-seven taxa of vascular plants were found in the marshy habitat of the Merrimack River Estuary (Table VII). All except <u>Spartina</u> spp. and <u>Scirpus</u> spp. (major components of the bank community along the shoreline), were found above mean high water. Fourteen of the 37



#### TABLE VII

#### VASCULAR PLANTS OF THE MERRIMACK RIVER ESTUARY

#### AND THEIR ESTUARINE DISTRIBUTION

- Acnida cannabina L. Found in salt marshes and tidal shores.
- Acorus calamus L. (Sweet flat or Flagroot) (older name for a reed) has an aromatic rhizome. Found in wet places and borders of quiet water. (Primarily found in freshwater.)
- Ambrosia artemisiifolia L. (Ragweed). Ubiquitous distribution.
- Ammophila breviligulata Fern. (Beach grass). Found on dunes and in sandy habitats near the open coast.
- <u>Artemisia stelleriana</u> Bess. (Dusty Miller). Found on sandy beaches and dunes.
- Aster subulatus Michx. A plant of saline marshes.
- Atriplex patula L. var. hastata (L.) Gray (Orach). Found in saline, brackish or rich soils both on the coast and inland.
- Bulbostylis capillaris (L.) C. B. Clarke. A plant of dry open soil.
- <u>Cakile</u> <u>edentula</u> (Biegl.) Hook. (Sea-rocket). Found on sandy gravelly beaches and seacoast.
- <u>Carex</u> <u>salina</u> Wahlenb. A true halophyte found on saline or brackish shores.
- Cyperus filiculmis Vahl var. macilentis Fern. (Limited distribution)
- <u>Distichlis</u> <u>spicata</u> (L.) Greene. (Spike grass). Grows in saline marshes.
- Eleocharis acicularis (L.) R. & S. Commonly found on damp shores and low grounds.
- Gnaphalium obtusifolium L. (Cat foot). Typically found in dry woods, clearings and on the edges of woods.
- Hudsonia tomentosa Nutt. (Beach heath, poverty grass). Found on sandy
  areas primarily near the coast.

#### TABLE VII (continued)

- Hypericum gentianoides (L.) BSP. (Orange grass). Found in sandy, sun baked soil.
- Juncus gerardi Loisel. (Black grass). Saline areas and salt marshes.
- Lathyrus japonicus Willd. (Beach Pea). Found on sandy beaches and dunes.
- Limonium carolinianum (Walt.) Britt. (Sea-Lavender) L. or Nashii Small. Found in salt marshes almost exclusively.
- Lythrum salicaria L. (Purple loosestrife). A plant of wet areas and river floodplains. This is considered a local nuisance in many New England areas. Often outcompetes other local species at times to their exclusion.
- <u>Plantago juncoides</u> Lam. (Seaside Plantain). Mostly a maritime (shore side) species.
- Plantago oliganthos R. & S. (Seaside Plantago). Grows in salt marshes and saline or brackish shores.
- Polygonella articulata (L.) Meisn. Found in dry sandy habitats.
- Polygonum hydropiper L. Common Smartweed. Grows in damp soils.
- Potentilla egedei Warmsk. var. groenlandica (Tratt.) Polunin. Normally grows by the seacoast.
- Salicornia europaea L. (Glasswort or Samphire). Grows primarily in salt marshes occasionally found inland.
- Scirpus maritimus L. var. fernaldi (Bickn.) Beetle (Bullrush). Occurs from saline to brackish marshes and extending from brackish to freshwater (tidal) areas.
- Scirpus validus Vahl. Found in brackish or fresh shallow water and marshes.
- Sium suave Walt. (Water Parsnip). A plant of meadows, wet thickets and muddy river banks. (Primarily freshwater.)
- Solidago sempervirens L. (Seaside Goldenrod). Found in saline, brackish or even freshwater habitats near the coast.
- Spartina alterniflora Loisel. (Salt water cord grass). Grows on saline shores and marshes.

#### TABLE VII (continued)

- Spartina patens (Ait.) Muhl. (Salt meadow grass). Grows on saline marshes and brackish shores.
- Spergularia marina (L.) Griseb. Found in saline or brackish soils.
- Triglochin maritima L. (Arrow-grass). Saline, brackish or fresh marshes and shores.
- Typha latifolia L. (Cat-tail). Found in marshes as well as in shallow waters.
- Zizania aquatica L. (Wild rice). River mouths growing in fresh to brackish waters. (Found in freshwater lakes and ponds.)

vascular plants collected were widely distributed, the others were sporadic in occurrence or only collected once. A detailed description of species composition at each station is presented in Table VIII and summarized in Figure 12.

No flowering plants were found in the intertidal zone at Stations 1 through 3. However, a fairly uniform distribution of typical salt-marsh plants was apparent from Station 5 to Station 19, with Spartina spp. dominating the bank community. Species consistently present included Solidago sempervirens, Spartina alterniflora, Spartina patens, Salicornea europea, Atriplex patula and Limonium sp. Several other species occurred sporadically within the bounds of Station 5 to Station 19 (e.g., Acnida cannabina, Potentilla egedei, and Juncus geradi). Scirpus validus was collected for the first time along the river at Station 14, but not again until Stations 26 through 29. Its limited abundance at Station 14 suggests that it was probably carried downriver intact by spring floods. Scirpus maritimus var. fernaldi was collected for the first time at Station 18, and with the exception of Station 20, persisted in noticeable abundance up to Station 29.

Station 20 was characterized by a diminished salt-marsh flora.

Grazing activity (cows) may have contributed to this paucity of species.

Only four species (Spartina alterniflora, Spartina patens, Atriplex patula, and Potentilla egedei) were found at this station. This was

TABLE VIII

SPECIES COMPOSITION AND DISTRIBUTION OF CONSPICUOUS VASCULAR PLANTS OCCURING IN THE TIDAL REACHES OF THE MERRIMACK RIVER ESTUARY.

							STATIO	NS						
PLANT	4	5	6	10	11	14	18	19	20	23	27	28	29	
Triglochin maritima						х								
Artemesia stelleriana	Х	Х				Λ								
Lathyrus japonicus	X	X												
Ammophila breviligulata	X	••												
Solidago sempervirens	X	X	х	х	х	х	х	х		х	х			
Spartina alterniflora		Х	Х	Х	X	X	X	X	Х	X	X			
Spartina patens		Х	Х	Х	Х	Х	Х	Х	Х	Х	X			
Salicornia europea		Х	Х	Х		Х		Х						
Ambrosia artemisiifolia		Х	Х		Х		Х							
Plantago juncoides		Х	X											<
Atriplex patula var. hastata		X		Х	Х	Х	Х	Х	Х					.6T-A
Limonium carolineanum	•	X				Х	Х	Х						•
Lythrum salicaria			Х				Х							
Bulbostylis capillaris			Х											
Cakile edentula			Х											
Aster sp.			Х											
Plantago oliganthos			X											
Cyperus filiculmis var. maci	lentis		X											
Hypericum gentianoides			X											
Polygonella articulata			Х											
Carex salina			Х											
Hudsonia tomentosa			Х											
Gnaphalium obtusifolium			х											
Acnida cannabina				Х	Х	Х	Х			Х	X			
Potentilla egedei var. groen	landica	a		X			Х	Х	Х					

(continued)

TABLE VIII (continued)

						STATIO	NS						
PLANT 4	 5	6	10	11	14	18	19	20	23	27	28	29	
Juncus geradi			v			17							
			X			X							
Spergularia marina			Х										
Eleocharis acicularis			X										
Rannunculus sp.			X							Х			
Scirpus validus					Х				Х	Х	Х	Х	
Scirpus maritimus var. fernaldi						Х	Х		Х	Х	Х	Х	
Typha latifolia									Х	Х			
Sium suave										Х			
Acorus calamus											Х	Х	
Zizanis aquatica											Х	X	<
Polygonum hydropiper											X		-20
Aster subulatus											Х		0.
Distichlis spicata						х							

SELECTED INTERTIDAL	STATIONS  5 TATIONS  1 T
VASCULAR PLANTS	4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29
Solidago sempervirens	\$3355555555555555555555555555555555555
Spartina alterniflora	800000000000000000000000000000000000000
Spartina patens	\$5555000000000000000000000000000000000
Atriplex patula var. hastata	<b>30000000000000000000000</b>
Limonium carolineanum	XXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX
Salicornia europea	888888888888888888888888888888888888888
Acnida cannabina	XXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX
Potentilla egedei var. groenlandica	<b>5000000000000000000000000000000000000</b>
Juncus geradi	200000000000000000000000000000000000000
Scirpus validus	200000000000000000000000000000000000000
Scirpus maritima var. fernaldi	\$
Typha latifolia	8889855500
Sium suave	88
Acarus calanus	9888
Zizanis aquatica	9000

Figure 12. The distribution of selected intertidal vascular plants occurring along the Merrimack River Estuary, Massachusetts, 1971.

the last upriver station that Atriplex patula and Potentilla egedei were recorded. Scirpus maritimus var. fernaldi and Scirpus validus were again found at Station 23 and showed an increase in abundance over earlier stations. Typha latifolia, a species which occupies a niche in freshwater habitats similar to Spartina spp., was seen at Station 23 for the first time. Spartina alterniflora, Spartina patens and Acnida cannabina were still present.

sempervirens, Spartina alterniflora, Spartina patens, and Acnida cannabina were collected. Sium sauve was collected for the first time at this station in association with Typha latifolia and Scirpus validus. New associations were present at Stations 27 and 28 in the form of Scirpus validus, Scirpus maritimus, Acorus calamus, and Zizania aquatica. These four species are essentially brackish to freshwater inhabitants and represent a marked change in association away from some of the more persistent halophytes such as Spartina alterniflora, Spartina patens, Salicornea europea, and Solidago sempervirens. Both Spartina species, Salicornea sp. and Solidago sp. dropped off completely by Stations 28 and 29, probably due to a reduction in salinity.

Species Composition of Intertidal Algae at Representative
Habitats Along the Length of the Merrimack River Estuary:

A total of 31 taxa of seaweeds was collected (Table IX).

TABLE IX

LIST OF THE ALGAL SPECIES OF THE MERRIMACK RIVER ESTUARY, THEIR LONGEVITY AND DISTRIBUTION

SPECIES	LONGEVITY	DISTRIBUTION	
HLOROPHYCEAE:			
Blidingia minima (Nägeli ex Kützing) Kylin	Annual	Cosmopolitan	
Enteromorpha erecta (Lyngbye) J. Agardh	Annual	Cosmopolitan	
Enteromorpha groenlandica (J. Agardh) Setchell			
et Gardner	Annual	Estuarine	
Enteromorpha intestinalis (L.) Link	Annual ?	Cosmopolitan	
Enteromorpha linza (L.) J. Agardh	Annual	Cosmopolitan	
Monostroma oxyspermum (Kützing) Doty	Annual	Estuarine	
Pseudendoclonium marinum (Reinke) Aleem et Schulz	Perennial	Cosmopolitan	
Rhizoclonium riparium (Roth) Harvey	Annual	Cosmopolitan	
Spongomorpha arcta (Dillwyn) Kützing	Annual	Coastal*	
Ulothrix flacca (Dillwyn) Thuret in Le Jolis	Annual	Cosmopolitan*	
Ulva lactuca (L.)	Annual ?	Cosmopolitan	
Urospora penicilliformis (Roth) Areschoug	Annual	Cosmopolitan*	
HAEOPHYCEAE:			
Ascophyllum nodosum (L.) Le Jolis	Perennial	Cosmopolitan	
Ectocarpus confervoides (Roth) Le Jolis	Annual	Cosmopolitan	
Elachista fucicola (Velley) Areschoug	Perennial	Cosmopolitan*	
Fucus vesiculosus (L.)	Perennial	Cosmopolitan	
Fucus vesiculosus var. spiralis Farlow	Perennial	Estuarine	
Laminaria digitata (Hudson) Lamouroux	Perennial	Cosmopolitan*	
Laminaria saccharina (L.) Lamouroux	Perennial	Cosmopolitan*	
Petalonia fascia (O. F. Müller) Kuntze	Annual	Cosmopolitan	
Pilavella littoralis (L.) Kjellman	Perennial ?	Cosmopolitan	
Ralfsia verrucosa (Areschoug) J. Agardh	Perennial	Cosmopolitan	
Scytosiphon lomentaria (Lyngbye) Link	Annual	Cosmopolitan	

<sup>\*</sup>Documented by collections from other Massachusetts locations.

TABLE IX (continued)

			V-	24.	
DISTRIBUTION		Cosmopolitan Estuarine ? Coastal Cosmopolitan Coastal	Estuarine		Cosmopolitan ?
LONGEVITY		Perennial Annual ? Annual Annual Perennial	Perennial ?		Annual
SPECIES	RHODOPHYCEAE:	Hildenbrandia prototypus Nardo Polysiphonia fibrillosa (Dillwyn) Sprengel Porphyra leucosticta Thuret Porphyra umbilicalis (L.) J. Agardh Ptilota serrata Kützing	XANTHOPHYCEAE:  Vaucheria sp.	BACILLARIOPHYCEAE:	Amphipleura rutilans Melosira sp.

Twelve Chlorophyceae (green algae), eleven Phaeophyceae (brown algae), and five Rhodophyceae (red algae) were identified. A detailed evaluation of the Cyanophyceae (blue-green algae), Xanthophyceae (yellow-green algae), and Bacillariophyceae (diatoms) was beyond the scope of the present investigation, although some data were collected. For example, the colonial diatom, Amphipleura rutilans, was a conspicuous component at Stations 1, 6, 8, and 14, and Vaucheria sp. and various blue-green algae (primarily species of Lyngbya, Oscillatoria and Merismopedia) formed a conspicuous mat amongst Spartina roots at many stations.

Details of species composition and distribution of seaweeds are summarized in Table X. The maximum number of species was found at Stations 1, 3, and 6, and beyond Station 6 there was a rapid and progressive reduction in species numbers. Red algae appeared to be least tolerant of reduced salinities. Three of the five species dropped out at Station 3, and no red algae were found beyond Station 10. Brown algae showed a wider distribution than red algae, but even so they were not found upstream of Station 14, and their largest number of species was found at Station 3. Green algae were the most cosmopolitan of the three major groups, with Enteromorpha erecta extending to the low salinities of Station 26. The yellow-green alga, Vaucheria sp., and the green alga, E. erecta, were the most widespread of all seaweeds. Blue-green algae are probably equally tolerant to reduced

TABLE X

SPECIES COMPOSITION AND DISTRIBUTION OF CONSPICUOUS INTERTIDAL ALGAE IN THE MERRIMACK RIVER ESTUARY

						ST	ATIONS						
SPECIES	1	3	6	8	10	14	15	18	20	26	28	29	31
CHLOROPHYCEAE:													
Blidingia minima	Х	Х	х		Х	Х							
Enteromorpha erecta	X	Х	Х	Х	X	X	Х	Х	Х	X			
Enteromorpha groenlandica					Х								
Enteromorpha intestinalis	X	X	X		X	X	X						
Enteromorpha linza	X	Х	Х	Х									
Monostroma oxyspermum					X	X	Х						
Pseudendoclonium marinum	X	X	X										
Rhizoclonium riparium							X						
Spongomorpha arcta	X												
Ulothrix flacca	X		X	X									
Ulva lactuca	X		Х										
Urospora penicilliformis		X											
SUBTOTAL	8	6	7	3	5	4	4	11	1	1		·····	
PHAEOPHYCEAE:													
Ascophyllum nodosum	х	х	Х	х	х								
Ectocarpus confervoides	Х												
Elachista fucicola	Х												
Fucus vesiculosus	Х	X											
Fucus vesiculosus var. spiralis	}		Х	X	Х	X							
Laminaria digitata	- х												
Laminaria saccharina	X												
Petalonia fascia	Х												

(continued)

(continued)

TABLE X (continued)

						ST	ATIONS	· · · · · · · ·					
SPECIES	1	3	6	8	10	14	15	18	20	26	28	29	31
PHAEOPHYCEAE (continued)													
Pilavella littoralis	х		Х	х									
Ralfsia verrucosa	X	Х											
Scytosiphon lomentaria	X												
SUBTOTAL	10	3	3	3	2	1	<del>1-1-1-2-2-2</del>						
RHODOPHYCEAE:													
Hildenbrandia prototypus	Х	Х	х		Х								
Polysiphonia fibrillosa			X										
Porphyra leucosticta	X												
Porphyra umbilicalis	X												
Ptilota serrata	X												
SUBTOTAL	4	1	2		1								
XANTHOPHYCEAE:													
Vaucheria sp.			Х	х		X	Х	X	Х	Х	Х		
SUBTOTAL	***		1	_1		1	1	1	1	1	1		
CYANOPHYCEAE:													
Various blue-green algae			Х	Х		Х	Х	X	Х	Х	Х		
SUBTOTAL			1	1		1	. 1	1	1	1	1		

TABLE X (continued)

8 10 14 15 18 20 26 28	14 15 18 20 X X	14 15 18 20 X X X I I I I I I I I I I I I I I I I I	14 15 18 20  X  X  X  X  8 6 4 3
			x 1 8
	×	x 1	× 1 8
:			
2			ω
	×		
	×		1
			22
ARIOPHYCEAE:	LLARIOPHYCEAE: mphipleura rutilans elosira sp.	METOPHYCEAE:  Amphipleura rutilans  Melosira sp.  SUBTOTAL	BACILLARIOPHYCEAE:  Amphipleura rutilans  Melosira sp.  SUBTOTAL  TOTAL
	×	X X	x 1 22 11 1

•

\_

salinities, but lack of specific identifications precluded a precise evaluation.

An inspection of Table X indicates that most seaweeds (23) occurred both on the open coast and within the estuary, exhibiting a cosmopolitan distribution. Only five species (Vaucheria sp., Enteromorpha groenlandica, Monostroma oxyspermum, Fucus vesiculosus var. spiralis, and Polysiphonia fibrillosa) are considered to be truly estuarine, and were found exclusively within the estuary. Three species (Spongomorpha arcta, Porphyra leucosticta, and Ptilota serrata) appear to be coastal forms, since they were not found within the mouth of the river.

# Factors Influencing the Distribution and Abundance of Plants in the Merrimack River Estuary:

The variety and abundance of rock are major factors restricting growth and distribution of algae in the Merrimack River Estuary. The breakwater at Stations 1 and 3 provided maximum stability and surface area for the growth of seaweeds, and highest species diversity and biomass of algae were found at these two sites. The reduced biomass and species diversity upstream of Station 3 can be attributed, at least in part, to unsuitable substratum. Most rocks upriver of this station were mud covered, and it is obvious that films of mud and silt will inhibit the attachment and growth of many algal species. In addition, small cobbles and pebbles, characteristic of upriver stations, are

unsuitable as substrata for many larger plants because of their instability. Only crustose algae (e.g., <u>Hildenbrandia prototypus</u> and <u>Pseudendoclonium marinum</u>) were found on such rocks. <u>Vaucheria sp., Enteromorpha spp.</u>, and various blue-green algae were the only forms collected on the muddy surfaces stabilized by the roots of <u>Spartina alterniflora</u> and <u>Spartina patens</u>. The <u>Spartina spp.</u> appear to play an important role in the formation of substrata suitable for algal colonization by such species.

In contrast, the rocky substratum at Stations 1 and 3 was not suitable for attachment and colonization of estuarine vascular plants, and progressive increases in species diversity of estuarine vascular plants was observed in relation to a decrease in the amount of rocky substratum upstream. Therefore, an increase in biomass and species diversity of vascular plants upriver can be attributed to suitable substratum, including small rocks and fibrous peat. Maximum species diversity occurred at Stations 18, 19, and 20. Beyond this point the reduction in species number (but not biomass) probably resulted more from sub-optimal hydrographic factors than from suitability of substrata. At these stations four vascular plants (Scirpus

<u>validus</u>, <u>Scirpus</u> <u>maritimus</u>, <u>Acorus</u> <u>calamus</u>, and <u>Zizania</u> <u>aquatica</u>) accounted for nearly all the plant biomass.

Spatial and temporal variations of hydrographic factors in the Merrimack River Estuary, particularly the low upstream salinities, restrict the longitudinal distribution of many species. Species having limited tolerances to temperature and salinity changes would not be expected to migrate upstream for any distance. As suggested earlier, Spongomorpha arcta, Porphyra leucosticta, and Ptilota serrata have a distinctly coastal distribution, and they did not extend inland of Station 1. Other species exhibited gradations of tolerances to temperature and salinity fluctuations within the estuary. The most tolerant ones exhibited the widest distributions (e.g., Enteromorpha erecta and Vaucheria sp.) while the less tolerant ones had limited estuarine distributions (e.g., Elachista fucicola and Petalonia fascia). The most conspicuous reduction in species diversity occurred between Stations 6 and 8, probably caused by the greater fluctuations of temperature and salinity and the limited amount of solid substrata.

Pollution is often an important limiting factor in algal distribution and abundance. A comparison of species composition of seaweeds from the Merrimack River Estuary with that of the Hampton-Seabrook Estuary (Mathieson and Fralick, In Press) and the Great Bay Estuary Systems (Mathieson, Reynolds, and Hehre, In Press) of New Hampshire indicates a paucity of species in the Merrimack. A total of 118 taxa

of seaweeds was collected from the Hampton-Seabrook Estuary and adjacent open coast, while over 150 species were found within the vicinity of the Great Bay Estuary System. The low species diversity (only 28 taxa) from the Merrimack River Estuary is in part due to the extreme domestic and industrial pollution of this interstate river. The concept of species diversity has been applied extensively in evaluating eutrophication of freshwater habitats. In general, a decrease in species diversity is a typical response to an increase in either domestic and/or industrial pollution. Under polluted conditions, a few tolerant species tend to dominate in large numbers and high biomass. The abundance of many Ulotrichalean green algae (e.g., Enteromorpha spp., Ulva lactuca, and Monostroma sp.) typifies a polluted estuarine habitat. The latter species are not only tolerant of extremes in pollution, but to gross fluctuations in hydrographic factors.

# Possible Effects of Freshwater Diversion on Plants of the Merrimack River Estuary:

Little information is available concerning the optimal growth requirements of both seaweeds and higher plants, but it is generally assumed that juvenile stages are more sensitive to environmental changes than adult stages. Salinity is known to affect both growth and reproduction of marine plants, and it has been shown in certain species (i.e, Porphyra sp.) that germlings require low salinities (15 to 20 %)oo) while adult plants grow best in higher salinities.

Low salinities can increase the respiration rate of plants and subsequently reduce their net photosynthesis (i.e., growth) and their reproductive success.

The net effects of higher salinities are not as well documented, but most studies indicate a broad tolerance to them, at least within the range expected to occur from a freshwater diversion. It would seem that the effects of increased salinities would be minimal on marine plants during both reproduction and growth of juvenile stages, but it is difficult to evaluate the effects of increased salinities on cosmopolitan species such as <a href="Porphyra">Porphyra</a>, which reproduce best under low salinities. In addition, estuarine species that actually require a fluctuating temperature and salinity regime may not be able to reproduce effectively if this fluctuation is reduced.

As suggested previously, marine and estuarine plants vary in their tolerance to reduced salinities. Hence, those species which are euryhaline are the most widespread in an estuary, while stenohaline species are limited in distribution. One of the most obvious results of a freshwater diversion from the Merrimack River could be an alteration of the delicate balance between freshwater, brackish water, and marine organisms, evidenced by changes in distribution and abundance of species. An increase in salinity would no doubt allow the upstream movement of marine or estuarine algae such as <a href="Ascophyllum nodosum">Ascophyllum nodosum</a> and Fucus vesiculosus, and subsequently alter the composition and

dominance of algal species in a locale. Typically estuarine vascular plants such as <u>Spartina alterniflora</u>, <u>Spartina patens</u>, <u>Salicornea</u> europea, and <u>Solidago sempervirens</u> would also extend their distribution further upriver, probably at the expense of freshwater species such as <u>Scirpus validus</u>, <u>Scirpus maritimus var. fernaldi</u>, <u>Acorus calamus</u>, and <u>Zizania aquatica</u>.

It would seem that the true estuarine species would be the most vulnerable to increased salinities. Preliminary studies (unpublished data, A. C. Mathieson) suggest that several species, among them Monostroma oxyspermum, Polysiphonia fibrillosa, and Polysiphonia elongata, actually require low salinities. Comparable data is known for some shellfish (e.g., oysters), where mass mortalities have been recorded in association with alterations of salinities.

Secondary effects of such shifts in species distribution are difficult to predict. It is possible that alterations of photosynthetic productivity or disappearance of specific hosts for epiphytes and epizooans may result. As an example, the survival ability of several fish and invertebrates may be altered by a change in the Typha latifolia populations of brackish water locations. An increase in salinities might kill off this species, and limitations of other parameters such as pollution may not allow its re-growth upriver. Hence, the associated fauna could be eliminated because of loss of the primary host.

It is conceivable that other changes in plant communities may be initiated by associated effects of freshwater diversion such as alterations of current flow and velocity, changes in sediment transport and patterns of deposition, reduction of seasonal temperature variation, and changes in pollution load. Alterations of current flow (velocity) would no doubt be associated with differential transport of sediments, and a reduction of silt and mud deposition upriver may provide a greater availability of solid substrata for algal attachment. In addition, a reduction of turbidity would extend the depth of the photosynthetic zone, and contribute to a greater diversity and biomass of plants throughout the estuary. Plant communities could also be affected by changes in distribution of sand throughout the estuary. At present, sand is not evident beyond Station 4, and it is possible that with reduced flow more sand may be moved upriver. Differential communities of plants and animals are found in sandy versus muddy habitats, and some plants, specifically Ahnfeltia plicata (a psamophytic species), thrive in sandy habitats. Plants such as these might be introduced if a major alteration of substratum occurred. This, however, is not likely.

Changes in temperature may also affect plant communities. The water temperatures of the Merrimack River Estuary result, at least in part, from the mixing of freshwater and salt water. Differential temperatures of the two bodies often result in intermediate temperatures, as well as cold and warm extremes, and these

pronounced seasonal variations of temperature in the Merrimack River Estuary are correlated with major fluctuations in plant populations. Thus, the flora is heterogeneous and it is composed of both cold (boreal) and warm (temperate) water components. Any major alteration of temperature could change the composition of the vegetation, particularly the annual components.

#### 4. Intertidal Invertebrates:


Methods:

Collections and observations of conspicuous intertidal invertebrates were made at selected sites (Figure 11) throughout the Merrimack River Estuary during high and low flow periods of 1971. To develop a broad overview of the intertidal zone from open ocean to freshwater, 29 stations were sampled during the spring (Stations 1 through 26, and Stations 30 and 31). This number was reduced to 12 representative stations during the fall (Stations 1, 3-6, 10, 14, 18-20, 23, and 27). Emphasis was placed on the invertebrates of rocky habitats, although organisms from other types of substrata adjacent to the rocks were also studied. Where positive field identification was not possible, the organisms were collected, preserved, and returned to the laboratory.

Species Composition of Intertidal Invertebrates at Representative Habitats Along the Length of the Merrimack River Estuary:

Forty-seven species of invertebrates representing six phyla were collected in the Merrimack River Estuary during the sampling period (Table XI.). Sixteen of these species were found only outside the estuary where physico-chemical conditions approximate the oceanic environment. Twenty-six species were found within the estuary where extreme hydrographic fluctuations occur. Five species were restricted

TABLE XI. SPECIES COMPOSITION AND DISTRIBUTION OF CONSPICUOUS INTERTIDAL INVERTEBRATES IN THE MERRIMACK RIVER ESTUARY - 1971.



to the freshwater habitat. Of the 26 species living within the estuary, 19 are euryhaline marine organisms found also in marine environments, four are true estuarine organisms found exclusively in the estuarine environment, and three are freshwater species capable of withstanding periodic low level salinities.

The maximum number of species was found at Station 1, a typical open ocean rocky habitat (Figure 11), where 24 species were collected throughout the study period. Sixteen of those species were stenohaline marine forms such as Strongylocentrotus droehbachiensis and Asterias vulgaris, while the remaining ones were euryhaline marine organisms. This habitat was dominated by extremely abundant sets of Mytilus edulis and Balanus spp., and large numbers of their predators, Thais lapillus. Littorina littorea was extremely abundant in the mid-tidal zone, as was L. saxatilis in the upper intertidal. Large numbers of small Asterias vulgaris, Dendronotus frondosus, and several species of gammarids predominated in the tide pools, and extremely abundant populations of Mesodesma arctata lived in the sand surrounding the rocks.

Even though marine conditions predominate at Station 3 through 6 during much of the year, no stenohaline marine species were found at these locations. This is probably due to the lethal effects of periodic low salinities during flood periods. Seven to 13 euryhaline marine species were found on the rocky substratum. Extensive beds of Mytilus edulis, moderate sets of Balanus spp., and large numbers

of Gammarus oceanicus living under the rocks predominanted. Thais lapillus, a species which preys upon Mytilus and Balanus, was scarce at Stations 2 and 3, and did not extend beyond Station 4.

Euryhaline marine organisms continued to predominate from Stations 7 through 10, but showed a steady decline in both species numbers and abundance with upriver progression. Balanus spp. and Mytilus edulis were extremely abundant at Stations 6 and 7, but Balanus spp. abundance dropped drastically beyond this point, and M. edulis was scarce at Station 10. Littorina saxatillis was not found beyond Station 8, and other euryhaline marine species such as M. edulis and L. littorea were last seen at Station 10.

The invertebrate community between Stations 12 and 17 differed from all previous locations in that species diversity was extremely low, estuarine organisms dominated, and the fauna was found not on the surface of the rocks, but rather under them. This community was characterized by large numbers of gammarids (primarily G. tigrinus) and oligochaetes living on the surface of the mud, and an abundance of Nereis diversicolor in mud tubes. Only five species of marine organisms extended beyond this point. One species, Jaera marina, was present during both spring and fall, while Balanus spp. spat and three species of amphipods were only found during the fall, having migrated into this region during the higher salinities of late summer.

Estuarine species continued to dominate the community beyond Station 17, but in association with an increasing number of salt tolerant freshwater species. As at previous stations, the community was composed of large numbers of <u>G. tigrinus</u>, oligochaetes, and <u>N. diversicolor</u>. Balanus improvisus, the only remaining marine species, was last found at Station 19. Physa sp., a freshwater snail, appeared for the first time at Station 10; the freshwater hydroid, <u>Cordylophora lacustris</u>, was first found at Station 19; and <u>G. fasciatus</u>, a salt tolerant freshwater amphipod, replaced the estuarine <u>G. tigrinus</u> beyond Station 21.

The intertidal invertebrate community beyond Station 21 can best be described as being an impoverished freshwater association. This probably results from a combination of high pollution and periodic low level salt intrusion. It was composed exclusively of high numbers of both oligochaetes and G. fasciatus living in the anoxic muck under rocks. Nereis diversicolor did not extend upriver of Station 22, and the last remaining estuarine species, Cyathura polita, was present in low abundance under rocks up to Station 29.

Beyond Station 30 species diversity increased significantly, and the community consisted of typically freshwater organisms.

# The Relationship of Salinity to the Present Distribution of Intertidal Invertebrates in the Merrimack River Estuary:

A thorough examination of the distribution of intertidal invertebrates in the Merrimack River Estuary reveals a definite progression of invertebrate associations extending from the open ocean to the freshwater river. No definite boundaries exist which could serve to separate one association from the next, but for the purposes of discussion, these associations and their locations in the river can be roughly classified as follows (Figure 11):

Marine Open ocean (Station 1)

Euryhaline marine 0-1 miles upriver (Stations 2-6)

Estuarine 1-5 miles upriver (Stations 7-21)

Impoverished freshwater 5-9 miles upriver (Stations 22-29)

Freshwater Above 9 miles (Stations 30+)

The nature of these associations, and the manner in which salinity
may determine their development at a particular location in the estuarine
system are discussed below.

A study of the intertidal habitat in the Merrimack River Estuary provides an illustrative example of the effects of adverse environmental conditions on two broad groups of organisms, the marine invertebrates and the freshwater invertebrates. Organisms in both of these groups are generally best adapted for living in a relatively stable environment,

and come under increasing physiological stress as physico-chemical conditions fluctuate from the optimum. Since the majority of marine and freshwater species are particularly intolerant of major fluctuations in salinity, highest species diversity in these two groups in an unpolluted estuarine system would be found in the open ocean and in the freshwater river, respectively, where the salinity is uniformly high or uniformly absent throughout the year.

The situation within an estuary is entirely different. Here physico-chemical conditions fluctuate significantly, and salinities cover the broad spectrum from salt to freshwater. Failure to osmoregulate and/or tolerate flucutations in body fluids is most important in restricting many intertidal invertebrates from this habitat, and thus the estuary proper in inhabited by associations of species that have varying degrees of tolerance to salinity fluctuations.

Usually the number of true estuarine species, i.e., those found only in estuaries, is low. The remaining organisms in an estuarine community are either marine or freshwater species that have developed a limited ability to survive sub-optimal salinities.

The marine association found at Station 1 contained the highest number of species found at any location in the estuary, and approximately 75% of these species were stenohaline. Hydrographic conditions in this area are relatively constant, and all 24 species inhabiting

this area are characteristic of the oceanic environment. However, the freshwater habitat at and above mile 11 (Station 30+) contained a relatively low number of invertebrates (seven), all of them typically freshwater species. While this number is higher than in the upriver stations subject to low level salt intrusion, it is well below expectations for an unpolluted river. Probably the combined pollution effects, including low oxygen and constant silting, have acted to eliminate all but the pollution tolerant species.

The euryhaline marine association found from the mouth of the estuary to approximately one mile upriver (Stations 2 through 6) is in reality an attenuated extension of the open ocean community found at Station 1. All organisms living in this region are generally found in the oceanic environment, but in contrast to the stenohaline forms found at that habitat, these organisms are capable of surviving under periodically reduced salinities. This environment, however, does not support any true estuarine species.

In the estuarine zone extending from mile 1 through approximately mile 5 (Stations 7 through 21), five species of true estuarine invertebrates are found in association with a variable number of euryhaline marine and salt-tolerant freshwater species. Progressing upriver,
the euryhaline marine organisms rapidly drop out, and the associtation becomes dominated by the true estuarine species. Salinity fluctuations in this

area are drastic, and may change from below 5 %/oo at ebb tide to well above 25 %/oo on the flood. Species diversity in this environment is usually lower during months of high river discharge, and increases as river flows drop in late summer and early fall. At this time motile euryhaline marine species, including spat of sessile forms, may migrate into the area, producing a noticeable increase in species numbers. For example, during the 1971 sampling, young Mytilus, Balanus, Littorina, and Gammarus oceanicus moved considerable distance upriver. In fact, Balanus sp. spat had successful sets nearly three miles beyond the limits of the spring distribution. It is likely, however, that these species will not be able to establish themselves permanently, but rather will be eliminated during the next flood period.

The estuarine fauna becomes progressively reduced from miles 5 through 9 (Stations 21 through 29), and increasing numbers of salt tolerant freshwater species begin to appear. Salinities are too low for most estuarine species, and periodically too high to permit establishment of freshwater species. In addition to the effects of salinity, most species in this habitat suffer from pollution induced oxygen deficiency and loss of suitable substratum due to silt and sludge deposition. Because of the severity of environmental conditions, this region presently contains the most unsuitable intertidal habitat in the Merrimack estuarine system.

Species diversity increases in the freshwater zone beyond mile 8 (Stations 30 and 31), but it is well below that found in other rivers of comparable size (Oldaker, 1966). This low species diversity is probably due to the effects of gross pollution, for the area is not affected by salinity intrusion.

# Potential Effects of Freshwater Diversion on the Intertidal Invertebrates of the Merrimack River Estuary:

A complex interaction of physical, chemical, and biological factors operates to establish the existing pattern of invertebrate distribution, and it is probable that four changes resulting from diversion could significantly effect the ecology of the intertidal habitats of the Merrimack River Estuary. These are an increase in salinity, a fluctuation in pollution, a reduction in sedimentation, and shifts in intertidal floral distribution. These changes would probably result from a continuous diversion scheme, rather than from diversion only during periods of high flow. Each possible change can best be evaluated by discussing separately the effects, where applicable, on each invertebrate association found along the length of the estuary.

The stenohaline marine association at Station 1 should not be affected in any manner by freshwater diversion, since the habitat presently is under little influence from the estuarine environment. The area is exposed to open ocean salinities throughout most of the

year, is little affected by the gross pollution from the Merrimack River, and already has a stable, well developed marine flora.

Some changes in species composition, however, may occur in the euryhaline marine zone extending from the end of the breakwater upriver to approximately mile 1. It is likely that with an increase in salinity there will be a net migration of several additional marine species into the area, and an increase in abundance of some marine species already there. Probably the most conspicuous of the migrants would be Thais lapillus, which is presently found in low abundance just inside the breakwater, but does not extend upriver of Station 4. If salinity increase results in an increase in abundance of Mytilus and Balanus, it is probable that Thais could become well established in the estuary. Other marine organisms may also move into this part of the estuary from outside the breakwater, but an introduction of these species should not lead to interspecific competition, since they presently exist outside the estuary.

More significant changes could occur in the estuarine zone extending from miles 1 to 5, but the net effect of these changes would undoubtedly be to increase the total number of species. There should be a net upriver migration of several species through the length of the estuary. In the lower estuary, this shift could bring euryhaline marine organisms into the area now occupied by estuarine species, and

could result in possible interspecific competition. For example, Nereis virens is a clamworm living in euryhaline marine mud flats, and Nereis diversicolor occupies a similar niche in the estuarine zone. It is probable that with salinity increase Nereis virens could extend its distribution into the habitat now occupied by Nereis diversicolor, and physiological stress and competition for habitat could lead to the elimination of the latter species. Similarly, Gammarus oceanicus, a euryhaline marine amphipod, may migrate upriver into the area now inhabited by G. tigrinus, its estuarine counterpart, and one species may be eliminated through physiological stress or competition. The tendency of G. oceanicus to extend its range was evidenced between the spring and fall of 1971, when it migrated more than four miles upriver under the influence of late summer increased salinities. As will be discussed in a later section, it is also possible that clam predators such as the green crab, moon snail, and horseshoe crab could migrate onto the clam flats that are presently free from predators, leading to increased clam predation. In addition, if algal and vascular plant growth is enhanced either through increased salinities or decreased sedimentation as has been suggested in an earlier discussion, it is probable that intertidal invertebrates now feeding or living on these plants in the lower zones will move into this area to fill the newly established niche.

Changes may also occur in the upper estuary. Some salt tolerant

freshwater species such as Physa sp. and Cordylophora lacustris, now present in low abundance in the upper reaches of the estuarine zone, may shift further upstream with increased salinity. It is also possible that Gammarus fasciatus, the freshwater amphipod that presently replaces Gammarus tigrinus above Station 21, may be displaced further upriver.

Any change in the impoverished freshwater zone extending from miles 5 to 9 will probably be beneficial. This zone is now in a serious state of ecological stress due to a combination of pollution and low level salt intrusion. A decrease in discharge would probably permit migration of some estuarine species into this area, but should have little effect on the few salt tolerant freshwater species existing there in low abundance, since they presently are found in higher salinities downriver. If diversion is preceded by a decrease in pollution, accompanied by an increase in oxygen and lowering of sedimentation, a further enrichment of the fauna in this habitat would result.


Since the salt water, after diversion, would not intrude beyond the limits presently reached, no migration of estuarine organisms into the freshwater zone is possible. However, a decline in pollution and lowering of sedimentation should increase the diversity of the freshwater fauna.

#### C. SUBTIDAL BENTHIC INVERTEBRATES

Free swimming invertebrates and most finfish are able to migrate when adverse environmental conditions arise.

However, infaunal invertebrates (invertebrates living in or associated with bottom sediments) are restricted in movement and therefore must be able to withstand changing conditions in order to survive. In the open ocean the benthic environment is relatively free from drastic physical changes, and substantial numbers of infaunal species are found in this habitat. In an environment such as an estuary, where dramatic physical and chemical changes occur within each tidal cycle and throughout the year, the number of species able to survive is considerably less (Gunter, 1961). In view of these circumstances, many of these organisms are living at the limits of their physiological tolerance, and any additional stress, such as that associated with pollution, may eliminate all but the hardiest.

Benthic organisms can often be utilized as important indicators of ecological imbalance or stress. Therefore, subtidal benthic sampling was conducted to determine the species composition and distribution of this biological component of the Merrimack River Estuarine environment (Figure 13).



### 1. Methods

Using a Van Veen grab, three samples were taken during August, 1971 in midchannel at each of the eight locations along the length of the tidal estuary from Route 113 Bridge in Groveland to the open ocean beyond the Plum Island Breakwater (Table XII). The samples were placed in large plastic bags, labeled, and returned to the laboratory where they were sieved through a standard sieve series. The organisms retained by the sieves were preserved in 70% alcohol and later identified. Sediment samples were also collected at each station and readings of depth, temperature, and conductivity were recorded.

#### 2. General Results

Sediments in the region of saltwater influence (Stations 1 through 6) were composed primarily of gravel, mixed with lesser amounts of pebbles and small stones, while sediments collected at the two freshwater stations (Stations 7 and 8) were much less homogeneous, ranging from pebbles and gravel to fine sand and silt (Table XIII) Hartwell (1970) found similar sediment composition in the estuary channel.

Eighteen species of bottom invertebrates were found during the sampling period, but only fifteen were collected alive. Of these fifteen species three were marine, three were true estuarine, and the

V-53.

## TABLE XII

## ECOLOGICAL STUDY

## MERRIMACK RIVER ESTUARY - MASSACHUSETTS

## BENTHIC STATION DESCRIPTIONS

STATION *	DESCRIPTION
1	In channel outside of Plum Island breakwater
2	In channel off Badger's Rocks
3	In channel off Morrill Creek
4	In channel off Coffin Point
5	In channel halfway between Eagle and Carr Islands
6	In channel halfway between entrances of Artichoke and Indian Rivers
7	In channel just upriver of Rocks Bridge, West Newbury
8	In channel just upriver of Groveland Bridge

<sup>\*</sup>see map, Figure 13, page V-51.

V-54.

## TABLE XIII

## ECOLOGICAL STUDY

## MERRIMACK RIVER ESTUARY - MASSACHUSETTS

## PREDOMINANT BOTTOM SEDIMENT CHARACTERISTICS AT BENTHIC STATIONS

	DEPTH	CHARACTERISTIC
STATION *	(In Feet)	BOTTOM TYPE
1	18'	Gravel
2	24'	Gravel
3	20'	Gravel
4	16'	Gravel & Pebbles
5	15'	Gravel & Pebbles
6	22'	Gravel & Pebbles
7	10'	Pebbles, Coarse Gravel
		Sand and Mud
8	11'	Rock through Mud

<sup>\*</sup>see map, Figure 13, page V-51.

remainder were typically freshwater species. The largest number of species found at Stations 7 and 8, both freshwater stations. No living organisms were collected at three of the estuarine stations, and diversity was extremely low at the remaining stations (Table XIV).

#### 3. Analyses According to Sampling Stations

STATION NO. 1: This site is located well beyond the mouth of the estuary, and is under influence of open ocean water for a considerable portion of the year. Salinities range upward from 30 °/00 and the habitat is subject to extreme turbulence at various portions of the tidal cycle, with sediment composed primarily of coarse gravel.

Only one species, the marine bivalve <u>Mesodesma arctata</u>, was collected. Abundance was extremely high, with as many as 130 specimens from several age classes found in one sample. Some indication of the severity of bottom conditions can be seen from the observations that this bivalve is usually found in abundance on surf beaches such as those of Salisbury Beach and Plum Island.

STATION NO. 2: Sediments are similar to those found at Station 1, but salinity variation is somewhat greater, especially during periods of high river flow.

Only two species were collected at this site. Large Mesodesma

OCCUMENCATION TARE TO THE STATE OF THE STATE

## TABLE XIV

## ECOLOGICAL STUDY

## MERRIMACK RIVER ESTUARY - MASSACHUSETTS

## Distribution and Abundance of Subtidal Benthic Animals

				STAT	CIONS				SALINITY
SPECIES	1	2	3	4	5	6	7	8	RANGE
Annelida									
Oligochaetes		1		L.			x	x	?
Nereis diversicolor				Х					Estuarine
Leech #5			<u> </u>					Х	Freshwater
Mollusca									
Mytilus edulis		X							Marine
Mesodesma arctata	X	X							Marine
Pisidium sp.							Х	Х	Freshwater
Ligumia sp.		T						Х	Freshwater
Sphaerium sp.							Х	Х	Freshwater
Mya arenaria*			Х						Marine
Physa sp.	.							Х	Freshwater
Ferrissia sp.*									Freshwater
Gyraulus sp.*									Freshwater
Amnicola sp.								Х	Freshwater
Helisoma sp.		<u> </u>	ļ					Х	Freshwater
Arthropoda			1						
Cyathura polita				х			x		Estuarine
Gammarus tigrinus				Х			Х		Estuarine
Gammarus fasciatus								х	Freshwater
Haustorius canadensis				х					Marine

<sup>\*</sup>Collected dead.

were found in low abundance in two grabs, with no small individuals present. One individual of <a href="Mytilus edulis">Mytilus edulis</a> was also collected.

STATION NO. 3: No living macro-organisms were found in the coarse gravel at Station 3, although Oldaker (1966) found two species, Mya arenaría and Nereis sp., living in the fine sediments inshore from this location. Salinities in this area have a wide range from above 30 °/oo to below 5 °/oo.

STATION NO. 4: Salinities at this station have a range similar to those observed at Station 3. Three estuarine species (the polychaete, Nereis diversicolor; the isopod, Cyathura polita; and the amphipod, Gammarus tigrinus) and one marine species (the amphipod, Haustorius canadensis) were collected. Oldaker (1966) reported two of these species, Nereis sp. and G. tigrinus, plus specimens of Mytilus edulis.

STATION NO. 5: No macro-organisms were collected from this station, although Oldaker (1966) reported two estuarine species, Cyathura polita and Gammarus tigrinus, in the vicinity. Both of these species are tolerant of the extreme fluctuations in salinity occuring in the area.

STATION NO. 6: Water in this area is fresh for a considerable portion of the year, but sufficient salt intrusion occurs during periods

of low flow to restrict the establishment of freshwater organisms.

No living macro-organisms were found, and Oldaker (1966) reported only a few specimens of <a href="Cyathura polita">Cyathura polita</a> in the vicinity.

STATION NO. 7: The habitat at Station 7 is characterized by sediment of various grades from mud to coarse gravel, and while predominately freshwater, is subject to low level salt intrusion during periods of reduced flow. At least five species of benthic organisms were found in this habitat. Two of them, Pisidium sp. and Sphaerium sp., are small, relatively pollution tolerant freshwater bivalves that are present at various points along the length of the freshwater river. Large numbers of very small oligochaetes were also found, but it has not been possible to identify them. In addition, two estuarine species, Cyathura polita and Gammarus tigrinus, were collected in low numbers in all grabs.

Oldaker (1966) found five species in bottom samples taken from this region. The estuarine species, <u>Cyathura polita</u> and <u>Gammarus tigrinus</u>, were present in moderate abundance, as were two species of freshwater midgeflies and a species of sludgeworm.

STATION NO. 8: The habitat at Station 8 has no characteristic bottom type, but ranges from rock to gravel and sand into silt and mud.

We have no record of saline water ever reaching this region of the river.

At least nine species of invertebrates were found, most being pollution tolerant freshwater species. The estuarine amphipod,

Gammarus tigrinus, has dropped out and been replaced by Gammarus

fasciatus, and the number of freshwater molluscan species has increased from two at Station 7 to six at Station 8. Three of these molluscs are bivalves, and three are gastropods. Only one species of leech was found at this station, although leeches were quite abundant at intertidal stations in the vicinity.

oldaker (1966) found eight species of invertebrates in bottom samples taken from this region, all of them freshwater species with the exception of Mya arenaria, which is without question a mistaken identification. Of the seven valid species, one was the bivalve Pisidium, three were pollution tolerant midgeflies, two were leeches, and one a sludgeworm.

# 4. Discussion

It is obvious from the above descriptions that the benthic fauna of the Merrimack River Estuary is extremely limited. Old-aker (1966) came to similar conclusions, finding only eight species from 24 stations along the same length of river. This

condition is probably brought about by a combination of five interrelated factors: 1) the prevalance of a mixed gravel/pebble substratum; 2) the occurrence of widely fluctuating and rapidly changing
salinities throughout the estuary; 3) the high pollution load resulting from industrial and domestic sewage; 4) turbulence; and 5) scouring.

While large numbers of species of marine and estuarine epifaunal organisms are generally found in rocky habitats in the shallow subtidal zone (Oldaker, 1966), and smaller but still substantial numbers of infauna are found in submerged mud and sand flats, species diversity is generally low in habitats composed of mixed pebbles and gravel (Southward, 1965). The presence of pebbles and gravel indicates currents and waves sufficiently strong to disturb the substratum and remove all fine components. Conditions for survival are severe in regions where the sediment is subject to this frequent disruption, and few organisms are able to adapt to this environment.

Of the organisms that can survive a shifting substratum, many are restricted from the Merrimack River estuarine habitat by the widely fluctuating and rapidly changing salinity. Animals are able to maintain themselves in this type of environment either because they can regulate the concentration of their body fluids independently of the environment (i.e., they can osmoregulate), or because they can tolerate rather large changes in the concentrations of their body fluids. Most

invertebrate species cannot do either, thus the fauna in areas of wide salinity variations is usually limited when compared with marine environments (Potts and Parry, 1963).

As important as the salinity changes in reducing species diversity is the effect of high pollution load, with resulting anaerobic conditions in the sediment and low oxygen tension in the overlying waters (Patrick, 1949). Few species can survive under such conditions. The relatively low diversity at Station 8, where salt intrusion does not occur and where a variety of substrata are found substantiates this.

Because a low benthic species diversity was found throughout the estuary resulting from a combination of factors, it is difficult to hypothesize on the effects of diversion. The existing maximum upriver intrusion of salt water will not change, so unless abatement of pollution produces more optimum conditions, an increase in species in the freshwater zone should not occur. However, the portion of the estuary now subject to salt intrusion will be saline more often, probably resulting in a net upriver migration of some estuarine and marine species, particularly those with larvae now existing as plankton in the Merrimack River Estuary. The extent of the upriver migration cannot be predicted at this time.

#### D. PLANKTON

Plankton studies are important for several reasons. Except for microbes, plankton are the most abundant group of organisms in the estuarine environment. In addition, they constitute the base of food chains upon which larger organisms depend, and any change in their distribution and/or abundance will affect higher trophic levels. Furthermore, a knowledge of the longitudinal distribution of meroplankton (organisms which are temporarily planktonic) under varying river discharges, correlated with some knowledge of the salinity tolerances of the adults, can be used to predict the potential upriver migration of intertidal and subtidal invertebrates after diversion.

The objectives of this study were to describe present plankton associations within the Merrimack River Estuary, and to predict possible changes in these associations as a result of river diversion. In addition, a brief discussion of possible secondary effects of changes in plankton assemblages is presented.

## 1. Methods:

During April and October of 1971 surface and near-bottom plankton samples were collected on the flooding tide with a Clarke-Bumpus sampler equipped with a #20 mesh net. Selection of sampling sites during each sampling event (i.e., spring and fall) depended on prevailing salinities and thus on flows. Efforts were made to sample representative marine, estuarine, and freshwater habitats. Spring samples were taken at Stations 1, 3, 4, and 5, while fall samples were collected at Stations 2, 4, 5, 6, and 7. Temperature, depth, and conductivity were measured at each station with a Martek TDC Meter, periodically calibrated with a Beckman Salinometer (RS 5-3). Samples were preserved in neutralized formalin and later analyzed for species composition (Figure 14.).

#### 2. Results:

Twenty-two species, five genera, and at least seven higher taxa were identified from the spring plankton (Table XV). The phytoplankton was composed chiefly of diatoms, although dinoflagellates and chlorophytes were also present. All major phyla were represented in the zooplankton, with the calanoid copepods of the phylum Arthropoda numbering higher than other taxa. Approximately 65% of the zooplankton were holoplanktonic, spending their entire life cycle as plankton; the remainder were meroplankton or temporary plankton.

Diversity was greatest in the lower estuary (Station 3) where at least 20 distinct taxa were collected, and gradually decreased upriver. Only nine distinct taxa were collected at Station 5, the freshwater station. Species abundance at Station 1, just outside the estuary, was intermediate and similar to that of Station 4




TABLE XV

SEASONAL DISTRIBUTION OF PLANKTON IN THE MERRIMACK RIVER ESTUARY, 1971

	STATI	ONS	GEOGRAPHICAL	
SPECIES	SPRING	FALL	DISTRIBUTION	
CHRYSOPHYCEAE:				
Coscinodiscus sp. Thalassiosira gravida	1,3,4,5 1, 3	2,4,5	Cosmopolitan	Euryhaline
Thalassiosira nordenskiodii	3			Benthic
Fragillaria islandica	1,3,4	6, 7		Benthic Fresh, Benthic
Fragillaria crotonensis Chaetoceros debilis	1, 3	0, /		riesh, benchic
Chaetoceros convolutus	3			
Thalassiothrix nitzschioides Thalassiothrix fraunfeldii	1,3,4	6, 7		Fresh
<u>Isthmia nervosa</u> Asterionella japonica	3 3, 4	2,4,5		Euryhaline, Benthic Euryhaline to low brackish
Melosira moniliformis	4			Euryhaline, Benthic
Detonula confervacea	4			
Rhizosolenia sp. Navicula sp.	4 5			
THE TOTAL OF THE T	-			
PYRROPHYCEAE:				
Ceratium longipes	1, 3	2,4,5		Euryhaline
Ceratium fusus	3	2,4		Euryhaline
<u>Ceratium tripos</u> Ceratium bucephalum		2,4,5 2		Euryhaline Marine
Peridinium depressum	1,3,4	2,4,5	Cosmopolitan	Euryhaline
	2,0,1	_, _, _	-	
CHLOROPHYCEAE:				
Vorticella sp.	3,4,5			

(continued)

TABLE XV (continued)

	STATI	ONS	GEOGRAPHICAL		
SPECIES	SPRING	FALL	DISTRIBUTION		
CHLOROPHYCEAE (continued)					
Closterium moniliferum		6,7		Freshwater	
Pediastrum bivae	4	5,6,7		Fresh	
Staurastrum dorsidentiferum		6, 7		Fresh	
CYANOPHYCEAE:		6,7	•	110311	
PROTISTA:		0,1			
Tintinnids	4, 5				
Parafavella qiqantea		4			
Foraminiferans		2			
CNIDARIA:					
Hydromedusae		2			4
ASCHELMINTHES:					V-66.
Keratella cochlearis	4, 5	6, 7		Fresh, < 4 <sup>O</sup> /oo	
Pleurotrocha sp.	1, 3			Euryhaline	
Brachionus calyciflorous		6,7		Fresh	
Kellicottia longispina		6,7		Fresh	
Argonotholca foliacea		6,7		Fresh	
PLATYHELMINTHES:					
Rhabdocoels		2			
NEMATODA:	3,4,5	2, 5		Benthic	
BRYOZOA:					
Cyphonautes larvae		2, 4			

TABLE XV (continued)

	STATI	ONS	GEOGRAPHICAL	
SPECIES	SPRING	FALL	DISTRIBUTION	
MOLLUSCA:				
Gastropod veligers	1, 3	2, 4		
Gastropod juveniles		7		Fresh
Modiolus sp. (veligers)		2,4,5	Boreal Province & Virginian Province	Littoral to shallow, Euryhaline
Mytilus edulis (veligers)		2,4,5	Boreal Province & Virginian Province	Littoral to shallow, Euryhaline
Hiatella arctica (veligers)		4	Boreal Province & Virginian Province	Littoral to 183m
Other bivalve veligers		2,4,5	•	
Cerastoderma pinnatulum (juve	2	Boreal Province & Virginian Province	6 <b>-</b> 183m	
ANNELIDA:			-	
Spionid larvae Polychaete trochophores Other polychaete larvae	1, 3, 5	2,4,5 2 5		
ARTHROPODA:				
Calanus finmarchicus	3		Boreal Province & Virginian Province	Marine > 29 <sup>O</sup> /oo
Pseudodiaptomus coronatus	3			0 - 23.9
Pseudocalanus minutus	1, 5	2,4,5	Boreal Province (circumpolar)	7.2 - 35 <sup>O</sup> /oo
Paracalanus parvus		2	Cosmopolitan	Lit., Ner., > 14.8 °/
Acartia clausi	1, 3	2,4,5	Boreal Province	Lit., Ner., 0 - 36 0/6
Acartia longiremus	3, 4		Arctic, Boreal & Virginia Provinces	Lit., Ner., 6.5 - 35 <sup>O</sup> /oo
Acartia tonsa		2,4,5	Cosmopolitan	Lit., 0 - 30 <sup>O</sup> /oo

(continued)

TABLE XV (continued)

	STATI	ONS	GEOGRAPHICAL		
SPECIES	SPRING	FALL	DISTRIBUTION	···	
ARTHROPODA (continued)					
Centropages typicus		2, 4	Boreal Province & Virginian Province	Neritic, > 30 º/oo	
Centropages hamatus		2	Boreal Province & Virginian Province	Littoral, Neritic, 1 - 31 <sup>O</sup> /oo	
Eurytemora <u>herdmani</u> Temora <u>longicornis</u>		2,4,5 2,4,5	Boreal Province Boreal Province & Virginian Province	Marine - brackish Littoral, Neritic, 6.5 - 35 <sup>O</sup> /oo	
Oithona similis Oithona nana Oithona juveniles	1, 3	2,4,5 2,4,5 2,4,5	Cosmopolitan	7 - 38 <sup>0</sup> /oo	
Microsetella norvegica Copepod nauplii Copepodites	1,3,4,5 1,3,4	2 2,4,5 2,4,5		Marine	
Podon intermedius	3	5	Boreal Province & Virginian Province	Euryhaline	
Balanus nauplii Balanus cypris Euphausiid calyptopis	3,4,5 1, 4 1,3,4				
Corophium volutator Crangon septemspinosa larvae	5	2 2, 4	Boreal Province Boreal Province & Virginian Province	Littoral, Euryhaline Littoral to 128m, Euryhaline	
Philomedes sp. Ostracods		5 6	· 9-··		
ECHINODERMATA					
Ophiopluteus larvae	1, 3				

TABLE XV (continued)

	STATI	ONS	GEOGRAPHICAL	
SPECIES	SPRING	FALL	DISTRIBUTION	
HORDATA				
Oikopleura dioica		2,4,5	Cosmopolitan	> 11.4 0/00
Clupeid larvae	1,3,4		-	,
Fritillaria sp.	, , -	2	Boreal Province	
Fish eggs	1, 3			

(Table XIV). Typically marine-estuarine assemblages were present in both surface and near-bottom samples from Stations 1 and 3 with estuarine diatoms, Chaetoceros debilis, Thalassiosira gravida, and Thalassiothrix nitzschioides, extremely abundant. A freshwater fauna was found in the surface water at Station 4, while both freshwater and estuarine organisms were present near the bottom. Samples from Station 5 contained primarily freshwater organisms such as Vorticella and Keratella cochlearis (Table XVI). A consistently greater number of individuals and taxon categories was found in near-bottom samples than in surface samples.

Thirty-three species, four genera, and at least nine higher taxa were identified in the fall plankton (Table XVII). The phytoplankton was composed of approximately equal numbers of diatom and dinoflagellate species plus two chlorophytes and one cyanophyte.

Many species which had been extremely abundant during the spring, such as Chaetoceros debilis, Thalassiosira gravida, and Thalassiothrix nitzschioides, were no longer present. Most major phyla were represented in the zooplankton, and many new species, not present in the spring, were found. The number of species was by far highest among the calanoid copepods; rotifers and larvae of bottom invertebrates were also abundant. Approximately 75% of the zooplankton were holoplankton and 25% were meroplankton.

# TABLE XVI

# ECOLOGICAL STUDY - MERRIMACK RIVER ESTUARY - MASSACHUSETTS

# DOMINANT PLANKTON AT EACH SAMPLING STATION DURING

# SPRING

	CDPGTPG
STATION	DOMINANT PLANKTON SPECIES
1	Thalassiosira gravida Chaetoceros sp. Chaetoceros debilis Thalassiothrix nitzschioides Fragillaria islandica Coscinodiscus sp. Ceratium longipes Peridinium depressum
3	Thalassiosira gravida Thalassiosira nordenskioldii Chaetoceros convolutus Chaetoceros debilis Thalassiothrix nitzschioides Fragillaria islandica Coscinodiscus sp. Asterionella japonica Ceratium longipes Ceratium fusus
4	Fragillaria islandica
5	Coscinodiscus sp.

# V-72.

# TABLE XVII

# ECOLOGICAL STUDY - MERRIMACK RIVER ESTUARY - MASSACHUSETTS

# DOMINANT PLANKTON AT EACH SAMPLING STATION DURING

# FALL

STATION	DOMINANT PLANKTON SPECIES
2	Coscinodiscus sp. Ceratium longipes Ceratium tripos Oithona similis Oithona nana Copepod nauplii Cyclopoid copepod juveniles Acartia tonsa Temora longicornis Centropages typicus Mytilid veligers
4	Ceratium longipes Oithona similis Oithona nana Copepod nauplii Cyclopoid copepod juveniles
5	Oithona similis Oithona nana Cyclopoid copepod juveniles
6	Thalassiothrix fraunfeldii Fragillaria crotonensis Pediastrum bivae Staurastrum dorsidentiferum Keratella cochlearis Brachionus calyciflorous Kellicottia longispina
7	Thalassiothrix fraunfeldii Fragillaria crotonensis Pediastrum bivae Staurastrum dorsidentiferum Keratella cochlearis Brachionus calyciflorous

Diversity was highest at Station 2 and gradually decreased upriver. The number of species and genera at Station 7, the last freshwater station, was approximately one-third that of Station 2. Stations 2, 4, and 5 contained marine-estuarine assemblages dominated by species of dinoflagellates, bivalve larvae, and copepods, whereas the assemblages at Stations 6 and 7 were essentially freshwater with <a href="Fragill-aria">Fragill-aria</a> crotonensis, <a href="Thalassiothrix">Thalassiothrix</a> nitzschioides, <a href="Pediastrum">Pediastrum</a> bivae, <a href="Staurastrum">Staurastrum</a> dorsidentiferum present in "bloom" proportions (Table XVII).

# 3. Existing Composition and Distribution of Plankton:

The overall composition of plankton in the Merrimack River Estuary is typical of large estuaries where, as a result of incomplete flushing, resident (i.e., marine and estuarine) plankton populations are maintained. In contrast, smaller estuaries with complete flushing contain a freshwater plankton assemblage during the ebbing tide [derived from adjoining river(s)], marine plankton assemblages during the flooding tide (derived from adjacent offshore waters), and no true estuarine plankton. Most species found in the Merrimack River Estuary were either boreal or cosmopolitan in distribution; none were uncommon in this latitude (Table XV).

Species composition within the estuary varied seasonally. Temperate estuaries are generally characterized by spring diatom blooms, which rapidly diminish and are replaced in summer by high numbers of dinoflagellates and meroplankton (Clarke, 1954; Johnson, 1957; and Odum, 1959). A lesser diatom peak occurs during the fall, followed by a winter low (Clarke, 1954). This cycle explains most of the seasonal "anomalies" in composition found in the Merrimack River Estuary. In this study, the majority of diatom species were found in the spring, while dinoflagellate species were dominant during fall. Generally, phytoplankton species present in April were not present in October, and vice versa. For example, the diatoms Thalassiosira gravida, Fragillaria islandica, Chaetoceros debilis, and Thalassiothrix fraunfeldii, were extremely numerous during April, but not found in the fall, and the dinoflagellates Ceratium tripos and C. bucephalum were collected in the fall, but not found in the spring. Many more species of copepods, rotifers, and molluscan larvae were found in the fall than in the spring and, as with phytoplankton, species present in the spring were usually not found in the fall and For example, Calanus finmarchicus, a spring and summer species in the Gulf of Maine was collected only in spring, and Centropages typicus and Acartia tonsa, summer and fall species low, 1924; Deevey, 1943 and 1946), were present only during the fall. Pseudocalanus minutus and Oithona similis, typically year-round copepod species, were found throughout the study period.

Horizontal species distribution within the Merrimack River Estuary varied seasonally, depending upon the amount of freshwater discharge. During the spring, when freshwater discharge was high, euryhaline marine and estuarine zooplankton were found upriver as far as Coffin Point. However, in the fall, when reduced river flow allowed saline water to intrude further, they were present beyond Carr Island.

Differential surface-bottom distributions of marine, estuarine, and freshwater species were noted in spring. In other words, marine and estuarine species were found farther upriver in bottom waters than in surface waters, and freshwater species extended farther downstream in surface waters. This is attributed to greater physical stratification within the estuary at this time. Differential surface-bottom distributions were not found during the fall when reduced flows caused vertical mixing.

### 4. Projected Changes as a Result of Diversion:

The net effect of river diversion will probably be a slight upriver shift of euryhaline marine and estuarine species during diversion, but this extension should not exceed that found during the low flow periods which occur naturally. This extension will affect the meroplankton to a greater extent than the holoplankton, in that holoplankters should merely oscillate about some zone farther upriver

than present, but meroplankters which lead a benthic adult existence (e.g., clams), may encounter unsuitable substratum conditions when they settle. Since many of these benthic organisms spawn during the summer, extension of larval forms upriver, as well as possible temperature-salinity induced changes in estuarine adult reproductive patterns, should be considered if diversion, to an extent which would create below average flow rates during this period is anticipated. On the other hand, certain other meroplankters (barnacles, Mytilids, and wood-boring bivalves) may indeed find suitable habitat and thus extend their range upriver.

Although there will not be an upriver intrusion of saline water beyond areas that are now periodically affected by low level salinities, the areas between mile 1 and the mouth of the estuary will be under stronger marine influence. Present dominant euryhaline species in this region should not change, but marine species such as <a href="Calanus finmarchicus">Calanus finmarchicus might extend farther into the estuary</a>. It is not expected that new species will be introduced as a result of diversion.

In addition to a longitudinal effect, vertical distribution of plankton may also be disrupted since water stratification breaks down during periods of low flow. Thus, diversion could increase the amount of time organisms would be exposed to a homogeneous water column.

Furthermore, maintenance of a distinct salt wedge may be essential to continued estuarine residency for a number of plankters (Green, 1968). The magnitude of such an effect is in the realm of speculation however.

Finally, an upriver shift in plankton could result in an upriver shift of organisms which feed on plankton, for example, filter-feeding invertebrates, and some bait-size fish and fry of commercial species.

# E. COMMERCIALLY IMPORTANT INVERTEBRATES

- 1. The Soft-Shell Clam, Mya arenaria
- a. Importance to the Area:

The soft-shell clam, Mya arenaria, has played a major role in the economy of the Merrimack River region since colonial times, and is today the only commercially valuable shellfish living in the Merrimack River Estuary. Blue mussels, Mytilus edulis, are present at various locations, but are generally not utilized in the Merrimack River. A thorough review of the history of the clam fishery in this region is presented by Jerome, et al (1965).


Extensive intertidal mud flats located along both banks of the lower Merrimack River Estuary provide an excellent habitat for the soft-shelled clam, and these flats have not been seriously altered by dredging, filling, or other man-made physical changes. Pollution has been a serious problem since the mid 19th century, and while it has practically eliminated the soft-shell fishery, it apparently has not seriously affected the survival of the clams. In fact, the population of clams in the entire estuary is quite high. If totals for the Salisbury, Newbury-port, and Newbury flats are combined, it is estimated that approximately 100,000 bushels of clams of legal or near-legal size are present, and with pollution abatement this could result in a total estimated wholesale harvest of \$300,000.00 annually. Jerome, et al (1965) predicted that with proper management the harvest could exceed \$500,000.00 and approach \$1,000,000.00 annually.

In view of the tremendous future value of the clam fishery to the Merrimack River Estuary region, it is imperative that the potential effects of diversion on this resource be evaluated in detail before the idea proceeds beyond the planning stage.

# b. Present Distribution and Abundance of Mya arenaria:

Mya arenaria is found in great abundance in the lower Merrimack
River Estuary from near the mouth at Black Rocks and Newburyport Light
upriver to Coffin Point several miles inland. Although considerable
substratum suitable for clam settlement is found upriver of Coffin Point,
no clams have been found or reported from this region.

A complete population count on all flats bordering the Merrimack River Estuary has been completed by Jerome, et al (1965) and a description of clam density in each flat is presented in detail in their report. Results of this study seem to indicate that distribution and abundance are not strictly controlled by the nature of the substratum or presence of  $H_2S$ , for clams were abundant in several grades of sediment and in varying amounts of  $H_2S$ . However, it is apparent from the pattern of distribution, summarized and represented in Figure 15, that abundance is greatest nearest to the mouth of the estuary, and decreases in the upriver direction. The Humpsand and Old Mussel Flats are an exception to this generality, but in these areas  $\underline{Mya}$  abundance is primarily restricted by competition with Mytilus edulis.



c. Potential Effects of Diversion on the Survival, Distribution, and Abundance of Mya arenaria:

A considerable amount of information is available on life history aspects of Mya arenaria, most of it being included in a bibliography by Pfitzenmeyer, et al (1960). While many aspects of Mya life history should not be noticeably affected by the potential diversion, certain physical changes brought about by decreased discharge could directly or indirectly present problems that would affect the survival of the clam population.

#### CHANGES IN SALINITY AND TEMPERATURE:

Mya arenaria occurs in the Western Atlantic from Labrador to North Carolina, and according to Pfitzenmeyer (1965) throughout its range it is tolerant of considerable variation in annual water temperatures and salinities. In the northern part of the range it is primarily a marine species, found in coastal inlets and bays in high salinity, while in more southerly areas it tends to become increasingly estuarine in habitat choice. Chesmore (1971, pers. comm.) has stated that in Massachusetts Mya is normally found in salinities above 15 % oo, and Hanks (1953) has shown that at Woods Hole, Massachusetts, the absolute minimum salinity at which a population can be established is 6 % oo, and below this salinity the clams will not remain buried in the sand.

Salinities vary drastically in the Merrimack River Estuary within

each tidal cycle, and readings at Coffin Point, the presently observed upper limits of Mya distribution, range from near 0 % oo during periods of high flow to above 30 % oo when discharge is low. Since the clam is tolerant of such a wide range of salinity, it is unlikely that salinity increase will have any directly negative effect on its distribution and abundance. If any direct effect is observed, it is probably that abundance might increase in the presently low density portion (Stations 1 and 2) of Salisbury and Joppa Flats, primarily due to a reduction in the amount of time suboptimal salinities cover these habitats.

Within the normal salinity limits of the species, salinity variation does not appear to be a significant factor in the timing or success of spawning. Pfitzenmeyer (1965), Orton (1920), and others have shown that in New England the clam spawns continuously throughout the late spring, summer, and early fall. Time of spawning appears to be temperature regulated, beginning in April-May when waters warm to 10° - 12° C, continuing throughout the summer undiminished unless the temperature rises above 15° C, and terminating as temperatures cool in September and October. Because diversion should not result in significant temperature changes in the lower estuary, spawning should not be affected.

### CHANGES IN SEDIMENTATION:

Alterations in sedimentation can seriously affect a benthic bivalve population, for few bivalves are capable of migration out of

a heavily silted area. Along with others, Newcombe (1935) has demonstrated the limiting effect of shifting sand and silt-covered soft mud upon the growth of Mya arenaria, and Loosanoff and Tommen (1948) have shown that suspended silt in the water reduces the rate of feeding by oysters. As has been discussed earlier, a diversion of freshwater from the river could result in two potential changes in sedimentation. The first, a change in deposition of suspended sediments resulting from alteration of circulation, is unlikely to adversely affect the existing distribution and abundance of clams. Clams are presently abundant both over Joppa Flats, where sedimentation is very high, and over Salisbury Flats, where sedimentation rates are reported to be considerably lower (Hartwell, 1970). If the circulation pattern of the estuary does change over parts of the year when the critical low flow is reached, and if loss of stratification results in higher deposition over Salisbury Flats, it is probable that clams presently living there will survive just as they now do on Joppa Flats.

However, if a decrease in river discharge results in an increased accretion of the flood tidal delta, as Goldsmith (pers. comm.) has suggested may happen, then the possibility exists that some clam flats could be partly or completely covered over and smothered. However, the existing program of periodic maintenance dredging of the river channel should minimize this possibility. Further studies on rates of sediment inflow under reduced discharge would be needed to determine the extent of flood tidal delta migration.

#### POSSIBLE INTRODUCTION OF PREDATORY SPECIES:

Considerable research (much of it unpublished) has been completed on the biology of clam predators and methods of predator control. Several organisms have been reported to prey on Mya arenaria, among them the black duck, Anas rubrupes, but only three pose a definite threat to the survival of entire clam flats. The green crab, Carcinus maenas, appears to cause greatest year-round damage, followed in importance by seasonal destruction from the horseshoe crab, Limulus polyphemus, and lower sustained mortalities by the moon snails, Polinices heros and P. duplicata (Baptist, et al, 1957).

C. maenas and P. heros are present in low abundance near the mouth of the Merrimack River Estuary, but neither were observed on the clam flats during the 1971 sampling period, nor in the 1964 sampling by Jerome, et al (1965). Since these predators are presently causing damage to clam flats along other parts of the Northern New England Coast, it is important to determine if reducing discharge could lead to an immigration of these species onto the flats.

The green crab, <u>Carcinus maenas</u>, is presently found in considerable abundance in the tidal creeks along the lower end of the estuary and in the Basin area. In fact, Jerome, <u>et al</u> (1965) indicate that a minor green crab fishery has existed in the lower Merrimack River Estuary for years,

but it has not been particularly successful, in view of the specialized pots required and low yield obtained. Most crabs caught commercially are used primarily as bait by southern New England and New York fishermen while fishing for tautog, <u>Tautoga onitis</u>. The green crab is not presently found in any abundance on the Merrimack River Estuary clam flats.

Because of the green crab's devastating effect upon the clam flats in other areas, much research has been done on its biology. A considerable amount of this material is found in unpublished reports of the U. S. Department of the Interior, Fish and Wildlife Service, Clam Investigations, but some have been published by Broekhuysen (1937), Scattergood (1951), and others. These reports contain some information relevant to the diversion study:

- a) The green crab has been extending its range northward over the past century. Scattergood (1951) states that man's activities as well as drifting of the larvae and migration of the adults may be responsible for this northward spread. He further states that new populations will not be established unless environmental conditions are suitable.
- b) Populations of green crabs in some years appear to be unlimited, but in others they are relatively scarce.

  Broekhuysen (1937) suggested that a combination of low

temperatures and low salinities affect survival and distribution, especially in winter, and these factors account for fluctuations in abundance.

c) Goucher (1951) has reported catastropic mortalities of green crabs after the cold winter of 1931, and Broekhuysen (1937) and others have shown that green crabs eggs will not develop and hatch in salinities below 15 0/00.

Unpublished reports from the clam investigations and results of personal interviews indicate that the green crab is inhibited in some manner by low salinities and/or low temperatures. Obviously the crab is not restricted from the Merrimack River Estuary solely by low temperatures, for they thrive in colder waters in New Hampshire and Maine clam flats. Therefore, it is probable that the more important factor inhibiting migration onto the shallow Merrimack River Estuary flats is reduced salinities.

from this it is tempting to speculate that a decrease in river discharge will lead to conditions favoring a green crab invasion of the flats. However, no information is available to indicate whether periodic low salinities, such as those resulting from flood conditions, or continuous reduced salinities such as those observed in the river throughout most of the year, are more important in regulating distribution. If the flood is instrumental in limiting the crab, diversion should not

affect the distribution. However, if reduced salinities throughout the year is the critical factor, any diversion other than flood skimming could favor crab dispersal onto the flats. Before a diversion scheme is decided upon, it would be desirable to run short and long term salinity tolerance tests to determine the conditions that would permit an expansion of crab habitats in the Merrimack River Estuary.

Polinices heros is an important predator on Mya arenaria in the Hampton-Seabrook Estuary, New Hampshire, and the Parker River - Plum Island Sound Estuary (Jerome, et al, 1965). However, no individuals of this species were found on the Merrimack clam flats throughout the study period, even though they were found at the mouth of the estuary. According to Minor (1950) and Hanks (1953)

Polinices heros is a northern species normally found in high salinity waters. The snails cannot adjust to sudden changes in salinity (as little as 7 %)00) and react by complete withdrawal into the shell for four to five days. P. heros feeds normally at salinities of 32 %)00, but rates are reduced considerably at 18 %)00, and feeding terminates at 10 %)00, the salinity at which death eventually occurs.

Because of the species' inability to feed successfully in reduced salinity, it is probable that it is presently restricted from the Merrimack clam flats, at least in part, by this factor. If salinity is increased by diversion, a migration of snails onto the flats is possible. However, as in the case of the green crab, no definite conclusions can be made until it is known if the snail is affected more by low salinities of the spring flood or by low level freshwater intrusion throughout most of the year. If a continuous diversion is chosen, it would be desirable to determine the nature of the salinity factors now operating to limit distribution.

# 2. The American Lobster, Homarus americanus

According to Jerome, et al (1965) lobster fishing has been pursued for a long time by a small number of commercial lobstermen in the vicinity of the Merrimack River Estuary. No fishing is actually done within the limits of the estuary, but pots are placed in eight to ten fathoms outside the breakwater, in an area definitely influenced by the river. In addition to the commercial fishing, conversations with divers and local fishermen indicate that lobsters are also taken in fairly large numbers for home consumption by recreational pot fishermen and SCUBA divers.

Because lobsters are not taken within the Estuary, and since they are not dependent upon freshwater during any period of their life cycle, they should not be affected by the diversion.

#### 3. Crabs

Three species of crabs have been periodically fished in the Merrimack River Estuary, the green crab, <u>Carcinus maenas</u>, has been discussed earlier. Two edible crabs, <u>Cancer borealis</u> (Jonah crab) and <u>Cancer irroratus</u> (Rock crab), are taken by commercial fishermen in limited numbers, but no fulltime fishing activity has been reported in the area. According to Jerome, <u>et al</u> (1965), over 2,000 edible crabs were

taken in 1964 with a commercial value of \$325.00.


Few crabs were seen throughout the sampling period, and from lack of data it is not possible at this time to make predictions on the effects of diversion.

#### F. FINFISH

# 1. Present Distribution and Relative Abundance of Finfish in the Merrimack River Estuary:

Jerome, et al (1965) completed an extensive year-long survey of the inshore fishes frequenting the Merrimack River Estuary from the ocean at Plum Island upriver to predominantly freshwater at the Artichoke River. Seine samples were taken monthly at five sites along the length of the Merrimack River Estuary (Figure 16), and the results of the sampling are tabulated in Table XVIII. Seventeen species of fish were captured, but only four species (American sand lance, mummichog, blueback herring, and alewife) comprised 99% of all fish captured.

The American sand lance was the most abundant species captured, but, as will be described later, it was not found in salinities of less than 25 \(^{O}/\text{oo}\). Blueback herrings and alewives were abundant at all stations, and they tolerate a complete range of salinity variation, as does the mummichog, although the latter species was only found in



# ECOLOGICAL STUDY MERRIMACK RIVER ESTARUY - MASSACHUSETTS

TABLE XVIII

SURVEY OF 1964 MERRIMACK RIVER ESTUARY FISH SURVEY (Condensed from Jerome, et a!, 1965) - TOTAL NUMBER OF SPECIMEN CAPTURED PER THREE MONTHS, RANKED BY ABUNDANCE AT EACH STATION

	CC	DAST G	JARD	COVE	<del></del>	1	BAD	GERS	ROCKS	5	Ī	COF	FIN P	OINT		1	CARR	'S IS	LAND		A	RTICH	OKE R	VER	
SPECIES	RANK	А	В	С	D	RANK	A	В	C	D	RANK	A	В	С	D .	RANK	A	В	С	D	RANK		В	С	D
SQUIRREL HAKE	7			1																			<u>.                                      </u>		
AMERICAN SAND LANCE	1	9.	120	4387	6768	2		10	12	1105	5		11												
THREESPINE STICKLEBACK	6		7			7			1		9		1												
AMERICAN SMELT	5			8		5			123		4			1	43	5		17		5					
ATLANTIC SILVERSIDE	4		1	25		4			99	68	5				11	4			51						
BLUEBACK HERRING	2			1132	219	1			1981	1761	1			4280		1		2	772	32	3		:	L77	36
ALEWIFE	3			400		3			529	16	3			70		3		15	151	43	2		6 2	036	6
MUMMICHOG		-				6		2			2		227	1976	76	2		133	140	10	1	9	979	167	82
NORTHERN PIPEFISH											8			2											
WINTER FLOUNDER											6		1	3											
NINESPINE STICKLEBACK											9		1			8	1		1		9				1
WHITE PERCH											7		1		2	7		2	1	3	5			5	1
BLUEGILL											9		1								6		4	1	
AMERICAN EEL																6		2	5		7		1	3	
BROWN BULLHEAD																					8		2		
SPOTTAIL SHINER																8		2			4		14	20	
CARP																					9		1		

A = Janury, February, March B = April, May, June

C = July, August, September D = October, November, December

high numbers at the upper three stations. Silversides and smelt were seasonally abundant at the higher salinity stations.

Carp, brown bullhead, spottail shiners, and bluegills were the only freshwater fish seined throughout the year, and all four species were taken at the Artichoke River stations.

Monthly trawl samples were taken at three stations, but only one was located inside the estuary. Of 19 species captured at all stations, only five species (the winter flounder, striped bass, pollock, sea hare, and lumpfish) were taken within the estuary. The winter flounder was the only fish taken in abundance at the inshore station.

A complete list of all species taken by various methods is listed by Jerome, et al (1965).

# 2. Potential Effects of Salinity Change on the Abundant Finfish Species, and on Species of Sport and Commercial Importance:

It is obvious that with the limited data at hand there is no way to accurately assess the total impact of a river diversion on all components of the finfish community. However, it is possible to make certain predictions on probable changes that could occur in the ecology of most abundant species, and in species of sport and commercial interest. Nine

of these species are dicussed below. Most information on economic importance of each species has been obtained from Jerome, et al (1965).

Unless otherwise indicated in the text, all information on life history has been adapted from Bigelow and Schroeder (1953).

## a. THE SAND LANCE, Ammodytes americanus

IMPORTANCE TO THE AREA: The sand lance, Ammodytes americanus, is one of the most important fishes frequenting the Merrimack River Estuary. According to Jerome, et al (1965), this small fish has been used for food by many people during the past 60 to 70 years, but today the market is primarily for bait in the sport fishery, particularly in mackerel and tuna fishing. Considerable labor and special equipment are needed to harvest this fish successfully, and the sand lance bait industry is quite intensive during the fishing season from June through September. As a conservative value, it has been estimated that the total harvest of sand lance in the Merrimack River in 1964 was approximately 1,400 barrels.

Not only is the sand lance important as a commercial species, but is also serves as a main food supply for many sport fishes, including the striped bass, mackerel, and pollock, and as such, is of vital concern to the entire sport fishery in the Merrimack River Estuary.

PERTINENT ASPECTS OF LIFE HISTORY: Little is known of the biology of the sand lance, although Ohshima (1950) presents some biological notes

on a Japanese species A. personatus. Bigelow and Schroeder (1953) and Norcross, et al (1961) state that there is only one species, A. americanus, but Richards, et al (1963) claim that there are in reality two species, A. dubius and A. hexapterus, readily separated by meristic characters and habitat preference. A. dubius inhabits offshore areas in which the salinity is usually above 30 %, whereas A. hexapterus lives in inshore areas where the salinity fluctuates between 26 %, oo and 32 %, oo.

The lance is a schooling fish. It frequently congregates in dense schools along sandy foreshores and over the shoaler parts of the offshore fishing bank, but is seldom seen in rocky areas or on a muddy bottom. The lance has the unusual habit of rapidly burrowing several inches into the sand using its sharp snout, and in summer, during high tide, schools of lance swarm over sandy beaches above LW mark and burrow in, remaining there until the next high tide. It has been suggested that they spend most of their time buried in the sand, but it is not known if this habit is followed at all depths, or only in shallow waters. Adult sand lance feed abundantly on small crustaceans, fish fry, and worms. They, in turn, are a major source of food for such inshore fish as cod, haddock, halibut, silver hake, salmon, mackerel, striped bass, and bluefish.

Spawning in the American sand lance has not been directly ob-

served, but it is probable that spawning activity begins in deep waters early in November. Norcross (1961) states that temperature must play an important role in determining the onset of spawning, and it is probable that most animals spawn when the water temperature drops to near 9° C. Hatching begins in late November, reaches a peak sometime after mid-December, and continues until mid-March. From plankton tows taken by Norcross (1961), few larvae were collected in water with salinities less than 30 °/oo.

PROJECTED EFFECTS OF DIVERSION ON THE ECOLOGY OF THE SPECIES: The sand lance, probably A. hexapterus, congregates in dense schools in the extensive shallow sand and gravel areas at the mouth of the Merrimack River Estuary from spring through fall, and it is at this time that most harvesting occurs. They probably migrate to deeper waters in the fall and winter.

Even though sandy areas are found throughout the lower estuary, it is likely that the species is presently restricted from entering farther upriver by periodic wide fluctuations in salinity. Because of the intolerance of both species of lance for lowered salinity, it is probable that a reduction in freshwater outflow in the estuary could result in a net upriver increase in suitable habitat, and the possibility of an increase in the size of the resident population.

## b. THE STRIPED BASS, Morone saxatilis

IMPORTANCE TO THE AREA: The striped bass, Morone saxatilis, is one of the most prized fishes caught in the Merrimack River Estuary, and according to Jerome, et al (1965), this fish is the basis of a sport and commercial fishery contributing many thousands of dollars and much recreational enjoyment to the towns along the lower Merrimack Valley. Thousands of local and visiting sportsmen fish from shore and boats during the months of May through October. Any legal sized fish (16" from the tip of the snout to the fork of the tail) may be kept by the fishermen, or may be sold if it has been taken by hook and line. Commercial fishing is reportedly on the increase, and an estimated 178,000 pounds of striped bass sold for \$44,500.00 in 1964. This quantity was approximately half of the total harvest, and it is obvious that this fishery contributes significantly to the local economy through equipment sale and rental, food, and lodging.

pertinent aspects of LIFE HISTORY: Most aspects of the life history of the striped bass are well known, and the following report has been adapted primarily from data contained in Bigelow and Schroeder (1953). It is a relatively large, fast growing fish, a strong swimmer, and a voracious carnivore. Individuals have been known to live for more than 40 years, and to reach 125 pounds in weight. According to most reports, the striped bass is strictly an inshore fish, and is equally

at home in fresh, brackish, and coastal waters. Most bass frequent the coast, but some run up into estuaries and river mouths. In some rivers they travel so far upstream that it is likely they remain all year.

Bass are active over a temperature range of from 43° to 70° F.

Below 40° F they tend to become inactive, and mortality is high when

fish are subjected to temperatures much above 77° F. The striper

can tolerate a wide range of salinty.

The striped bass is a voracious carnivore, feeding on any available fish, chiefly herring, smelt, sand lance, eels, and silver hake in the Gulf of Maine. They also feed, exclusively at times, on squid, crabs, lobsters, and Nereis (the clam worm), especially in estuarine situations.

Resident populations of striped bass migrate locally throughout the year. Most stripers travel in schools when they are undergoing migration, but individuals may be scattered while feeding in one general locality. Local migrations follow a seasonal pattern. In summer the fish school in feeding migrations near the surface of tributaries, bays, and coastal areas. In autumn the schools move into lower tributaries and bays for feeding and overwintering, and as winter approaches they concentrate in a somewhat less active condition in

deeper water, mature fish ascend the rivers to spawn, and immature ones start their feeding migrations.

In addition to local migrations, some populations of the Atlantic Coast stock undertake coastal migrations. In late winter and early spring some striped bass from the mid-Atlantic states migrate to New England and remain all summer. In fall they may move south again, but more recent evidence indicates that the fish may just move offshore into deeper water for the winter.

The striped bass is anadromous, and will either spawn in brackish water at the heads of estuaries, or in freshwater farther upriver. There is no evidence of fish spawning in coastal waters. Those that enter freshwater may deposit their eggs only a short distance above the head of tide, or may run far upstream. Spawning appears to be governed primarily by water temperature (Nichols, 1966), and the peak of egg production occurs around 65° F. A spawning population may often consist of males, two or more years old, and larger females, four or more years old. One large female and several smaller males may often undergo common courtship. Spawning, when it does occur in the Gulf of Maine, usually occurs in the end of May or early in June, and the chief requirement for successful spawning appears to be a current turbulent enough to prevent the eggs from settling on the bottom where they could be covered by silt and suffocated.

The semi-buoyant eggs tend to slowly drift downstream with the current, and eggs that were produced far upriver may not hatch until they have reached tidewater. The eggs hatch in approximately two days at 65° F. Newly hatched larvae live in open freshwater and brackish water until they are 1/2 inch long, when they move toward shore and remain in schools throughout the first summer. Feeding habits of the young differ with age. Larvae feed on zooplankton, while the young consume small fish, worms, and other fleshy invertebrates.

During the second summer when the young are greater than six inches in length, they move down into bays and sounds, and begin feeding on small schooling fish, soft-shell clams, crabs, and clam worms. After the second year the young bass form denser schools and begin migratory patterns.

According to Bigelow and Schroeder (1953), the Merrimack River has never been an important overwintering ground for the striped bass, even though they are known to overwinter in the Parker River. There is no evidence of any spawning activity of the bass in the Merrimack River. In fact, the only area in the Gulf of Maine still utilized for spawning by the stripers are the Mousam Stream in Maine and the Parker River in Massachusetts. In recent years it has been sufficiently established that a great majority of the bass that summer in the western side of the Gulf come from spawning grounds to the west and south,

probably from the Chesapeake and Delaware Bays, at an age of two to three years.

PROJECTED EFFECTS OF DIVERSION ON THE ECOLOGY OF THE SPECIES: Because the striped bass is equally at home in fresh, brackish, and coastal waters, and in light of the observation that the Merrimack River Estuary is neither a spawning area nor an important overwintering habitat, diversion of freshwater should have little observable effect on the ecology or biology of this important fish.

#### c. THE ATLANTIC SALMON, Salmo salar

HISTORIC IMPORTANCE OF THE SPECIES: During colonial times, salmon were found in every large stream not blocked by impassable falls. They were plentiful in the Merrimack River, and large numbers spawned in its upper tributaries, especially the Pemmigewasset, as late as 1793 (Lyman and Reed, 1866). However, the completion of the dam at Lawrence, Massachusetts, in 1847 completely blocked the salmon from the upper reaches of the Merrimack.

It was reported that for several years thereafter salmon congregated at the base of the Lawrence Dam in spring and summer, but there has been no run of salmon in the upper Merrimack since 1860, when the last salmon hatched above the dam had lived its life span. Salmon continued to enter the lower Merrimack River up to 1896, when there was

a minor run in June and July. Many fish were observed at the Lawrence Dam, but only a few were lifted over.

According to Bigelow and Schroeder (1953), there has not been a single sea run salmon seen in the Merrimack River since 1901, although a few land-locked individuals have been reported in recent years.

PERTINENT ASPECTS OF LIFE HISTORY: Most aspects of the life history of the Atlantic salmon, Salmo salar, have been summarized by Bigelow and Schroeder (1953), and the following is adapted from their report. The Atlantic salmon generally lives the greater part of its life at sea and makes most of its growth there, but enters freshwater to spawn. Adults in the sea do not make extensive migration, but tend to remain localized not only within the coastal belt, but also within the zone of influence of the particular river system from which they came. This observation is strongly supported in the Gulf of Maine, where the fish appear about the mouth of rivers so soon after the ice has melted that they could not have come a long distance. The majority of Gulf Of Maine salmon become river mature considerably before the spawning season, but it is not certain if all salmon move inshore in spring, or only those that return to spawn. While none of the fish spawn before October, many enter freshwater as early as March and April, with the large runs occurring in June.

The salmon are silvery and fat when they begin their journey upriver, but once in freshwater they feed little and undergo extensive morphological changes. In smaller streams they may spawn only a short distance above the head of tide, but in large unobstructed rivers they may run upstream for more than 200 miles.

In the Gulf of Maine, salmon spawn in October and early November in sand and gravel stream beds. After spawning the spent fish are so weak that some of them die. Most of those that survive in small rivers return to the sea immediately, but those in large rivers sometimes overwinter and regain strength, returning to the sea the following spring.

The eggs are large and thick-shelled. They lie loose on the sand and gravel and develop slowly during the winter, not hatching until late April or early May. When the larvae hatch they carry a large yolk sac for nearly six weeks, and during this time they hide among pebbles, taking no food. When the yolk sac is absorbed the young, now called parr, commence to swim and feed. Parr live in freshwater for a variable amount of time, but generally move downstream from two to five years. The seaward migration begins any time from late spring to autumn, but most parr in the Gulf of Maine make the journey in June or July.

As the fish approach the sea they become silvery in color, and

upon reaching saltwater become known as smolts. They remain for a time in river mouths and estuaries, but drop into deeper water with the onset of cold weather. The smolts grow rapidly when at sea, and may reach seven pounds after one year.

Salmon of all sizes are voracious predators in saltwater, feeding primarily on alewives, smelts, and mummichogs when they re-enter the estuaries to spawn. At times they also feed heavily on euphausid shrimp, pelagic amphipods, and sand fleas.

The salmon grow little in spawning years, and the size of a salmon depends more on the number of times it has spawned and on the date when it enters the river than on its age. There appears to be no specific pattern in spawning behavior. While some salmon return to spawn after one year at sea, others spawn only after up to five years at sea. No matter what the size or how often they spawn, few fish live to be older than eight or nine years in age from the time of hatching.

PROJECTED EFFECTS OF DIVERSION ON THE ECOLOGY OF THE SPECIES: State and Federal fisheries biologists in both New Hampshire and Massachusetts are formulating plans to restore natural runs of Atlantic salmon into the Merrimack River and its tributaries. According to Mr. Leigh Bridges of the Massachusetts Division of Marine Fisheries, a stocking program is essential to restore salmon runs to meet the spawning habitat's

carrying capacity of 11,000 individuals per year. As with the shad program, potential problems that remain to be resolved include the threat of thermal pollution from projected power plants, present and future multi-purpose impoundments, lack of operational fish ladders, stream flow regulation, problems of canal entrapment, and stream bed gravel mining.

Minimum flow limits are extremely important to the success of this restoration program, for both the survival of smolts in their seaward migration and the success of spawning adults in reaching spawning grounds depend on a plentiful supply of freshwater at specific times throughout the year. The minimum flow required for successful restoration of the Atlantic salmon is presently being evaluated by the Bureau of Sport Fisheries and Wildlife, and others.

According to Bigelow and Schroeder (1953), yearly and seasonal differences in salmon fishing result from corresponding differences in numbers of smolts that reach seawater in any given year. The primary factor responsible for these differences is the height of the river water from summer to summer, or over periods of several summers. The river height is presently affected by yearly rainfall and present domestic and industrial use, and could be drastically affected by any future diversion plans.

When water is high, parr are protected from predation by king-

fishers, mergansers, and other fish-eating birds, and are better able to escape trout predators, thus reaching the sea in great numbers.

If the water is low, however, predation rates increase, fewer smolts reach seawater, and fewer then return as grilse or older fish.

Upriver migration is also regulated by stream flow. Salmon enter rivers in runs that are spaced irregularly in time, and vary in date from year to year, depending on the height of water in rivers and the strength of the current. Freshets tend to bring them in, but if the current becomes too strong, the fish simply hold position until currents slack. Fish that are in the estuaries remain there during periods between freshets, waiting for a pulse of freshwater to begin their migration, and salmon already in rivers are similarly quiescent during periods of low water and weak currents.

A minimum flow is also necessary to prevent stagnant areas and the resulting increase in temperature from insolation from developing in parts of the river during summer. Studies on Coho and sockeye salmon in the Bonneville Fish Hatchery in Oregon (Bouck, 1969) have shown that slight elevations in temperature increase disease and lead to high mortality in spawning salmon.

In view of the above, any diversion plan should consider the salmon restoration program, and the flows necessary to ensure its success.

### d. THE SHAD, Alosa sapidissima

HISTORIC IMPORTANCE OF THE SPECIES: When the settlers first arrived in New England they found a seemingly inexhaustable supply of shad, Alosa sapidissima, annually running up all the large rivers and many of the smaller streams (Bigelow and Schroeder, 1953). The Merrimack River was especially noted for its abundance of shad, and it is reported that they formerly ascended for over 125 miles into Lake Winnepesaukee to spawn. The species very early became a staple item in the diet, and the demand increased as towns and cities sprang up. Efforts were made to intensify fishing to satisfy this demand, but the catch began to decline around 1800, and by 1896 only seven shad were reportedly caught in the whole length of the Merrimack River (Stevenson, 1899).

The decline has been attributed to pollution which rendered the river unsuitable for the species, to over-fishing which did not allow enough fish to spawn for replacement, and to the construction of dams which prevented fish from reaching spawning areas (Walburg and Nichols, 1967).

Today the shad is completely excluded from the Merrimack River,

and the dam\_at Lawrence, only 20 odd miles upstream, stops any stray fish that may still enter the estuary.

PERTINENT ASPECTS OF LIFE HISTORY: Much information on the shad has been compiled by Bigelow and Schroeder (1953). The following is adapted from their reports. Like the alewife and other anadromous fish, the shad spends most of its adult life at sea, although it may enter brackish estuaries on occasion. While at sea the shad is a schooling fish, primarily feeding on plankton such as copepods, mysids, and larval barnacles. Individuals may also select bottom amphiphods on occasion.

Shad enter streams in spring and early summer when river water warms to 50° - 55° F. In the Gulf of Maine the heaviest runs are in May, with most spawning occuring in June. In large rivers the shad run far upstream, and take little or no food prior to spawning. Spawning occurs in sandy or pebbly shallows, where from 100,000 to 600,000 eggs are deposited. The emaciated spent fish depart immediately, begin feeding before reaching salt water, and have regained weight by the time they re-enter the sea.

The semi-buoyant eggs slowly roll on the bottom with the current, hatching in from 6 to 15 days, depending on temperature. Young shad remain in the river during the summer, feeding on insects and crustaceans, and grow rapidly. In the fall they depart for salt water and winter

near the mouth of the parent stream.

Schools of adult shad are often seen inshore at the surface during spring, summer, and fall, but during the winter they disappear from these areas, heading out into deeper water. Shad undergo extensive migrations throughout the year, with large numbers of recently spawned individuals from both the Chesapeake area and from Canada moving into the Gulf of Maine for the summer and autumn.

PROJECTED EFFECTS OF DIVERSION ON THE ECOLOGY OF THE SPECIES: State and Federal fisheries biologists in both Massachusetts and New Hampshire have initiated plans to restore the shad fishery in the Merrimack River to its full potential. According to Mr. Leigh Bridges of the Massachusetts Division of Marine Fisheries, the spawning area as far north as Franklin, New Hampshire, should be able to support nearly one million shad, and initial stocking is expected to commence when present programs in the Connecticut River show signs of success. Problems that have to be resolved before this potential may be fully realized include the threat of thermal pollution from projected power plants, present and future multi-purpose impoundments, lack of operational fish ladders, stream flow regulation, problems of canal entrapment, and stream bed gravel mining.

For the success of this program, it is imperative that a minimum supply of freshwater be permitted over the dams throughout the year,

and that a certain amount of this flow pass down properly designed fish ladders. The minimum amount of flow required for a successful shad restoration is presently being evaluated by the Bureau of Sport Fisheries and Wildlife, and others. Watson (1970) showed that temperature and percentage of river flow passing through the attraction channel, even during the increasing phase of upstream migration, were extremely important in determining numbers of Connecticut River shad passed over the Holyoke Dam, Massachusetts. A diversion then, even during peak periods of flow, may have some effect on spawning success of American shad, and downstream movement of juveniles may be affected also, although specific studies dealing with causal relationships behind juvenile movements are not at hand. Watson (1970) did suggest, however, that juvenile migration commences in September and continues through October in the Connecticut River, so extreme low water conditions encountered during summer months may not be of consequence.

## e. THE ALEWIFE, Alosa pseudoharengus

HISTORIC IMPORTANCE TO THE AREA: Historically, large numbers of alewives entered the Merrimack River each year to spawn, and as late as

1896 when the alewife fishery was the subject of inquiry by the

Bureau of Fisheries, catches large enough to be worthy of special

notice were reported at the mouth of the Merrimack River. However,

with the construction of dams and the increase in pollution resulting from industrialization, alewive runs declined precipitiously. Although few alewives enter the Merrimack today due to gross pollution and physical obstructions, fishways recently constructed at Lowell, Massachusetts, facilitate their ascent, at least this far. Projected pollution abatement schedules and construction of additional fishways give promise of potential comeback of this species in the future.

PERTINENT ASPECTS OF LIFE HISTORY: (Excerpted from Bigelow and Schroeder, 1953.) The alewife is an anadromous fish, and with the exception of spawning season, the adults spend all of their time at sea.

Alewives are chiefly plankton feeders, with some evidence of selectivity for copepods, amphipods, shrimp, and appendicularians. They may also take small fish such as herring, eels, sand lance, and cunners.

Alewives enter small streams in April to spawn, and while the species is very general in choice of stream, it is believed that individuals return to the stream in which they were hatched. The alewife is more successful than the shad in surmounting fishways of suitable design, and in large rivers the fish may run far upstream. Most individuals do not eat when they are going upstream.

Sexually mature adults spawn in ponds and sluggish stretches of streams, but never in swift water. Spawning lasts only a few days, and then spent fish return downriver immediately thereafter. Adults

make the rapid change from saltwater to freshwater and back again without damage, but the strain of spawning leaves the fish thin. They feed ravenously on shrimps and other small organisms upon entering brackish water, and recover rapidly when they enter the sea.

Spawning occurs at 55° to 60° F, and the juveniles hatch in approximately five days at this temperature. They begin to descend the stream as early as June 15, continue all summer, and by autumn the two to four inch young are in saltwater, and remain there until sexual maturity.

At sea alewives are gregarious like herring, and a given school maintains its integrity for extended periods of time. It is likely that the majority remains in the vicinity of the freshwater influence of stream mouths and estuaries from which they came, although individuals have been found as far out as the banks.

PROJECTED EFFECTS OF DIVERSION ON THE ECOLOGY OF THE SPECIES: Even though few alewives presently enter the Merrimack River, a comeback potential does exist for the species if properly designed fish ladders are constructed and pollution is lessened. Though adult upstream migration occurs in spring when flows are usually high, presumably alewives exhibit rheotaxes similar to the shad and may require similar attraction velocities. Young alewives on the other hand may be more

susceptible to low flow conditions during the summer since they descend the river throughout this period and may experience high mortality due to inability to go over dams or bypass them, except via turbine intakes.

As in the case of the shad and salmon, the success of restoration of this valuable fishery depends on strict adherence to minimum required flows arrived at through consultations with biologists involved in state and federal anadromous fisheries programs.

## f. THE BLUEBACK HERRING, Alosa aestivalis

According to Bigelow and Schroeder (1953), the blueback herring, Alosa aestivalis, is nearly identical to the alewife both in physical appearance and in life history. There are some minor differences in breeding habits, including runs later in the season when the water is warmer, and spawning shorter distances upriver. Because of the apparent similarities in the biology of these two species, conclusions drawn from the alewife should also pertain to the herring.

## g. THE ATLANTIC MACKEREL, Scomber scombrus

ECONOMIC IMPORTANCE TO THE AREA: According to Jerome, et al (1965), mackerel fishing is one of the chief sport attractions in the Plum Island area. Mackerel often arrive at the mouth of the estuary in late

spring or early summer, and they are intensively fished by private, party, and charter boats from this time until their departure in fall. The mackerel fishery forms the main-stay of the party boat business in summer, and contributes thousands of dollars to the economy of the area each year.

PERTINENT ASPECTS OF LIFE HISTORY: The mackerel is an open ocean fish, and while small individuals may enter estuaries and harbors in search of food during the summer, they never enter freshwater. Mackerel appear in great numbers inshore as temperatures rise, and they remain close to the surface to feed for indefinite periods of time during the summer. With the onset of colder temperatures the mackerel migrate to deeper offshore waters. Most aspects of life history, including feeding, spawning, and larval development, take place in open ocean waters.

PROJECTED EFFECTS OF DIVERSION ON THE ECOLOGY OF THE SPECIES: The mackerel often appear in great numbers at the mouth of the Merrimack River Estuary and adjacent areas around Plum Island, possibly to feed on locally abundant marine organisms such as sand lance and clam worms. Since freshwater diversion should not diminish the abundance of these or any other primary prey species, no effect on the local mackerel fishery should be evidenced.

### h. THE WINTER FLOUNDER, Pseudopleuronectes americanus

ECONOMIC IMPORTANCE TO THE AREA: According to Jerome, et al (1965), the winter flounder, <u>Pseudopleuronectes americanus</u>, is one of the most important sport and commercial fishes found in the Merrimack River Estuary. Most of the present day commercial catch is taken in the open ocean using otter trawlers, but an extensive sport fishery occurs over the shallow flats and deeper channels of the Merrimack River Estuary, and in its tidal tributaries. No estimate of the size of the sport catch has been made, but it is believed to be large.

PERTINENT ASPECTS OF LIFE HISTORY: The winter flounder is the commonest and most familiar bottom fish found in the Gulf of Maine. Bigelow and Schroeder (1953) indicate that it is a cosmopolitan species, running from the intertidal in estuaries up to freshwater, and going as deep as 70 fms in the open ocean. Smaller fish are usually found in shoal water, and larger ones tend to live deeper. The winter flounder usually lies on the bottom buried in sand or mud, with all but the eyes covered, and darts out rapidly to capture prey. Most spawning occurs in deep water where salinities are above 30 °/oo, but some spawning individuals are reported in estuaries in one to three fms of water and salinities as low as 11 °/oo. The eggs are non-buoyant, and sink to the sandy bottom, where they hatch in from 12 to 14 days. Metamorphosis occurs rapidly, and the young fry soon change from a diet of diatoms

to crustaceans and other small invertebrates.

potential effects of diversion on the ecology of the species: The winter flounder spawns over a wide range of salinities, and it is generally considered to be euryhaline throughout its life. However, although periodic increases in salinity of the estuary are not expected to have any marked affect on this species, recent evidence has shown that winter flounder exhibit a definite preference for estuarine waters during parts of their life cycle (Frame, 1972).

## i. THE AMERICAN EEL, Anguilla rostrata

ECONOMIC IMPORTANCE TO THE AREA: The American eel, Anguilla rostrata, played an important role in the economy of the Merrimack River Valley region in the past, when it was in demand as a food or table fish (Jerome, et al, 1965). Significant numbers of eel were taken in pots placed in the tidal portions of the Merrimack River, and up to 7,000 pounds per week were shipped to markets in Boston and New York. The fishery has undergone a precipitous decline in recent years, primarily due to a reduction in demand, and by 1964 only 3,000 pounds per year (with a total value of \$540.00) were taken for both food and bait. The primary use of eels today is as live bait for the striped bass fishery.

PERTINENT ASPECTS OF LIFE HISTORY: Many aspects of the life history of the American eel have been unknown until recently, but it is now certain that the species is catadromous; that is, it spends most of its life in fresh or estuarine waters, and returns to the deep sea to spawn.

(The life history of Anguilla rostrata is adapted from Bigelow and Schroeder, 1953.)

Young elvers, two to three and a half inches long, appear in coastal waters in spring, and invade all waters entering the Gulf of Maine. Some elvers settle in tidal marshes and harbors, and some even remain in protected coastal areas, especially if there is Zostera present. Most, however, enter freshwater, and many go up into the fartherest reaches of the river. They can live and thrive wherever food is available, and can tolerate the whole spectrum of salinity and a wide range of temperature. No animal food, living or dead, is refused, and the diet depends on what is available.

American eels are chiefly nocturnal in habit, but they are often seen during the day. They grow slowly, and may take ten to twenty years to mature. At the onset of sexual maturity in the fall, the eels that are living in freshwater move downstream, cease to feed, and undergo physiological change. Individuals living in estuarine conditions undergo the same changes, and all mature individuals of both sexes then move out to sea, where the ovaries of the female begin to ripen.

After leaving the shore the eels disappear and it is believed that they re-appear in the Sargasso Sea, one to two months later.

They spawn in mid-winter, and die immediately thereafter. The eggs float until hatching into a leptocephalus stage, and metamorphosis takes place a year later after the leptocephali have migrated to offshore waters. After metamorphosis, the elvers continue their migration to shore.

PROJECTED EFFECTS OF DIVERSION ON THE ECOLOGY OF THE SPECIES: The American eel was found in low numbers throughout most of the study area, and Jerome, et al (1965) found it living in salinities ranging from 0.0 % to 18.0 % oo.

Because the American eel is extremely tolerant to both salinity and temperature variation, and considering the wide variability of food eaten, there is no reason to believe that diversion of freshwater from the Merrimack River would have any effect on its distribution and abundance.

## ECOLOGICAL STUDY

MERRIMACK RIVER ESTUARY - MASSACHUSETTS

VI. POTENTIAL EFFECTS OF DIVERSION ON THE PARKER RIVER ESTUARY AND THE PARKER RIVER NATIONAL WILDLIFE REFUGE

#### ECOLOGICAL STUDY

#### MERRIMACK RIVER ESTUARY - MASSACHUSETTS

VI. POTENTIAL EFFECTS OF DIVERSION ON THE PARKER RIVER ESTUARY AND

THE PARKER RIVER NATIONAL WILDLIFE REFUGE

Major tidal channels have a significant influence on estuarine circulation patterns, and the Plum Island River (Figure 1) is the largest major tidal channel in the region (Hartwell, 1970). It connects the Merrimack River Estuary with the Parker River Estuary and flows through the heart of the Parker River National Wildlife Refuge. Because Refuge wildlife are attracted to the area by the richness of the estuarine waters of the Plum Island River, it is important to determine if the Merrimack River contributes substantially to these waters.

The Plum Island River is very shallow in places, and numerous sand and mud flats restrict flows between the systems to a minimum except at highest tides. Hartwell (1970) has shown that even though there is considerable hydraulic exchange between the two estuaries, the nature and orientation of sand bars and spits indicate that ebbtidal currents flowing from the Parker River Estuary into the Merrimack River Estuary are dominant over flood currents passing in the reverse direction. In addition, a study of the charts prepared by Hartwell

(1970) and results of discussion with Goldsmith (1971) indicate that the interface between the two water masses tends to oscillate back and forth with each tidal cycle resulting in little net exchange between the systems. Therefore, in spite of the connection between the two systems, we have found no evidence to indicate that changes in salinity in the Merrimack River Estuary will affect the Refuge. Mr. Edward Moses, Director of the Parker River National Wildlife Refuge, has concurred in this belief.

## ECOLOGICAL STUDY

MERRIMACK RIVER ESTUARY - MASSACHUSETTS

VII. SUMMARY, CONCLUSIONS, AND RECOMMENDATIONS

#### ECOLOGICAL STUDY

# MERRIMACK RIVER ESTUARY - MASSACHUSETTS

VII. SUMMARY, CONCLUSIONS, AND RECOMMENDATIONS

## A. SUMMARY OF MAJOR ELEMENTS STUDIED

## 1. Salinity Study - Mathematical Model:

The mathematical model used to investigate the effects of diversion on the salinity of the Merrimack River is based on the salt-balance equation of Pritchard (1959), as modified by Boicourt (1968). This model was selected because it was the most realistic model that could be used, consistent with the input data available.

The results of the study are presented as a graphical atlas of the salinity distribution along the longitudinal axis of the estuary. Each entry in the graphical atlas represents the effect of given diversion at various river flows. The effects at both low and high tide are considered.

The limits of salt intrusion vary from 7 Km (4.3 statute miles) to 17.5 Km (10.9 statute miles) from the mouth, representing river flows from 16,000 cfs to 800 cfs, respectively for the high tide case. For the low tide case, the limits of salt intrusion vary from 5 Km (3.1

statute miles) to 11 Km (6.8 statute miles) from the mouth, representing river flows from 16,000 cfs to 800 cfs, respectively.

The model is found to agree reasonably well with the results of measurements over the range of flow rates investigated. The model over predicts slightly under some conditions based on the limited experimental data available for verification; more data or verification would be of value for the lower flow rates. Since the coefficient determining the diffusion rates are based on the input data, the use of the model outside the range of validation should be done with caution.

- 2. Potential Effects of Diversion on the Physical Characteristics of the Estuary:
- a. Longitudinal Changes in Salinity Distributions and Alterations of Estuarine Conditions.

The Merrimack River Estuary is essentially fresh throughout most of the tidal cycle, but saline water progresses further upstream as discharge drops. While natural flows rarely drop below 800 cfs (control level established for October through May) on an average weekly basis, the daily operational pattern of the several dams along the Merrimack River is such that flows fluctuate markedly within a week. This is reflected in monthly averages of daily minima which are in fact below control levels during summer and early fall months.

with this fluctuation in mind, we may say that although certain stretches of the river may be subjected to more frequent saline influence due to diversion, this should not represent an entirely new experience. Increased time of exposure to particular salinities would depend upon flow rate, and for the range of diversions considered here (100 to 2,000 cfs), this time would be minimal under peak dischange and greater as flows decrease.

Seasonal patterns of longitudinal salinity distribution are markedly different due to amount of discharge, yet within any given season the pattern is displaced only 1/2 to 1 and 1/2 miles upstream at the highest rates suggested. Salinity encroachment at control levels is higher, ranging from 2 to >5 miles upstream depending upon season, but intrusions this far and further upriver do occur periodically under extreme low flow conditions.

Tidal oscillations produce changes in the longitudinal salinity pattern amounting to approximately 4.5 miles (7 to 8 Km). Such changes would persist with diversion, but oscillations would merely be about a node further upstream.

Additional effects which diversion may have upon the Merrimack

River Estuary have to do with circulation patterns, and, in turn, their effect on certain other physical parameters. Workers have shown that vertical stratification in the estuary depends upon river discharge (i.e., under low flow rates the estuary becomes progressively more well-mixed). Such changes must be considered as they relate to the ecology of the area.

#### b. Alterations in Suspended Sediment Distribution

Ocean water entering the estuary carries less sediment than river water. When Merrimack River flows are high, most sediment is flushed out of the estuary, but as discharges drop to normal levels and stratification develops, sedimentation becomes heaviest over Joppa Flats. When stratification breaks down under summer and fall low flows, sedimentation tends to occur rather evenly throughout the estuary.

1) Diversion of freshwater will reduce the total load of suspended sediments brought into the estuary, but at the same time will also lower the flushing rate, possibly resulting in a net increase in deposition. Because of changes in circulation brought about by lower flows, deposition should generally be reduced over Joppa Flats, and somewhat increased throughout the rest of the estuary.

c. Net Inflow of Bottom Sediments Resulting from Changes in Current Flow

Current velocities entering the Merrimack River Estuary on the flood tide tend to be considerably stronger than those leaving on the ebb, and these currents are active in the formation of a flood tidal delta through a net influx of sediment into the estuary.

Estuary is at present relatively stable. Goldsmith has suggested that a reduction in river discharge could lead to an increased rate of sediment movement, and a net migration of the flood tidal delta into the estuary. This could result in changes in circulation within the estuary through clogging, and increased erosion along Plum Island. Continual dredging to remove sediments would alleviate the first problem.

#### d. Upper Estuarine Temperature Changes

Daily and seasonal temperature variability in river water is generally more pronounced than in ocean waters, with summer temperatures warmer and winter temperatures colder. Because of this, freshwater diversion could affect the temperature characteristics of the Merrimack River by leading to a reduction in temperature fluctuations in the upper estuary, and to summer low flow/high temperature conditions in

the freshwater river. Further studies are suggested to determine the extent of the latter.

### e. Changes in the Effect of Pollution Load

Because of domestic and industrial pollution, dissolved oxygen readings presently drop to critical levels under low flow/high temperature conditions in late summer and early fall. It is probable that unless pollution is abated, diversion during this time period may further aggravate the situation.

## 3. Potential Biological Changes Resulting From Diversion:

#### a. Intertidal Plants

compared with other estuarine environments, plant species diversity is low in the Merrimack River Estuary. At least 37 taxa of vascular plants are found in the estuarine portion of the river, with 14 species widely distributed and the remainder only occurring sporadically. Twenty-eight taxa of algae are found in the same region, but only the green algae are cosmopolitan throughout the study area.

Preliminary observations indicate that distribution is primarily controlled by presence or absence of suitable substrata, salinity, sedimentation, and pollution load. No vascular plants are found at the lower stations, primarily due to the absence of suitable substrata.

With progression upriver, rocky shores give way to mud and sand, and the number of intertidal vascular plants increase, until reaching greatest diversity at Stations 18 through 20. Beyond this point salt water species drop out and are replaced by typically freshwater species. No salt water species are found above Station 28.

As opposed to the vascular plants, maximum numbers of algae are found in the lower estuary. These plants rapidly diminish in numbers above Station 6, and show a progressive dropping out of species with upriver progression until none are found above Station 26.

One of the principle effects of diversion should be an alteration of the delicate balance between freshwater, brackish water, and salt water species, evidenced by changes in distribution and abundance. An increase in salinity resulting from diversion would probably allow upriver movement of marine or estuarine algae such as A. nodosum and F. vesiculosus, and therefore alter existing community composition. Typically estuarine vascular plants such as Spartina spp. would also go further upriver and replace freshwater species. Other changes in plant communities, as yet undefined, may result from alteration of current flow and velocity, changes in sediment transport and patterns of deposition, reduction of seasonal temperature variation, and changes in pollution load. Further studies would be needed to determine the nature of these changes.

#### b. Intertidal Invertebrates

Forty-seven species of invertebrates were collected in the Merrimack River Estuary during the sampling period. Sixteen species were only found outside the harbor entrance, 26 were found in the estuary proper, and five species were restricted to the freshwater river. Of the 26 species living within the estuary, 19 were euryhaline marine organisms, four were true estuarine organisms found exclusively in the estuarine environment, and three were freshwater species capable of withstanding periodic low salinities.

The distribution of intertidal invertebrates in the Merrimack River Estuary exhibit a definite progression of invertebrate associations extending from the open ocean to the freshwater river. These associations, and their approximate locations in the river, can be roughly classified as stenohaline marine (open coast), euryhaline marine (0-1 miles upriver), true estuarine (1-5 miles upriver), impoverished freshwater (5-9 miles upriver), and freshwater (above 9 miles).

The marine association contains the highest number of species found at any location in the estuary, and approximately 75% of these species are stenohaline (intolerant of lowered salinities). The eury-haline marine association just upriver contains far fewer species, and is in reality an impoverished extension of the open ocean community. All organisms living in this region are generally found in the oceanic

environment, but in contrast to stenohaline forms, they are capable of surviving periodically reduced salinities.

In the estuarine zone extending from miles 1 through approximately 5, five species of true estuarine marine species and a few salt-tolerant freshwater species. As one progresses upriver, the euryhaline marine organisms rapidly drop out, and the association becomes dominated by true estuarine species. Salinity fluctuations in this area are drastic, and during periods of low flow, mobile euryhaline marine species will migrate into the area, producing a noticeable increase in species numbers. These species are generally unable to establish permanently, however.

The estuarine fauna becomes progressively reduced from miles 5 through 9, and increasing numbers of salt-tolerant freshwater species begin to appear. Salinities are too low for most estuarine species, and periodically too high to permit establishment of typical freshwater species. Because of the severity of these conditions, along with the effects of pollution and sedimentation, this region presently represents the most unsuitable habitat in the Merrimack estuarine system.

Species diversity increases in the freshwater zone beyond mile 8, but it is still well below that found in other rivers of comparable size, due to the combined effects of pollution and sedimentation.

The stenohaline marine association should not be affected in any manner by freshwater diversion, since the habitat presently is under little influence from the estuarine environment. Some changes in species composition, however, may occur in the euryhaline marine zone. It is likely that with an increase in salinity there will be a net migration of several additional marine species into the area, and an increase in abundance of some species already there. An introduction of these species should not lead to interspecific competition, since they presently exist outside the estuary.

More significant changes could occur in the estuarine zone, the net effect of which would undoubtedly be to increase the total number of species. There should be a net upriver migration of several species along the length of the estuary in response to increased salinity. In the lower estuary, this shift could bring euryhaline marine organisms into the area now occupied by estuarine species. In addition, if algal and vascular plant growth is enhanced either through increased salinities or decreased sedimentation, as has been suggested previously, it is possible that intertidal invertebrates now feeding or living on these plants in the lower zones will move into this area to fill the newly established niche. In the upper estuary, some salt tolerant freshwater species, now present in low abundance in the upper reaches of the estuarine zone, may shift further upriver with increased salinities.

Any change in the impoverished freshwater zone will probably be beneficial. It is now in a serious state of ecological stress due to a combination of pollution and low level salt intrusion. A decrease in river discharge would probably permit migration of some estuarine species into this area, but should have little effect on the few salt-tolerant freshwater species existing there in low abundance, since they are presently found in higher salinities downriver. If diversion is preceded by a decrease in pollution, followed by an increase in oxygen and a reduction of sedimentation, a further enrichment of the fauna in this habitat would result.

No migration of estuarine organisms into the freshwater zone is possible, since the salt water, after diversion, would not intrude beyond the limits presently reached.

#### c. Subtidal Benthic Invertebrates

The results of benthic sampling demonstrated that the benthic fauna of the Merrimack River Estuary is extremely limited in species numbers. Eighteen species of bottom invertebrates were found during the sampling period, but only 15 were collected alive. Of these species, three were marine, three were truly estuarine, and the remainder were typically freshwater. The largest number of species was found at the freshwater stations above mile 12, while no living organisms were collected at three of the estuarine stations. Diversity was extremely low at the remaining stations.

Because of this low species diversity throughout the estuary, resulting from a combination of factors, it is difficult to hypothesize on the effects of diversion. The existing maximum upriver intrusion of salt water will not change, so unless abatement of pollution produces more optimal conditions, an increase in species diversity in the freshwater zone should not occur. However, the portion of the estuary now subject to salt intrusion will be saline more often, probably resulting in a net upriver migration of some estuarine and marine species, particularly those with larvae now existing as plankton in the Merrimack River Estuary. The extent of the upriver migration cannot be predicted at this time.

#### d. Plankton

The overall composition of plankton in the Merrimack River Estuary is typical of large estuaries where resident plankton populations are maintained as a result of incomplete flushing. At all times plankton species diversity was greatest in the lower estuary, and lowest in the upper. Typically marine-estuarine assemblages were found in surface and near-bottom tows from the lower estuary, but estuarine organisms were only found in bottom tows in the upper estuary. Surface tows contained only freshwater species at these stations. A consistently greater number of individuals and taxa categories was found in near-bottom samples than in surface samples.

The net effect of river diversion will probably be a slight up-

river shift of euryhaline marine and estuarine species during diversion, but this extension should not exceed that found during the low flow periods which occur naturally. This extension will affect the meroplankton to a greater extent than the holoplankton, in that holoplankters should merely oscillate about some zone farther upriver than present, but meroplankters which lead a benthic adult existence may encounter new substratum conditions which may be unsuitable for some, but which may induce settlement of others, leading to an upriver extension of their range.

Although there will not be an upriver intrusion of saline water beyond areas that are now periodically affected by low level salinities, the area between mile 1 and the mouth of the estuary will be under stronger marine influence. Present dominant euryhaline species in this region should not change, but marine species might extend farther into the estuary. An upriver shift in plankton communities could result in an upriver shift of organisms which feed on them. It is not expected, however, that new species will be introduced as a result of diversion.

In addition to longitudinal effects, vertical distribution of plankton may also be disrupted since water stratification breaks down during periods of low flow.

#### VII-15.

#### e. Commercially Important Invertebrates

The soft-shell clam, Mya arenaria, is the only commercially valuable shellfish in the Merrimack River Estuary. Because of pollution in the river, this valuable resource is not presently utilized. However, it is estimated that with proper management the harvest could approach one million dollars annually.

The effects of diversion upon the soft shell clam center upon possible changes caused by salinity and sedimentation patterns. Since the clam is tolerant to a wide range of salinities, it is unlikely that salinity increases will have any directly negative effect on its distribution and abundance. If any direct effect is observed, it will most likely be an increase in abundance on those flats now exposed to suboptimal salinities. Spawning in the clam appears to be temperature regulated, but since diversion should not result in significant temperature changes in the lower estuary, spawning should not be affected.

Changes in patterns of suspended sediment deposition should not affect the distribution and abundance of clams, but if decreased river discharge results in an increased accretion of the flood tidal delta, it is possible that some flats could be partly covered, This, of course, would not happen if dredging prevented sand accumulation.

In the Northeast, the clam is threatened by predation from the

green crab, the horseshoe crab, and the moon snail. While none of these predators are presently found on the clam flats, they are living at the mouth of the estuary. Since their distribution and abundance is greatly affected by salinity, it is possible that an increase in salinity could lead to a migration of clam predators onto the flats. Studies dealing with this probability should be explored.

#### f. Finfish

Even though pollution has seriously reduced the quality of the natural habitat, the Merrimack River Estuary remains rich in diversity and abundance of fishes. Because of the limited amount of data available on life histories of individual species, there is no way of accurately assessing the total impact of a river diversion on all components of the finfish community. However, it is possible to make certain predictions concerning changes that could occur in the ecology of the most abundant species and species of sport and commercial interest.

- 1) Sand Lance Because of the intolerance of the sand lance for lowered salinities, it is probable that a reduction in freshwater flow into the estuary could result in a net upriver increase in suitable habitat, and the possibility of an increase in size of the resident population.
- 2) Striped Bass The striped bass is equally at home in fresh, brackish, and coastal waters, and in light of the observation that the Merrimack River Estuary is neither a spawning area nor an important over-wintering habitat, diversion of freshwater should have little observeable effect on the ecology or biology of this species.

- 3) Atlantic Salmon At present, federal and state fisheries biologists are working to restore natural runs of Atlantic salmon to the Merrimack River. If flow augmentation during low flow periods becomes an important part of such restoration, diversion flows should not intrude on such augmentation plans. Minimum flow limits are extremely important for the success of this restoration program, since both the survival of the smolts in their seaward migration and the success of spawning adults in reaching spawning grounds depend on a sufficient supply of freshwater at specific times throughout the year. In view of this, any diversion plan should consider the salmon restoration program, and the flows necessary to ensure its success.
- 4) Shad As in the case of the salmon restoration program, success in shad restoration depends on the presence of minimum flows at certain times of the year, particularly when adults are returning to the spawning grounds and juveniles are migrating to the seas. In addition, success in both restoration programs will only come after additional problems, such as pollution abatement and construction of effective fish ladders, are resolved.
- 5) Alewife and Herring It is probable that alewife and herring runs will become re-established on the Merrimack River when suitable fish ladders are constructed. As is the case for the shad and salmon, minimum flows are essential for successful re-establishment of the species.
- 6) Atlantic Mackerel Mackerel is an open ocean fish, even though it often feeds inshore. Since diversion should have no effect on any important prey species, no effect on the mackerel population should be seen.
- 7) Winter Flounder The winter flounder spawns over a wide range of salinities, and is considered to be euryhaline throughout its life, but shows a preference for estuarine waters at certain ages. A periodic increase in salinity in the estuary should not greatly affect the ecology of the species, but its metabolic requirements should be considered further.
- 8) American Eel The American eel is extremely tolerant to both salinity and temperature variation, and considering the wide variety of their diet, there is no reason to believe that diversion of freshwater from the Merrimack River would have any effect on its distribution and abundance.

# 4. Potential Effects of Diversion on the Parker River Estuary and the Parker River National Wildlife Refuge:

Estuary and the Merrimack River Estuary are connected, there apparently is little net exchange between the two systems. Because of this, there is no evidence to indicate that changes in salinity in the Merrimack River Estuary will affect the Parker River Estuary and the Parker River National Wildlife Refuge in any manner.

#### B. CONCLUSIONS

Because of the complexity of an ecosystem, simplistic answers relating to effects of physical changes are usually not possible. The reliability of predicting ecological effects resulting from alterations of the physical environment is generally dependent upon the magnitude of the proposed change.

A review of the proposed diversion schemes, as outlined in Sections I, III, and IV of this report, indicates that certain diversion rates would probably have no detectable effects on the ecology of the Merrimack River Estuary. However, other diversion rates may produce effects. These could be either desirable or undesirable. It is not possible, however, to make definite predictions on the magnitude of these effects, but only to describe them as significant

or insignificant.

Several important criteria have emerged in the evaluations of possible ecological effects on diversion. These are based essentially on present normal fluctuations of various environmental conditions occurring within the estuary and include normal periods of salinity stratification and mixing; normal salinity distribution within the length of the estuary; minimum flows which occur within the estuary; and normal variations in temperature, dissolved oxygen, and sediment rates.

By incorporating the suggested diversion rates and control flows proposed in the scope of work outlined in the project description, and reviewing the historic record of flows for the period 1927-1967, the projected changes in salinity distribution generated by the mathematical model, the results of biological field investigations, literature research, and consultation with various organizations and agency personnel, the following evaluations have been made.

In our best judgement, at diversion rates of

100 cfs	No significant ecological effects are predicted for any month of the year.
300 cfs	It is unlikely that any significant ecological effects would occur during any month of the year.
500 cfs - 80	O cfs No significant ecological effects are predicted for the months of January, February, March, April, May, June, November, or December. However, during

the months of July, August, September, and October, the prediction is made that effects are possible, but there is insufficient data to speculate on their magnitude.

1,100 to 2,000 cfs July, August, September, and October - Significant ecological effects are probable.

January, February, June, November, and December - Effects are possible but cannot be predicted.

March, April, and May - No effects are expected.

The proposal to provide upstream storage during high flow, and flow augmentation during low flow periods, has also been evaluated for possible ecological effects. A review of the proposed diversion rates, ranging from 185 cfs to 8,050 cfs, indicates that effects may be expected during spring when water is being stored. While the magnitude of ecological effects during spring storage is unknown, it should be emphasized that these flows are essential in maintaining the ecological balance of any river or estuary. This is particularly true for anadromous fishes. During periods of low discharge, flows would be augmented to maintain desired diversion rates without exceeding control levels, and thus the estuary should not experience any change. Additional studies incorporating proposed retention rates and discharge schedules should be conducted if this plan is implemented.

Although no additional effects are postulated for the Merrimack

River Estuary other than those relating to the net reduction in flows as discussed in the previous section, higher flows experienced above the point of diversion resulting from augmentation may produce significant effects and should be considered in the future.

#### C. RECOMMENDATIONS

It is recommended, based on the data collected and the results summarized in this section, that as a part of the proposed diversion a carefully developed ecological monitoring program be implemented. This should consist of both pre- and post-operational monitoring. Operation of the diversion system should be keyed to the result of this monitoring. In addition, it is recommended that studies on possible ecological effects of diversion be continued to further refine the present predictions. Areas of study should include a survey to determine the exact flow rates at which salinity destratification occurs within the estuary and river. More detailed studies should be conducted of possible effects of proposed diversion rates on sediment deposition and sand movement, changes in water temperature, and possible intrusion or upstream movement of predators.

Since diversion systems are by their design controllable, operation of the system should be regulated so effects on the estuary remain minimal. It is suggested, therefore, that operation should be coordinated with information derived from the ecological monitoring program.

### ECOLOGICAL STUDY

MERRIMACK RIVER ESTUARY - MASSACHUSETTS

VIII. LITERATURE CITED

AND BIBLIOGRAPHY

#### LITERATURE CITED

- Baptist, J. P., O. R. Smith, and J. W. Ropes, 1957. Migrations of the horseshoe crab, <u>Limulus polyphemus</u>, in Plum Island, Massachusetts. U. S. Fish and Wildlife Service Spec. Sci. Report 220. 15 pp.
- \*Barnes, R. D., 1963. <u>Invertebrate Zoology</u>. W. B. Saunders Company, Philadelphia, Pa. 632 pp.
- Bigelow, H. B., 1924. Plankton of the offshore waters of the Gulf of Maine. Bull. U. S. Bur. Fish. 40 Part II. pp. 1-509.
- Bigelow, H. B. and W. C. Schroeder, 1953. Fishes of the Gulf of Maine. Fishery Bull. 74. Fish. Bull. of the Fish and Wildl. Ser. Vol. 53. U. S. Government Printing Office, Washington, D. C. 577 pp.
- \*Blacker, R. W., 1957. Benthic Animals as Indicators of Hydrographic Conditions and Climatic Change in Svalbord Waters. Ministry of Agr. Fish and Food, Fishery Invest. Ser. II 22(10: 1-49.
- Bouck, Gerald, 1969. Early tests show salmon can't take warm water.

  Report by Marge Davenport. The Oregon Journal, November 20, 1969.
- Boicourt, W., 1968. A Numerical Model of the Salinity Distribution in Upper Chesapeake Bay. Tech. Rpt. 54, Chesapeake Bay Insti., The Johns Hopkins University.
- Broekhuysen, C. J., 1937. On development, growth, and distribution of <u>Carcinides maenas</u> (L.). Archives Neerlandaises de Zoologie, Vol. II, 257-399. Leiden.
- \*Camp, T. R., 1947. Report on the disposal of sewage in the Merrimack River Valley. Comm. Mass. 404 pp.
- \*Camp, T. R., Dresser and McKee, 1963. Report on pollution control for the Merrimack River. Mass. Dept. of Public Health. 216 pp.
- \*Chapman, V. J., 1938. Studies in salt-marsh ecology, I-III. J. Ecol. 26(1): 144-179.
- \*Chapman, V. J., 1939. Studies in salt-marsh ecology, IV-V. J. Ecol. 27(1): 160-201.
- Clarke, G. L., 1954. Elements of Ecology. John Wiley and Sons, Inc. New York. 534 pp.

- \*Cross, F. A. and L. F. Small, 1967. Copepod indicators of surface water movements off the Oregon Coast. Limnol. Oceanogr. 12(1): 60-72.
- Daly, J. V., A. F. Ferullo and W. R. Jobin, 1970. Data record of water quality monitoring station on the Merrimack River at West Newbury, Massachusetts from August 1968 to September 1969. Water Qual. Management Section, Div. of Water Poll. Cont., Mass. Water Res. Comm.
- Deevey, G. B., 1952a. A survey of the zooplankton of Block Island Sound, 1943-1946. Hydrographic and Biological Studies of Block Island Sound, Bingham Oceanogr. Lab. Bull. 14:3 65-120.
- Deevey, G. B., 1952b. Quantity and composition of the zooplankton of Block Island Sound, 1949. Hydrographic and Biological Studies of Block Island Sound, Bingham Oceanogr. Lab. Bull. 14:3 120-165.
- Dorrestein, R., 1960. A Method of Computing the Spreading and Matter in the Water of an Estuary. Disposal of Radioactive Wastes; Intern. At. Energy Agency, Vienna, 163-166.
- Fernald, M. L., 1950. Gray's Manual of Botany, 8th Ed., American Book Company, New York. 1632 pp.
- Forste, Robert H., Editor. Proceedings. The New England Conference on River Diversions, May 1971. The Water Resources Research Center, UNH, Durham, New Hampshire. 162 pp.
- Frame, David M., 1972. Biology of young winter flounder, <u>Pseudopleuronectes</u> <u>americanus</u> (Walbaum), feeding habits, metabolism and food utilization. University of Massachusetts (Unpublished Dissertation).
- \*Fraser, J. H., 1952. The Chaetognatha and other zooplankton of the Scottish area and their value as biological indicators of hydrographical conditions: Scot. Home. Dept. Mar. Res., No. 2, Edenburgh.
- Fraser, J. H. and V. Kr. Hansen, 1960. Fiches d'identification du zooplankton. Andre, Fred. Host and Fils, Copenhague. Sheet 86 and 87 (Rolatoria).
- \*Gosner, K. L., 1971. <u>Guide to the Identification of Marine and Estuarine Invertebrates</u>. Riley-Interscience, New York. 693 pp.
- Goucher, Franklyn E., 1951. Commentary of a Clam Digger. (Unpublished Manuscript).
- \*Grainger, E. H., 1963. Copepods of the genus <u>Calanus</u> as indicators of eastern Canadian waters. <u>In</u>: Marine Distributions, M. J. Dunbar (Ed.)

- Green, J., 1968. The Biology of Estuarine Animals. Univ. of Washington Press, Seattle. 401 pp.
- Gunter, G., 1961. Some relations of estuarine organisms to salinity. Limnol. & Oceangr. 6: 182-190.
- Hanks, J. E., 1953. Comparative studies on the feeding habits of Polinices heros and duplicata relative to temperature and salinity. Fourth Annual Conference on Clam Research. U. S. Fish and Wildl. Ser., Boothbay Harbor, Maine. pp. 88-95.
- Hansen, D. V. and M. Rattray, Jr., 1965. Gravitational Circulation in Straits and Estuaries. J. Mar. Res. (23): 104-122.
- Hartwell, Allan D., 1970. Hydrography and Holocene Sedimentation of the Merrimack River Estuary, Massachusetts. Contri. No. 5-CRG Dept. of Geo., University of Mass. 166 pp.
- Hayes, M., V. Goldsmith, and K. Hobbs, III., 1970. Offset Coastal Inlets. Proc. 12th Coast. Eng. Conf. Sept. 1970. Washington, D. C. pp. 1187-1200.
- Hessler, R. R. and H. L. Sanders, 1967. Faunal diversity in the deep sea. Deep Sea Res. 14: 65-78.
- Hetling, L. J., 1968. Simulation of Chloride Concentrations in the Potomac Estuary. Fed. Water Poll. Cont. Adm., CB-SRBP Tech. Rept. No. 12, 29 pp.
- Hildenbrand, F. B., 1968. Finite-Difference Equations and Simulations.

  Prentice-Hall, Inc., Englewood, Cliffs, 338 pp.
- \*Holden, R. P., 1958. The Merrimack. Rinehart, New York. 306 pp.
- Jerome, Wm. C., Jr., A. P. Chesmore, C. O. Anderson, Jr., and F. Grice, 1965. A study of the marine resources of the Merrimack River Estuary. Monograph Ser. No. 1, Div. of Mar. Fish., Dept. of Natl. Res., The Comm. of Mass. 90 pp.
- Jerome, W. C., Jr., A. P. Chesmore, and C. O. Anderson, 1968. A sutdy of the marine resources of the Parker River-Plum Island Estuary. Monograph Ser. No. 6, Div. of Mar. Fish., Dept. of Natl. Res., The Comm. of Mass. 79 pp.
- Johnson, M. W., 1957. Plankton. <u>In</u>: Treatise on Marine Ecology and Paleoecology, J. W. Hedgpeth (Ed.) Vol. 1, Geo. Soc. of Amr., Mem. 67, New York. pp. 443-461.

- Ketchum, B. H., 1950. Hydrographic Factors Involved in the Dispersion of Pollutants introduced into tidal Waters. Jr. of the Boston Soc. of Civil Engr. Vol. 37: 296-314.
- \*Kinne, O., 1963. The Effects of Temperature and Salinity on Marine and Brackish Water Animals. I. Temperature. Oceanogr. and Mar. Biol. Ann. Rev. 1: 301-340.
- \*Kinne, O., 1964. The Effects of Temperature and Salinity on Marine and Brackish Water Animals. II. Salinity and Temperature Salinity Combinations. Oceanogr. and Mar. Biol. Ann. Rev. 2: 281-339.
- \*Lauff, George H. (Ed.), 1967. Estuaries, Publ. No. 83. Am. Assoc. Adv. Sci., Washington, D. A. 757 pp.
- Loosanoff, V. L. and F. D. Tommers, 1948. Effect of suspended silt and other substrates on rate of feeding of oysters. Science 107: 69-70.
- Lyman, T. and A. A. Reed. Report of the Commissioners Senate, Massachusetts Doc. No. 8, December 1865 (1966). pp. 3-41.
- Mathieson, A. C., E. Hehre, and N. B. Reynolds. <u>In Press</u>. Investigations of New England Marine Algae. I. A floristic and descriptive ecological study of the marine algae of Jaffrey Point, New Hampshire. Nova Hedwigia.
- , N. B. Reynolds, and E. Hehre. <u>In Press</u>. Investigations of New England Marine Algae. II. <u>Distribution of benthonic marine algae in the Great Bay Estuary System.</u>
  Nova Hedwigia.
- , and R. A. Fralick. <u>In Press</u>. Investigations of New England Marine Algae. V. The algal vegetation of the Hampton-Seabrook Estuary and the open coast near Hampton, New Hampshire. Rhodora.
- Minor, R. W., 1950. Field Book of Seashore Life. G. P. Putnam's Sons, New York. 888 pp.
- \*Moul, Edwin T., 1970. Higher plants of the marine fringe of southern New England. (Reprint) Systematics Ecology Progarm, Mar. Biol. Lab., Woods Hole, Mass. 56 pp.
- Newcombe, C. L., 1935. Growth of Mya arenaria (L.) in the Bay of Fundy Region. Canad. J. Res., 13: 97-137.

#### VIII-6.

- Nichol, E. A. T., 1965. The ecology of a salt marsh. J. Mar. Biol. Assoc., U. K., 20: 203-261.
- Nichols, P. R., R. V. Miller, J. E. Sykes, and I. M. Alperin, 1966. Striped Bass. Mar. Res. of the Atl. Coast. Leaflet No. 8, October 1966. Atl. States Mar. Fish. Comm.
- Norcross, J. J., W. H. Massmann, and E. B. Joseph, 1961. Investigations of inner continental shelf waters off Lower Chesapeake
  Bay. Part II. Sand Lance Larvae, Ammodytes americanus. Ches.
  Sci. II: 49-59.
- Odum, E. P., 1959. <u>Fundamentals of Ecology</u>. W. S. Saunders Co., Phil., Pa. pp. **54**6.
- Ohshima, Y., 1950. Biological notes on the sand eel, Ammodytes personatus. Gerard. Bull. Jap. Soc. Sci. Fish. 16(3): 99-107.
- Oldaker, Warren H., 1966. Report on pollution of the Merrimack River and certain tributaries. Part III. Stream Studies Biological. U. S. Dept. of the Intr., FWPCA, Northeast Region. 38 pp. plus Appendix.
- Orton, J. H., 1920. Sea temperature, breeding, and distribution of marine animals. Jour. Mar. Biol. Assoc. 12: 339-366.
- \*Owen, W., 1969. The Physical Hydrography of the Patuxent River Estuary Tech. Rpt. 53, Chesapeake Bay Institute, The Johns Hopkins Univ.
- Parke, M. and P. S. Dixon, 1968. Check-list of marine algae. Sec. Rev., Jr. Mar. Biol. Assoc., U. K. 48: 783-832.
- Patrick, R., 1949. A proposed biological measure of stream conditions, based on a survey of the Conestoga Basion, Lancaster County, Pa. Proc. Acad. Natl. Soc., Phila., Pa. 101: 277-341.
- \*Pennak, R. W., 1953. Freshwater Invertebrates of the United States.

  The Ronald Press Company, New York. 769 pp.
- Pftizenmeyer, Hayes T. and Carl N. Shuster, Jr., 1960. A partial bibliography of the soft-shell clam, Mya arenaria (L.). Maryland Depart. of Res. and Ed. and the Univ. of Delaware. January 1960. 29 pp.
- Pftizenmeyer, H. T., 1965. Annual cycle of gametogensis of the soft-shell clam, Mya arenaria, at Solomons, Maryland. Ches. Sci. 6: 52-59.

- Potts, W. T. W. and G. Parry, 1963. Osmotic and Ionic Regulation in Animals. Pergamon Press, London.
- Pritchard, D. W., 1959. Computation of the Longitudinal Salinity Distribution in the Delaware Estuary for Various Degrees of River Inflow Regulation: Chesapeake Bay Inst. Tech. Rept. XVIII, 72 pp.
- Pritchard, D. W., 1968. Lectures on Estuarine Oceanography delivered at the John Hopkins University (class notes, unpublished manuscript).
- \*Prosser, C. L. and F. A. Brown, Jr., 1961. Comparative Animal Physiology. W. B. Saunders Company. Phila., Pa. 688 pp.
- \*Reid, G. K., 1961. Ecology of inland waterways and estuaries. New York. Reinhold Company. 375 pp.
- Richards, S. W., A. Perlmutter, and D. C. McAveny, 1963. A taxonomic study of the genus <u>Ammodytes</u> from the East Coast of N. America. Copeia (2): 358-377.
- Ropes, J. L., 1968. Feeding Habits of Green Crab in Cape Code Area. Fish. Bull. 67:2
- Scattergood, Leslie W., 1952. The distribution of the Green crab,

  <u>Carcinides maenas</u> (L.), in the Northwestern Atlantic. Bull.

  of Dept. of Sea and Shore Dish. (Maine), Fish. Cir. No. 8,

  October 1952.
- \*Shuster, C. N., 1952. III. Observations on the natural history of the American horseshoe crab, <u>Limulus polyphemus</u>. 3rd Rept. on investigations of methods of improving the shellfish resources of Mass. Woods Hole Oceanogr. Inst. Co. Repr. 1951. Contr. 564: 18-23.
- Southward, A. J., 1965. Life on the Sea Shore. Harvard Univ. Press, Cambridge, Mass. 153 pp.
- Stevenson, Charles H., 1899. The shad fisheries of the Atlantic coast of the United States. Rept. U. S. Comm. and Fish. for 1898. pp. 101-269.
- Swan, E. F., 1952. The Growth of the clam, Mya arenaria, as affected by the substrate. Ecol. 33: 530-534.
- \*Taylor, W. R., 1957. Marine algae of the northeastern coast of North American. VIII, plus 509 pp., Univ. Michigan Press, Ann Arbor.

#### VIII-8.

- \*Walburg, C. H., 1960. Abundance and life history of the shad, St. Johns River, Florida. U. S. Fish & Wildl. Serv., Fish. Bull. 60(177): 487-501.
- , and P. R. Nichols, 1967. Biology and management of the American shad and status of the fisheries, Atlantic coast of the United States, 1960. U. S. Fish and Wildl. Ser., Spec. Sci. Rpt. Fisheries No. 550. IV + 105 pp.
- Watson, Jay F., 1970. Distribution and population dynamics of American shad, <u>Alosa sapidissima</u> (Wilson), in the Connecticut River above Holyoke Dam, Massachusetts. (Unpublished Dissertation), University of Massachusetts.

<sup>\*</sup>Indicates reference used but not cited in report.



APPENDIX A

HIGH TIDE SALINITY DISTRIBUTIONS

××1 1×11 ×××× 1×1×

#### REFERENCE

### SALINITY STUDY, MERRIMACK RIVER ESTUARY MATHEMATICAL STUDY

### DIVERSION INDEX

(Cubic Feet per Second) DIVERSION 100 200 300 500 600 800 1000 1100 1500 1900 2000 2800 5200 8000 FLOW 18. cfs

<sup>\*</sup>All blank table entries refer to Figure 1 of Appendices A and B for high and low tides, respectively. Figures 1 (A & B) represent the minimum control flow established by the Corps of Engineers.

### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 800. CFS

### DISTRIBUTION AT HIGH TIDE SALINITY




FIGURE A-1.

OI 1 MOOHHOOG

### DISTRIBUTION AT HIGH TIDE SALINITY




FIGURE A-2.

### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 900. CFS

### DISTRIBUTION AT HIGH TIDE SALINITY




FIGURE A-3.

### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 950. CFS

### DISTRIBUTION AT HIGH TIDE SALINITY




FIGURE A-4.

### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 1000. CFS

# DISTRIBUTION AT HIGH TIDE SALINITY




FIGURE A-5.

### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 1100. CFS

### DISTRIBUTION AT HIGH TIDE SALINITY




FIGURE A-6.

### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 1200. CFS

### DISTRIBUTION AT HIGH TIDE SALINITY




FIGURE A-7.

### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 1300. CFS

### DISTRIBUTION AT HIGH TIDE




FIGURE A-8.

### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 1400. CFS

# DISTRIBUTION AT HIGH TIDE SALINITY




FIGURE A-9.

### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 1500. CFS

### DISTRIBUTION AT HIGH TIDE SALINITY




FIGURE A-10.

### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 1600. CFS

# DISTRIBUTION AT HIGH TIDE SALINITY




FIGURE A-11.

#### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 1700. CFS

# DISTRIBUTION AT HIGH TIDE SALINITY




FIGURE A-12.

### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 1800. CFS

### DISTRIBUTION AT HIGH TIDE SALINITY




FIGURE A-13.

#### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 1900. CFS

## DISTRIBUTION AT HIGH TIDE SALINITY




FIGURE A-14.

#### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 2000. CFS

# DISTRIBUTION AT HIGH TIDE SALINITY




FIGURE A-15.

#### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 3000. CFS

## DISTRIBUTION AT HIGH TIDE SALINITY




FIGURE A-16.

#### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 4000. CFS

## DISTRIBUTION AT HIGH TIDE SALINITY




FIGURE A-17.

#### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 5000. CFS

# DISTRIBUTION AT HIGH TIDE SALINITY




FIGURE A-18.

### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 6000. CFS

# DISTRIBUTION AT HIGH TIDE SALINITY




FIGURE A-19.

#### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 7000. CFS

## DISTRIBUTION AT HIGH TIDE SALINITY




FIGURE A-20.

#### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 8000. CFS

## DISTRIBUTION AT HIGH TIDE SALINITY




FIGURE A-21.

#### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 10000. CFS

## DISTRIBUTION AT HIGH TIDE SALINITY




FIGURE A-22.

### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 12000. CFS

# DISTRIBUTION AT HIGH TIDE SALINITY




FIGURE A-23.

#### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 14000. CFS

## DISTRIBUTION AT HIGH TIDE SALINITY




FIGURE A-24.

#### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 16000. CFS

# DISTRIBUTION AT HIGH TIDE SALINITY




FIGURE A-25.

#### APPENDIX B

LOW TIDE SALINITY DISTRIBUTIONS

#### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 800. CFS

## DISTRIBUTION AT LOW TIDE SALINITY




FIGURE B-1.

#### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 850. CFS

### DISTRIBUTION AT LOW TIDE




FIGURE B-2.

#### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 900. CFS

### DISTRIBUTION AT LOW TIDE SALINITY




FIGURE B-3.

### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 950. CFS

### DISTRIBUTION AT LOW TIDE




FIGURE B-4.

#### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 1000. CFS

## DISTRIBUTION AT LOW TIDE SALINITY




FIGURE B-5.

### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 1100. CFS

# DISTRIBUTION AT LOW TIDE SALINITY




FIGURE B-6.

#### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 1200. CFS

## DISTRIBUTION AT LOW TIDE SALINITY




FIGURE B-7.

### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 1300. CFS

### DISTRIBUTION AT LOW TIDE




FIGURE B-8.

#### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 1400. CFS

### DISTRIBUTION AT LOW TIDE




FIGURE B-9.

### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 1500. CFS

## DISTRIBUTION AT LOW TIDE SALINITY




FIGURE B-10.

### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 1600. CFS

# DISTRIBUTION AT LOW TIDE SALINITY




FIGURE B-11.

#### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 1700. CFS

## DISTRIBUTION AT LOW TIDE SALINITY




FIGURE B-12.

### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 1800. CFS

# DISTRIBUTION AT LOW TIDE SALINITY




FIGURE B-13.

#### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 1900. CFS

### DISTRIBUTION AT LOW TIDE




FIGURE B-14.

#### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 2000. CFS

### DISTRIBUTION AT LOW TIDE SALINITY




FIGURE B-15.

#### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 3000. CFS

## DISTRIBUTION AT LOW TIDE SALINITY




FIGURE B-16.

#### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 4000. CFS

## DISTRIBUTION AT LOW TIDE SALINITY




FIGURE B-17.

#### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 5000. CFS

### DISTRIBUTION AT LOW TIDE




FIGURE B-18.

#### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 6000. CFS

## DISTRIBUTION AT LOW TIDE SALINITY




FIGURE B-19.

#### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 7000. CFS

## DISTRIBUTION AT LOW TIDE SALINITY




FIGURE B-20.

#### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 8000. CFS

### DISTRIBUTION AT LOW TIDE SALINITY




FIGURE B-21.

#### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 10000. CFS

### DISTRIBUTION AT LOW TIDE




FIGURE B-22.

#### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 12000. CFS

## DISTRIBUTION AT LOW TIDE SALINITY




FIGURE B-23.

#### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 14000. CFS

# DISTRIBUTION AT LOW TIDE SALINITY




FIGURE B-24.

#### LONGITUDINAL SALINITY PLOT FOR MERRIMACK RIVER FLOW 16000. CFS

# DISTRIBUTION AT LOW TIDE SALINITY




FIGURE B-25.

#### APPENDIX C

AVERAGE WEEKLY FLOW RATES 1927-1967

ىرى ك

21

AVERAGE	WEEKLY	FLOW	RATES	CFS	1927
AVERAGE	MFFF	, <b>L</b> ON			

		1	2	3	4	5
1 2 3 4 5 6 7 8 9	4114 3507 3958 6111 6187 4890 4227 4430 5491 7035	23714 25057 12142 9957 8020 8611 10201 5985 6145 8057	7857 6705 5021 3810 2462 2443 2215 2840 4128 3001	3375 2961 2525 2600 6655 8000 4180 3740 2925 3065	4305 8035 7984 8202 32767 11357 15485 13314 13871 18414	13542 8428
	AVERAGE WEE	KLY FLOW R	ATES CFS	1928		
		1	2	3	4	5
1 2 3 4 5 6 7 8 9 10	9628 8385 6972 9345 7284 6838 10454 9782 8294 5394	7612 8270 14428 12542 21128 12200 15814 22657 14557 8690	14900 15142 12157 12171 7934 7565 9802 4935 5308 5870	7167 7325 5104 3781 9065 7215 5244 5874 4824 3697	2987 3130 4120 3588 3597 3310 4231 3194 4087 3577	4610 4131
	AVERAGE WEE	KLY FLOW F	RATES CFS	1929		
		1	2	3	4	5
1 2 3 4 5 6 7 8 9 10	4920 6310 6790 7034 4457 8415 6021 4515 5055	19028 25242 19842 16757 17928 20857 23742 26142 18814 15657	13528 7860 4695 3857 3855 4884 3301 2604 2175 1939	1700 1583 2064 1698 1402 1535 2018 1787 1248 1647	1531 1384 2300 1822 1678 2294 3380 2000 1672 1538	2781 2477

		1	2	3	4	5
1 2 3 4 5 6 7 8 9	2715 6611 5058 3465 2684 2697 3115 6890 9650 11337	11845 8527 16914 11497 14842 9630 6954 6794 6508 4945	5375 5954 3652 7117 6224 3607 2652 2313 2197 1938	2005 1748 3072 2697 1891 1832 1685 1440 1220 1079	1101 1164 1625 1944 1935 2407 4981 3268 3307 2395	1789 1955
	AVERAGE WEEK	(LY FLOW R	ATES CFS	1931		
		1	2	3	4	5
1 2 3 4 5 6 7 8 9 10	1890 1991 1807 1666 1661 1570 2134 2540 2994 4330	5684 7760 18171 22185 24457 13200 11287 8670 8804 10322	10752 7812 8868 19128 10410 4962 2891 3617 2750 4668	2318 1889 3252 2087 2174 2066 1891 1584 2708 2115	1520 2177 2077 3641 2412 2678 3435 2462 2318 2992	4404 9370
	AVERAGE WEEK	LY FLOW R	ATES CFS	1932		
		1	2	3	4	5
1 2 3 4 5 6 7 8 9	4340 9065 13542 8977 8894 6507 7440 5640 5108 8605	6184 4954 8710 25742 31642 20228 14514 12300 8147 5812	4112 4042 3034 2432 1891 1708 2064 3427 2522 1992	1642 2612 2297 2072 1556 1426 1421 7481 3117 2831	6195 4940 10175 7712 8654 14628 16142 8540 6544 5355	4261 5904

		1	2	3	4	5
1 2 3 4 5 6 7 8 9	5975 5552 6065 8855 6298 5990 5687 7350 7064 11877	12185 13385 14742 32767 29957 32767 27657 20185 11985 9260	7318 6098 4960 3440 3094 2802 1915 1869 1746 1693	1715 1666 1727 2592 3288 2207 2494 7514 4355 3734	5770 4430 5647 5535 3992 3878 3594 4874 5798 3828	3532 3455
	AVERAGE WEE	KLY FLOW R	ATLS CFS	1934		
		1	2	3	4	5
1 2 3 4 5 6 7 8 9	4251 5901 5168 6070 5950 4105 3608 3265 3720 13771	9207 10948 15597 32271 32767 31300 20328 15200 14342 9148	6435 4274 3964 3707 5554 3407 1909 1797 1431 1783	2660 1827 1446 1400 1486 1511 2950 7367 3761 4855	4415 3718 3825 4192 7445 5372 5361 7068 10620 4188	4834 4674
	AVERAGE WEE	KLY FLOW R	ATES CFS	1935		
		1	2	3	4	5
1 2 3 4 5 6 7 8 9	3958 21524 10268 8735 7597 6520 6937 7764 8678 10907	15328 17328 14942 11644 15537 18542 14814 12482 12337 7745	5007 5127 6184 11114 14492 9331 4962 7751 4034 3274	2637 2481 2320 1855 1681 2862 3601 2890 2207 2465	1984 1725 1650 1883 2003 3672 3438 6902 4757 4191	3728 2520

		1	2	3	4	5
1 2 3 4 5 6 7 9 10	4537 5531 9211 6845 5264 4494 4021 4878 4897 5241	32767 32767 32767 28000 28171 18242 11725 11722 9150 7807	5614 3932 3051 2862 3624 2442 1794 2258 2041 1939	1795 1634 1691 1560 1664 2224 1744 1753 1591 1862	2003 4957 4850 4092 5580 3852 2614 2091 3354 12262	15488 12950
	AVERAGE WEE	KLY FLOW R	ATES CFS	1937		
		1	2	3	4	5
1 2 3 4 5 6 7 8 9	11325 10558 13318 13357 8342 6454 11545 15447 9638 6100	7068 12600 8404 10954 16271 20385 20757 21871 17414 25514	19400 13385 9681 6638 8685 7618 6090 3632 3285 2478	2478 2830 2845 2257 2397 2181 2571 2362 2092 2000	1601 2545 7434 4860 3101 15075 8634 18178 16681 11085	9607 7211
	AVERAGE WEE	KLY FLOW R	ATES CFS	1938		
		1	2	3	4	5
1 2 3 4 5 6 7 8 9	5690 7985 5727 15192 14500 14000 10814 8385 6940 7438	6955 16190 16128 11387 11591 19314 11002 7782 5342 10041	8447 5602 4300 6415 4451 5922 5548 3938 6442 14314	19928 7832 5724 4874 3915 3425 3775 32767 32767	6667 5231 9440 7674 5604 5327 8165 7067 19371 25257	11135 7892

		1	2	3	4	5
1 2 3 4 5 6 7 8 9 10	7314 11251 7144 5097 4832 4924 5534 7730 10090 11732	8840 8737 13528 19671 20371 32400 32767 20685 15771 8260	8605 7084 4402 3832 3751 3621 3427 2192 1919 1749	2325 2121 2043 2480 2234 1732 1971 1816 1434 1876	1721 1522 1574 5002 4687 3148 2307 1888 4511 2885	3205 2822
	AVERAGE WEEK	KLY FLOW R	ATES CFS	1940		
		1	2	3	4	5
1 2 3 4 5 6 7 8 9 10	1892 1763 3454 2325 1842 1921 3008 2571 2511 2947	3584 5315 5580 21685 32767 31642 27185 31200 26757 12671	11014 16185 17324 9144 6404 4655 4505 4402 3454 3620	3344 2527 1837 1785 1954 3634 2882 2437 2938 2400	1993 1763 1543 1954 5298 8795 7041 4071 3544 3888	5608 5162
	AVERAGE WEE	KLY FLOW R	ATES CFS	1941		
		1	2	3	4	5
1 2 3 4 5 6 7 8 9	10091 5757 4627 4504 4221 9311 10680 6905 5428 5177	5197 5264 8707 10858 12771 11757 6187 4651 5471 4354	2775 2820 2402 1989 3285 1754 1482 3073 3122 2147	2308 1389 1236 1386 1212 1408 1356 1200 1030 1110	1738 1891 1435 2542 3265 2356 1693 1711 1586 1898	2300 4455

C++++++

		1	2	3	4	5
1 2 3 4 5 6 7 8 9 10	4242 2340 3025 4340 2997 2670 2650 3107 3201 12437	16557 20114 14000 14914 17271 16457 12471 8590 6670 5617	6582 4342 3268 10321 10490 4197 4101 3850 2478 2315	4254 2570 2852 2204 1732 1566 2231 2013 2278 2365	2133 1696 2873 4184 4697 4291 5158 9521 12522 6064	4337 3610
	AVERAGE WEE	KLY FLOW R	ATES CFS	1943		
		1	2	3	4	5
1 2 3 4 5 6 7 8 9 10	9015 5000 4360 3894 3651 4324 5034 6788 10345 6557	12584 14628 18000 11514 10211 13914 18185 20328 18400 20128	16757 12088 6947 6241 5732 3784 3195 3032 2219 2697	3640 5940 6572 4168 2679 2994 3315 2285 1704 2172	1634 4832 4264 6242 9477 12540 7547 8151 5592 4808	3634 3064
	AVERAGE WEE	KLY FLOW R	RATES CFS	1944		
		1	2	3	4	5
1 2 3 4 5 6 7 8 9 10	2697 2705 2427 2867 3061 2540 2615 3782 3881 3587	5011 7510 15191 14371 18971 20200 21685 17528 14442 8530	5962 4435 2758 3155 5717 29471 7617 4772 3795 2652	2906 1983 1759 1630 1671 1748 2389 8914 2978 3202	3049 2990 4492 2893 2692 4381 3468 4602 7572 8834	5545 4392

		1	2	3	4	5
1 2 3 4 5 6 7 8 9 10	10342 6521 5775 5364 4928 5098 5220 6227 10467 14471	15414 31471 27314 21828 13661 8242 13258 15614 16514 27828	19300 11840 8335 7715 16614 13127 6625 4598 7558 5820	6292 4074 3041 2511 2585 3086 2277 3210 2805 5755	4501 3684 3358 3125 3984 3944 10700 7342 13512 14900	6581 6950
	AVERAGE WEE	KLY FLOW R	ATES CFS	1946	4	5
1 2 3 4 5 6 7 8 9	7760 14085 8105 6380 6305 6311 8234 7695 6535 19615	27257 19828 16985 13628 9220 6770 9020 8771 9805 13428	12200 16528 13514 8634 5007 3150 2908 2478 2141 3252	4401 4304 4194 3727 3491 3037 3152 2195 3074 10074	3865 4184 3777 3520 3894 4842 3794 3990 3500 4584	3702 4160

	AVERAGE WE	EKLY FLOW F	RATES CFS	1947		
		1	2	3	4	5
1 2 3 4 5 6 7 8 9	3981 3652 4268 6550 8804 12355 7528 6457 6684 9098	15417 13914 14957 16257 23671 17428 13185 17000 18814 10870	9665 9671 14228 11071 8394 6124 3248 3098 3365 6715	3584 2547 2522 2484 2196 2902 2158 2272 1977 1531	1242 1103 1134 1102 2089 7515 3330 4321 2672 2411	3025 2375
	AVERAGE WEE	EKLY FLOW F	RATES CFS	1948		
		1	2	3	4	5
1 2 3 4 5 6 7 8 9	2251 2484 2325 2175 2280 2245 2827 5708 4597 3808	4342 30057 29514 20285 12157 13957 10451 7904 10577 15214	20114 16485 11418 13028 9341 6938 5197 6082 3498 3238	3185 2307 2652 2105 1748 1502 1529 1390 1079 1137	1618 1256 1524 1298 2423 4148 6217 5651 3631 3124	2805 1992
	AVERAGE WEE	EKLY FLOW R	ATES CFS	1949		
		1	2	3	4	5
1 2 3 4 5 6 7 8	16142 13648 5828 4910 4681 4557 7348 10538	7940 7404 16685 10860 11200 12700 11645 9822	5295 6748 3707 2432 2059 2205 1431 1816	1313 1301 1270 1406 2156 1278 1486 1754	1761 1674 1574 2526 3095 3055 2601 2962	3512 4698

		1	2	3	4	5
1 2 3 4 5 6 7 8 9 10	4600 6494 7461 5341 6920 5364 6312 4992 4317 4881	6694 7761 19485 22685 14314 16500 20185 12000 8495 6157	5472 5375 8831 4112 2921 1966 1417 1920 1395 1331	1088 1125 1160 1650 1762 2728 1687 1401 1214 1207	1994 2808 2016 2035 3730 2231 3338 19458 13401 15654	6862 4754
	AVERAGE WEE	EKLY FLOW R	ATES CFS	1951		
		1	2	3	4	5
1 2 3 4 5 6 7 8 9	6034 6152 6702 9005 7284 14814 12885 18071 11857 10668	13187 18142 18628 32767 28814 19171 17542 12742 7758 7314	6400 11828 6242 5114 5148 4344 3864 4144 5398 4481	6264 3892 4347 5557 4400 5780 4232 3974 3515 3247	7494 4981 5685 11105 27528 14714 10552 9058 11080 10648	8875 11308
	AVERAGE WE	EKLY FLOW R	ATES CFS	1952		
		1	2	3	4	5
1 2 3 4 5 6 7 8 9	13042 10577 11942 15857 16971 17342 10765 9645 8318 8464	14314 12714 16457 28328 32767 29028 20257 18357 9964 17257	12771 14500 23471 9412 4630 3665 2644 2675 2464 1943	1819 2005 3261 2900 1762 2672 1643 1895 1914 2735	2571 1848 1854 1482 1476 1451 2562 3740 3292 13841	8297 5720

				_		
		1	2	3	4	5
1 2 3 4 5 6 7 8 9 10	5002 4498 5768 13472 14128 12145 13090 16000 11747 10527	28502 24885 32767 32767 23785 27528 19114 22100 18500 18428	13800 8075 4610 2922 2312 1927 1555 1572 1815 1770	1470 2827 2418 1505 1473 1101 1314 1383 1400 1317	1325 1461 1863 4124 2307 2340 2750 8335 8738 13557	8634 650 <b>5</b>
	AVERAGE WEE	KLY FLOW	RATES CFS	1954		
		1	2	3	4	5
1 2 3 4 5 6 7 8 9 10	4811 4162 3957 5160 5978 5367 4624 11652 15285 14785	7801 10285 10517 7840 12414 26428 19928 17342 31828 29528	24542 15414 14657 9418 6542 5208 5934 3542 2314 2437	3448 3161 2700 2158 5261 6621 24555 16842 9998 6447	5341 8127 5644 8008 13515 7562 15668 14628 10982 11215	21257 13257
	AVERAGE WEE	KLY FLOW	RATES CFS	1955		
		1	2	3	4	5
1 2 3 4 5 6 7 8 9	13314 9638 7092 5808 4735 5765 8877 8107 12457 9495	14328 10957 10688 16471 17428 19071 16957 15142 9744 6288	4255 8051 7400 6818 4771 4534 2712 2512 1936 1835	1527 1467 5454 9985 6642 4484 3302 2551 2634 2569	4000 15012 8420 10525 18757 14871 11375 7641 6508 5422	4324 2914

		1	2	3	4	5
1 2 3 4 5 6 7 8 9 10	2264 24004 19328 8221 6620 7204 8208 7005 7432 9015	8101 7787 7108 11061 22542 32767 26857 32767 19300 12771	8517 13288 14857 7611 3740 2870 2150 4104 6275 3058	2221 1866 1729 1590 1502 2288 2238 2962 4818 2967	4080 2844 2788 2598 3028 2529 4250 5572 3448 6537	7802 7095
	AVERAGE WEEK	KLY FLOW R	ATES CFS	1957		
		1	2	3	4	5
1 2 3 4 5 6 7 8 9 10	5187 5270 4730 11598 8395 6591 5355 3984 9698 7795	9822 10392 8575 10842 11571 8185 7752 5000 3484 4895	6042 4120 3122 2216 1685 2218 2627 2415 1486 1231	1407 1249 1258 1062 876 789 827 988 1077 823	1159 1142 1957 2307 4785 4585 5780 3934 4042 12114	13385 18900
	AVERAGE WEE	KLY FLOW F	RATES CFS	1958		
		1	2	3	4	5
1 2 3 4 5 6 7 8 9	9751 6900 6948 15971 19128 11197 8577 7494 9205	13357 11785 15400 23628 24257 29557 29114 24800 19928 14171	9182 6664 6531 4187 2828 2292 1650 2935 2554 2195	3340 2176 1936 1772 1777 1533 1448 2158 2774 2698	2322 1733 3125 4197 3892 4064 3477 5335 6354 4560	356 <b>5</b> 2684

		1	2	3	4	5
1 2 3 4 5 6 7 8 9	2798 2424 2834 8470 4972 5377 4190 4270 3674 9311	6817 13127 13442 32767 27428 16471 11240 10211 6828 5757	4405 3034 3200 2733 5550 4047 2720 2412 3555 4460	2662 1887 2158 1371 2444 4297 1998 1965 1680 1887	4831 2785 14432 13635 9558 9238 8352 22514 13828 18071	12657 7915
	AVERAGE WEE	KLY FLOW R	ATES CFS	1960		
		1	2	3	4	5
1 2 3 4 5 6 7 8 9	12080 9800 7500 6692 6478 8090 12771 11171 9098 7888	6991 7171 7670 32767 32767 29857 20014 15385 11645 17928	12347 11821 9757 5621 7102 3991 2957 2370 2795 2290	3130 2565 2577 2145 1675 1464 9129 7998 5557 4557	3151 3015 8378 9494 9160 6361 5084 5557 7387 4488	5385 4742
	AVERAGE WEE	KLY FLOW R	ATES CFS	1961		
		1	2	3	4	5
1 2 3 4 5 6 7 8 9	4200 3771 3550 3227 3142 3131 3391 5560 13712 13328	10154 8377 15737 18642 18071 24785 25214 19000 13757 11424	7608 9011 5422 6394 4284 3895 2590 2661 3110 2942	2661 1774 1551 1471 2428 1828 1742 3057 3848 2764	2348 2610 2271 1741 3027 3247 3827 5797 4461 3822	3258 3041

		1	2	3	4	5
1 2 3 4 5 6 7 8 9 10	3551 5651 5658 5357 4344 3797 2987 3148 3635 3925	6561 9188 19785 32767 30400 14742 11132 15142 10482 6970	8302 6382 5161 3847 2087 2281 1481 1552 1672 2168	1789 2284 2474 1962 1705 1634 1486 1814 1897 5831	21242 7428 5347 8814 9907 13545 9420 8417 15201 13697	7588 6372
	AVERAGE WEE	KLY FLOW R	ATES CFS	1963		
		1	2	3	4	5
1 2 3 4 5 6 7 8 9 10	5718 5701 5485 5944 5141 5241 4681 4685 4361 5510	7012 9154 25657 30828 17285 14771 12568 11848 9680 8575	9292 4832 2831 2411 2451 1643 1315 1527 1377 1304	1173 1142 1376 1302 1281 1588 1022 1109 1106 1599	1213 1056 1153 1556 9458 7677 5038 6872 7120 9261	5290 4482
	AVERAGE WEE	KLY FLOW R	ATES CFS	1964		
		1	2	3	4	5
1 2 3 4 5 6 7 8 9	4062 3880 3884 16928 12380 9011 6784 6072 5572 15092	15971 11465 12214 11071 17685 27957 16857 10341 7024 6927	5592 3038 2091 1941 1654 1353 1492 1528 1500 1427	1145 953 993 1144 1726 920 1181 1011 1006 930	860 800 1475 1188 1129 1180 1316 4420 2385 1940	1870 3653

		1	2	3	4	5
1 2 3 4 5 6 7 8 9 10	3935 2942 1981 1761 1604 2829 4090 2860 5482 8378	6440 4481 4181 3745 8204 14057 9735 8100 5948 4645	3560 2300 2255 2707 2301 1564 1092 1421 1168 1022	899 723 944 995 932 1692 1126 1035 1684 2110	2435 2288 2191 1770 1471 2414 3720 3682 2897 2150	2092 2495
	AVERAGE WEE	KLY FLOW R	ATES CFS	1966		
		1	2	3	4	5
1 2 3 4 5 6 7 8 9 10	3487 2541 2285 2350 2224 2218 5997 5264 5820 10597	7890 11017 16828 9568 8888 9074 9705 8338 7697 8962	9041 5270 3405 5335 3552 2103 975 1424 1355 1119	1083 967 1079 1837 1729 2237 1566 1418 2524 2101	1794 2705 5677 4322 11298 6921 4594 4738 4568 5751	4441 3511
	AVERAGE WEE	KLY FLOW R	ATES CFS	1967		
		1	2	. 3	-4	5
1 2 3 4 5 6 7 8 9	4194 3738 3314 4058 5112 4070 3555 3525 3171 3198	6140 5768 8815 28728 22685 24471 20500 15757 17042 16685	12971 15057 7334 6177 6917 6952 5898 4241 3802 3621	3724 3590 2775 2598 2507 1732 1938 1469 1573 3275	2424 2504 3165 3181 3678 3010 3874 5132 5651 9494	7624 5692